CLAYTON COUNTY WATER AUTHORITY

Request for Bid

FLINT RIVER OUTFALL REPLACEMENT – PHASE 2

Bid Opening:

Thursday, August 24, 2017 at 10:00 a.m. (local time) 1600 Battle Creek Road, Morrow, Georgia 30260

ADDENDUM #2

Dated: August 21, 2017

Acknowledgment of receipt of this addendum **MUST BE SIGNED AND INCLUDED IN** YOUR RESPONSE TO THE RFB.

QUESTION:

1. In response to Question #5 (of Addendum 1), it was pointed out that the carrier pipe for the steel casing per the Williams Developers' Handbook, that the pipe would remain FRPMP. Drawing #P-1 also shows that the clearance between the 48" FRPMP and the bottom of the existing 36" Gas Main is only 1.8'. Per the Williams Developers' Handbook, they will not allow machine excavation of pipelines or related facilities within 24" of Williams' pipelines. Since this designed clearance of the carrier pipe, much less the greater diameter casing, is already contradicting the clearance that Williams will allow, can the 48" FRPMP be re-profiled to allow a minimum 2' clearance from the steel casing?

<u>Answer</u>: CCWA has permitted the project with Williams Transcontinental Gas Pipe Line Company, LLC (Williams) as shown on Addendum Drawing # P-1. Williams is allowing FRPMP to be installed across the natural gas right-of-way. Steel Casing is not shown on Drawing # P-1; Williams is not requiring steel casing to be installed across the natural gas right-of-way. CCWA does not desire to change the slope of the pipe that crosses the natural gas right-of-way.

SIGNATURE

COMPANY NAME

DATE