



Know what's below.  
Call before you dig.


CRESTVIEW MAINSTREET PROJECT  
CITY OF CRESTVIEW  
SUMMARY OF APPROXIMATE QUANTITIES  
BASE BID - SCHEDULE A

ITEM NO.	ITEM DESCRIPTION	UNITS	Quantity		TOTAL		DESIGN NOTES
			PH 1	PH 2	P	F	
0101-1	MOBILIZATION	LS	0.5	0.5	1.0		
0102-1	MAINTENANCE OF TRAFFIC	DA	100.0	150.0	250.0		
0104-10-3	SEDIMENT BARRIER	LF	300.0	344.0	644.0		
0104-18	INLET PROTECTION SYSTEM	EA	24.0	28.0	52.0		
0104-15	SOIL TRACKING PREVENTION DEVICE	EA	2.0	3.0	5.0		
0110-1-A	CLEARING AND GRUBBING	AC	0.8	0.5	1.3		
0110-4	REMOVAL OF EXISTING CONCRETE PAVEMENT	SY	1181.4	589.1	1770.6		Includes brick crosswalk pavers
0110-4-3	REMOVAL OF EXISTING CONCRETE, CONCRETE SIDEWALKS AND DRIVEWAYS	SY	563.1	2789.4	3352.6		
0110-4-5	REMOVAL OF EXISTING CONCRETE, CURB ELEMENTS	SY	850.0	1186.7	2036.6		
110-21	TREE PROTECTION BARRIER	LF	400.0	520.0	920.0		
110-23	TREE REMOVAL	EA	21.0	35.0	56.0		
120-1	EXCAVATION	CY	1218.0	1826.0	3044.0		Includes 9,166 CY cut for roadway with 6,122 reused for fill material. RE Geotech
120-6	EMBANKMENT	CY	0.0	0.0	0.0		
285706	OPTIONAL BASE, BASE GROUP 06	SY	5550.0	8325.0	13875.0		8" base defined in geotechnical report.
E110-70	REMOVAL OF FLEXIBLE PAVEMENT	SY	8762.9	11787.0	20549.9		Complete in place removal of asphalt pavement
0327-70-14	MILLING EXISTING ASPHALT PAVEMENT, 6 1/2" AVG DEPTH	SY	0.0	0.0	0.0		
0327-70-3	MILLING EXISTING ASPHALT PAVEMENT, 4 1/2" AVG DEPTH	SY	0.0	0.0	0.0		
0337-7-8x	ASPHALT PAVEMENT	TN	3976.1	3157.7	7133.8		
0350-3-5	PLAIN CEMENT CONCRETE PAVEMENT 8" THICK	SY	6.0	13.0	19.0		
0425-11	MODIFY EXISTING DRAINAGE STRUCTURE	EA	0.0	0.0	0.0		
0425-1361	INLET CURB, TYPE P-6	EA	0.0	0.0	0.0		
0425-1441	INLET CURB, TYPE J-4	EA	9.0	6.0	15.0		
0425-1421	INLET CURB, TYPE J-2	EA	0.0	0.0	0.0		
0425-2-91	MANHOLES, J-8	EA	0.0	0.0	0.0		
0425-2-71	MANHOLES, J-7	EA	0.0	4.0	4.0		
0425-2-61	MANHOLES, P-8	EA	6.0	0.0	6.0		
0425-2-41	MANHOLES, P-7	EA	0.0	0.0	0.0		
0425-4	INLETS, ADJUST	EA	0.0	0.0	0.0		
0425-5	MANHOLES, ADJUST	EA	0.0	2.0	2.0		
0425-6	VALVE BOXES, ADJUST	EA	10.0	15.0	25.0		
0425-8	DRAINAGE STRUCTURES, MISCELLANEOUS, ADJUST	EA	0.0	0.0	0.0		
0430-030	CONCRETE END WALL	EA	1.0	0.0	1.0		
0520-1-10	CONCRETE CURB & GUTTER, TYPE F	LF	3538.0	4067.0	7605.0		
0520-002	CONCRETE DRAINAGE PAN	SY	92.2	0.0	92.2		
0522-1	CONCRETE SIDEWALK AND DRIVEWAY 4" THICK	SY	1975.0	3048.0	5023.0		Includes curb ramps and building entrance ramps
0522-2	CONCRETE SIDEWALK AND DRIVEWAY 6" THICK	SY	464.1	669.0	1133.1		Includes curb ramps and building entrance ramps
0523-1	STAMPED, COLORED CONCRETE CROSSWALK 7" THICK	SY	162.0	130.0	292.0		
0526-1-2	PAVERS, ARCHITECTURAL, SIDEWALK (BRICK)	SY	286.0	502.6	788.6		includes pavers, sand setting bed, aggregate, filter fabric
0527-2	DETECTABLE WARNINGS	SF	204.0	204.0	408.0		
0575-1-7	TURF (INCL. FINE GRADING)	SF	15409.0	17480.0	32889.0		
0575-2	PLANTER BACKFILL MIX	CY	144.0	435.0	579.0		
0575-2	TOPSOIL IMPORT FOR TURF AREAS, 6" DEPTH (INCL. AMENDMENTS AS NEEDED)	SF	15409.0	17480.0	32889.0		
0580-1-73	ROCK MULCH, 4" DEPTH	SY	211.0	138.0	349.0		
0580-4-2	LANDSCAPE TREES - DECIDUOUS TREES (2-INCH CALIPER)	EA	16.0	31.0	47.0		
0580-4-2	LANDSCAPE TREES - ORNAMENTAL (2-INCH CALIPER)	EA	4.0	12.0	16.0		
0580-4-2	LANDSCAPE - SHRUBS - 5 GALLON	EA	0.0	70.0	70.0		
0580-4-2	LANDSCAPE - SHRUBS - 1 GALLON	EA	96.0	276.0	372.0		
0580-7-21	LANDSCAPE - GROUNDCOVERS - 1 GALLON	EA	229.0	111.0	340.0		
0580-7-41	LANDSCAPE - ORNAMENTAL GRASSES - 1 GALLON	EA	32.0	142.0	174.0		
0580-13-1	TREE GUARD	LF	320.0	620.0	940.0		
0580-13-2	FILTER FABRIC (IN TREE WELLS & RAISED PLANTERS)	SF	1130.0	2738.0	3868.0		
0590-1	LANDSCAPE IRRIGATION SYSTEM	LS	1.0	1.0	2.0		
0635-1-11	PULL & JUNCTION BOX, F&I, PULL BOX	EA	4.0	0.0	4.0		
0639-2-1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	5540.0	0.0	5540.0		
0639-1111	ELECTRICAL POWER SERVICE, F&I, OVERHEAD, METER FURNISHED BY CONTRACTOR	AS	2.0	0.0	2.0		
0676-3100	100A 18-CKT PANEL NEMA 3R	EA	2.0	0.0	2.0		
0700-1-11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	26.0	22.0	48.0		
0700-1-12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	0.0	0.0	0.0		
0700-1-13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	0.0	0.0	0.0		
0700-1-14	SINGLE POST SIGN, F&I GROUND MOUNT, 31+ SF	AS	0.0	0.0	0.0		
0700-1-50	SINGLE POST SIGN, RELOCATE	AS	0.0	0.0	0.0		
0700-1-60	SINGLE POST SIGN, REMOVE	AS	26.0	22.0	48.0		
0710-90	PAINTED PAVEMENT MARKINGS, FINAL SURFACE	LS	2.0	1.0	3.0		
0715-4-60	LIGHT POLE COMPILE, RELOCATE	EA	25.0	40.0	65.0		
0751-32-15	RAISED PLANTER (INCL. CONCRETE, REINFORCING, STONE VENEER, STONE CAP)	LF	214.0	646.0	860.0		
0751-36-11	BICYCLE RACK, FURNISH & INSTALL, 1-2 BICYCLES (INCL. FOOTING)	EA	3.0	6.0	9.0		
0751-37	TRASH RECEPTACLE, F & I (INCL. FOOTING)	EA	5.0	6.0	11.0		
0751-38-10	BENCH, F&I, PROPRIETARY PRODUCTS (INCL. FOOTING)	EA	6.0	12.0	18.0		
0751-38-13	BENCH, F&I, CONCRETE (INCL. FOOTING)	EA	29.0	58.0	87.0		
1050-11211	UTILITY PIPE F&I, PVC, CONDUIT, 0-1.9"	LF	970.0	0.0	970.0		
1050-11212	UTILITY PIPE F&I, PVC, CONDUIT, 2-4.9"	LF	860.0	0.0	860.0		
1080-11304	UTILITY FIXTURES, F&I, 5-7.9", VALVE ASSEMBLY	EA	5.0	5.0	10.0		
1080-11404	UTILITY FIXTURES, F&I, 8-19.9", VALVE ASSEMBLY	EA	5.0	5.0	10.0		
1050-11223	UTILITY PIPE F&I, PVC, CONDUIT, 5-7.9"	LF	900.0	1000.0	1900.0		
1050-11621	UTILITY PIPE F&I, COPPER, WATER, 0-1.9"	LF	200.0	200.0	400.0		
0908104-1	CONTRACTOR'S SEDIMENT AND EROSION CONTROL	LS	0.5	0.5	1.0		
430174118	PIPE CULVERT, REINFORCED CONCRETE PIPE, ROUND 18-INCH	LF	172.0	303.0	475.0		
430174124	PIPE CULVERT, REINFORCED CONCRETE PIPE, ROUND 24-INCH	LF	0.0	0.0	0.0		
1055-15	UTILITY FITTINGS, ADJUST & MODIFY	EA	6.0	0.0	6.0		
1644300	FIRE HYDRANT, INSTALL	EA	1.0	3.0	4.0		
1644800	FIRE HYDRANT, RELOCATE	EA	0.0	0.0	0.0		
1644900	FIRE HYDRANT, REMOVE	EA	1.0	3.0	4.0		
E570-2	SEED & MULCH	SF	8544.0	1572.3	10116.3		
E110-3-3	REMOVAL OF EXISTING STRUCTURE (INLET)	EA	6.0	9.0	15.0		
E110-3-4	REMOVAL OF EXISTING STRUCTURE (MANHOLE)	EA	0.0	1.0	1.0		
E430-17-99	PIPE REMOVAL	LF	150.0	225.0	375.0		
E430-17-99A	PIPE REMOVAL - EXISTING CIP WATER	LF	925.0	925.0	1850.0		
ES80326-X	ROCK MULCH	SF	625.0	1250.0	1875.0		
N/A	RESET MEMORIAL BRICKS	EA	102.0	667.0	769.0		Includes the removal, safe storage, and reinstall of memorial bricks as show on plans
N/A	RESTORE BENCHMARK	EA	2.0	8.0	10.0		

1


NOTES:  
1) PHASE 1 IS INCLUSIVE OF US-90 TO BEECH AVE AND INCLUDES BEECH AVE.  
2) PHASE 2 IS FROM THE END OF PHASE 1 TO INDUSTRIAL AVE THE TERMINOUS OF THE PROJECTS.

REFERENCE DRAWINGS	NO.	DATE	DESCRIPTION	BY
X-MDG22x34-TEP	1	02/24/2023	BID CLARIFICATIONS	KSL
COMPUTER FILE MANAGEMENT				
FILE NAME: R:\21.1165.004 (CRESTVIEW IMPLEMENTATION PLAN)\DWG\CONSTRUCTION PLANS\TEPISQ01.DWG				
CTB FILE: MATRIX.CTB				
PLOT DATE: OCTOBER 2022				
THIS DRAWING IS CURRENT AS OF PLOT DATE AND MAY BE SUBJECT TO CHANGE.				



PREPARED FOR:  
The City of  
**CRESTVIEW**  
FLORIDA  
198 North Wilson Street  
Crestview, FL 32536  
Phone: 850-682-1560  
www.cityofcrestview.org

PREPARED BY:  
**Matrix**  
Excellence by Design  
320 Bayshore Drive, Suite B  
Niceville, FL 32578  
Phone: 850-279-4298  
www.matrixdesigngroup.com



**MAIN STREET IMPROVEMENTS**  
CITY OF CRESTVIEW - FDOT PROJECT NO. 449302-1-54-01  
ENGINEERING PLANS

**SUMMARY OF APPROXIMATE QUANTITIES**

DESIGNED BY: ACR	SCALE:	DATE ISSUED: OCTOBER 2022	DRAWING No.:
CHECKED BY: KSL	HORIZ: N/A	SHEET: 06 OF 101	SQ01
	VERT: N/A		

FOR AND ON BEHALF OF  
MATRIX DESIGN GROUP, INC.  
PROJECT No. 21.1165.004