

**City of Crestview**

**Crestview Main Street - Roadway Improvement**

**23-03-01-PS**

**ADDENDUM NO. 2**

This addendum is to advise that we have received the following questions and have responded, as well as uploading the Main Street GeoReport from Matrix Design Group:

- 1. The plans show removal of flexible pavement. The bid form shows 0.0 SY of milling. Are we to remove asphalt to its total depth? If so, there is no line item for new base material. **Yes, asphalt pavement is being removed to it's full depth as indicated on Sheet SQ01. In accordance with FDOT specifications, new base material is defined under the line item 120-6 Embankment.****
- 2. When we remove the existing asphalt between the proposed curb and the existing curb will it be a total removal? If so, how thick is the existing pavement? What line item on the bid form will be used for fill to bring these areas back to subgrade elevation for the concrete? **Yes, it will be a total asphalt removal between the proposed curb and the existing curb. The existing pavement information can be found in the geotechnical report. In accordance with FDOT specifications, fill material is defined under the line item 120-6 Embankment.****

---

**-END OF ADDENDUM-**