

DOCUMENT 00900

ADDENDUM NO. 2

Date: **November 11, 2016**

Project: **Real Time Intelligence Center
(RTIC) Renovation Project**
3410 Amnicola Highway
Chattanooga, Tennessee 37406

Architect: **Billingsley/Architecture**
Suite 800 Republic Centre
633 Chestnut Street
Chattanooga, Tennessee 37450
(423) 752-0030

This addendum forms a part of the Contract Documents and modifies the original Documents dated October 11, 2016, as noted below. Acknowledge receipt of this Addendum No. 2 in the space provided on the Bid Form and Contracts. Failure to do so may subject the Bidder to disqualification.

This Addendum No. 2 consists of (14) fourteen 8½" x 11" sheets and (1) one 11" x 17" sheet.

SPECIFICATIONS

Item 1. Specifications, Section 00 03 00, Bid Proposal: Add attached Bid Schedule.

Item 2. Specifications, Section 01 00 10, Summary of Work, Paragraph 1.01, A, Line 2: Delete in its entirety. Substitute the following:

2. Installation of new partitions, new finishes, new aluminum glazing, new (contractor furnished) access flooring and finish, new HVAC equipment, new electrical fixtures and appliances, data raceway and boxes, etc.

Item 3. Specifications, Add Section 09 68 13, Carpet Tile, attached.

Item 4. Specifications, Add Section 09 69 00, Access Flooring.

Item 5. Specifications, Section 12 21 00, Window Treatment, Paragraph 3.04: Delete Line A in its entirety.

GENERAL CLARIFICATIONS

Item 6. There is no hardware change at the existing entry door.

Item 7. There is no electric strike at swing gate 101.

Item 8. A new card reader will be required as shown in Hall 102 on sheet E5. It will connect to the access panel in the RTIC approximately 30 feet away.

Item 9. The extent of contract documents does not include any work on new base cabinets or wall cabinets. Existing wall mounted counters are to be removed & turned over to the owner.

Item 10. At Detail 5/Sheet A6.1, wood trim is to be poplar or select pine, painted in color yet to be selected.

Item 11. On sheet E5, the electric access panel 'AE' is new. Electric access panel 'A' is an existing panel.

Item 12. The roof structure is precast concrete double T's with a lightweight concrete topping. Penetrations shall occur as shown on the attached drawing. (R-1). The roofing is a new TPO membrane still under warranty. All cutting, patching, & flashing shall be performed by JDH Roofing.

CHANGES TO SPECIFICATIONS

1. The following attached specifications sections are to be inserted into the project manual and will be part of the contract documents.
 - a. Carpeting, Section 09 68 00

END OF DOCUMENT