

Tom Green County



OFFICE OF THE COUNTY AUDITOR

May 10, 2019

ADDENDUM 1

RFB 19-029: Roy K Robb Fencing

Please see the clarifications below. Include this signed addendum with your response.

The previous RFB 19-023: Roy K Robb Fencing does not contain the same specifications as RFB 19-029. The original bid was rejected by the Commissioners Court and reissued in two separate Request for Bids. Please pay particular attention to the specifications listed in this bid packet.

Numerous underground utilities run along and very near to the west fence line including gasoline, natural gas, water, and sewer. The contractor may need to install portions of that fence line in the asphalt.

The fence line at the northwest corner should be changed to a straight line roughly spanning the curve of the driveway to avoid the sewer line manhole on the north side. The line is changed to from the outside edge of the curve to the opposite outside edge of the curve. The drawing showed a different angle that is no longer the desired outcome.

Contractor will leave six feet from the sewer line on the north side to the fence line. This will cause the fence to not be centered exactly down the road that is being abandoned for use.

Set the east fence line approximately fifteen feet back from the small building and flag pole located on the edge of the work camp.

The south fence line between the southeast corner and gate should be in line with the existing work camp fence.

Vendor will need to set new posts near the existing Delek fence line. The Delek fence may not be tied into or touched in any way.

The 10 foot swing gate should swing in toward the existing CSCD fence and should be set back an additional five feet from as shown on the drawing to allow ample room for the slide gate.

Fence material should be schedule 20: 9 gauge chain link, 2 3/8" line posts, 2 7/8" corner/terminal posts, 4" gate posts, 1 5/8" top rail. Barbed wire is four point. Additionally, chain link mesh is 1.2 oz. zinc coating, barb arms are standard over the counter weight, and bottom wire is 9 gauge.

Post depth is a minimum of three feet for the corner or terminal posts and two feet for line posts.

Ensure that cantilever gate is properly braced to prevent the gate from bowing when the chain is tightened.

No Federal funds are being utilized for this project; therefore, no "Buy American" provision exists.

The Commissioners Court of Tom Green County has adopted a Texas Steel Resolution that may be viewed in the February 21, 2017, court minutes. This page may be accessed from the County's web site co.tom-green.tx.us by clicking on County Officials - Commissioners Court – "View Agenda and Minutes"

This established a preference for domestic iron and steel, but not a mandate. All metal is not required to be completely domestic. You may list a percentage of your project materials that are domestic iron and steel for the Commissioners Court to consider when evaluating the lowest and best bid.

Sincerely,



Darin Schell
Senior Buyer

Company

Date

Signature

Please Print Name and Title