

**Project Addendum 1  
(1 page, 2 attachments)**

Project: IH Park Improvements

Date: April 4, 2016

The listed corrections should be incorporated into the plans/specifications. All bidders are required to indicate on the outside of their proposal envelope the receipt of this information by giving the date and the addenda number. The attached Bid Schedule shall replace the original Bid Schedule included in the bid packet.

Description of Corrections:

1. Bid Schedule, Add the following Items:
  14. "Furnish Fill Material"
  15. "Density Testing"
  16. "Construction Survey and Staking"
2. Section 01650 Measurement and Payment, Add the following:
  - M. "Furnish Fill Material"
  - N. "Density Testing"
  - O. "Construction Survey and Staking"

  
\_\_\_\_\_  
City of Lakeland  
Emily Harrell, P.E., City Engineer

4/4/16  
Date

**BID SCHEDULE  
IH PARK IMPROVEMENTS**

BID DATE: \_\_\_\_\_

COMPANY NAME: \_\_\_\_\_

ADDRESS: \_\_\_\_\_

Contractor shall furnish and install items as shown on the Drawings or called for in the Specifications. All costs not included in the schedule that are necessary to provide a complete, functional project as depicted in the Drawings and Specifications are to be considered incidental and merged with costs of other related bid items.

LS = Lump Sum    R&R = Remove and Replace    LF = Linear Feet    F&I = Furnish and Install  
SY = Square Yard    CY = Cubic Yard    EA = Each    Ton = Ton    LB = Pounds

**Schedule A**

ITEM	DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL COST
1	Earthwork	LS	1		
2	F&I Granular Material (No. 8)	Ton	250		
3	F&I Granular Base (303.01)	Ton	868		
4	F&I Concrete Wheel Stop	EA	64		
5	F&I Concrete Pavement	SF	332		
6	F&I Asphalt Pavement	SY	222		
8	F&I Select Backfill	CY	100		
9	F&I 3 Rail Fence	LF	362		
10	F&I Bollard	EA	1		
11	F&I Modular Block Wall	LF	220		
12	F&I Bermuda Sod	SY	1973		
13	F&I Silt Fence	LF	300		
14	Furnish Fill Material	CY	1500		
15	Density Testing	LS	1	\$1,000	\$1,000
16	Construction Survey and Staking	LS	1		
Total Bid Schedule A					

**Total Base Bid :** \_\_\_\_\_

Dollars (\$ \_\_\_\_\_).

L. Furnish and Install Silt Fence

1. Measurement of this item shall be paid by lineal foot (LF) of silt fencing furnished and installed in place and approved. This item shall include silt fence, wire fencing, stakes and installation. Payment shall be made by the contract unit price per Lineal Foot (LF) in place.

M. FURNISH FILL MATERIAL

1. MEASUREMENT OF THIS ITEM SHALL BE BY CUBIC YARD (CY) OF FILL MATERIAL FURNISHED AND INSTALLED IN PLACE AND APPROVED. QUANTITIES SHALL BE VERIFIED AND PAID BY HAUL TICKET. THIS ITEM SHALL INCLUDE FILL MATERIAL, CLEARING, GRADING, COMPACTING, SHAPING AND EXCAVATION. PAYMENT SHALL BE MADE BY THE CONTRACT UNIT PRICE PER CUBIC YARD (CY).

N. DENSITY TESTING

1. MEASUREMENT OF THIS ITEM SHALL BE PAID BY LUMP SUM (LS) FOR DENSITY TESTING. CONTRACTOR PERFORMING TESTING SHALL BE APPROVED BY THE OWNER PRIOR TO PERFORMING WORK. PAYMENT SHALL BE MADE BY INVOICE FROM GEOTECHNICAL ENGINEER OF ACTUAL TESTING PERFORMED. PAYMENT SHALL BE MADE BY THE CONTRACT UNIT PRICE PER LUMP SUM (LS) OF WORK COMPLETED.

O. CONSTRUCTION SURVEY AND STAKING

1. MEASUREMENT OF THIS ITEM SHALL BE PAID BY LUMP SUM (LS) FOR CONSTRUCTION SURVEY AND STAKING. CONTRACTOR PERFORMING SURVEY AND STAKING SHALL BE APPROVED BY THE OWNER PRIOR TO PERFORMING WORK. THIS ITEM INCLUDES SURVEYING AND STAKING SITE ACCORDING TO PLANS. PAYMENT SHALL BE MADE BY LUMP SUM (LS) OF WORK COMPLETED.

**END OF SECTION**