

DOOR & FRAME SCHEDULE										
NO.	DOORS								FRAME	NOTES
	WIDTH	HGT	THK	TYPE	FIRE R	MATERIAL	FINISH	GLAZING		
D1	3'-0"	7'-0"	1 3/4"	F	N/A	STEEL	PAINT	N/A	STEEL S1	
D2	3'-0"	7'-0"	1 3/4"	F	N/A	STEEL	PAINT	N/A	STEEL S1	
D3	3'-0"	7'-0"	1 3/4"	F	N/A	STEEL	PAINT	N/A	STEEL S1	
D4	3'-0"	7'-0"	1 3/4"	F	N/A	STEEL	PAINT	N/A	STEEL S1	
D5	3'-0"	7'-0"	1 3/4"	F	45 MIN.	STEEL	PAINT	N/A	STEEL S1	
D6	PR. 3'-0"	7'-0"	1 3/4"	F	90 MIN.	STEEL	PAINT	N/A	STEEL S4	
D7	3'-0"	7'-0"	1 3/4"	F	45 MIN.	STEEL	PAINT	N/A	STEEL S1	
D8	3'-0"	7'-0"	1 3/4"	F	45 MIN.	STEEL	PAINT	N/A	STEEL S1	
D9	3'-0"	7'-0"	1 3/4"	F	45 MIN.	STEEL	PAINT	N/A	STEEL S1	
D10	14'-0"	14'-0"	2"	OH	N/A	STEEL	PAINT	N/A	STEEL S3	
D11	14'-0"	14'-0"	2"	OH	N/A	STEEL	PAINT	N/A	STEEL S3	
D12	12'-0"	12'-0"	2"	OH	N/A	STEEL	PAINT	N/A	STEEL S5	
D13	5'-0"	7'-0"	2"	N/A	N/A	STEEL	PAINT	N/A	STEEL S1	1
D14	3'-0"	7'-0"	1 3/4"	F	90 MIN.	STEEL	PAINT	N/A	EXIST.	2
D15	3'-0"	7'-0"	1 3/4"	F	90 MIN.	STEEL	PAINT	N/A	EXIST.	2
D16	3'-0"	7'-0"	1 3/4"	F	90 MIN.	STEEL	PAINT	N/A	EXIST.	2
D17	3'-0"	7'-0"	1 3/4"	F	90 MIN.	STEEL	PAINT	N/A	EXIST.	2
D18	3'-0"	7'-0"	1 3/4"	F	90 MIN.	STEEL	PAINT	N/A	EXIST.	2
D19	3'-0"	7'-0"	1 3/4"	F	90 MIN.	STEEL	PAINT	N/A	EXIST.	2
D20	PR. 2'-6"	7'-0"	1 3/4"	F	90 MIN.	STEEL	PAINT	N/A	EXIST.	2
D21	3'-0"	7'-0"	1 3/4"	F	90 MIN.	STEEL	PAINT	N/A	EXIST.	2
D22	3'-0"	7'-0"	1 3/4"	F	90 MIN.	STEEL	PAINT	N/A	EXIST.	2
D23	3'-0"	7'-0"	1 3/4"	F	90 MIN.	STEEL	PAINT	N/A	EXIST.	2
D24	3'-0"	7'-0"	1 3/4"	F	90 MIN.	STEEL	PAINT	N/A	EXIST.	2
D25	3'-0"	7'-0"	1 3/4"	F	90 MIN.	STEEL	PAINT	N/A	EXIST.	2
D26	3'-0"	7'-0"	1 3/4"	F	90 MIN.	STEEL	PAINT	N/A	EXIST.	2
D27	3'-0"	7'-0"	1 3/4"	F	90 MIN.	STEEL	PAINT	N/A	EXIST.	2
D28	3'-0"	7'-0"	1 3/4"	F	90 MIN.	STEEL	PAINT	N/A	EXIST.	2
D29	3'-0"	7'-0"	1 3/4"	F	90 MIN.	STEEL	PAINT	N/A	EXIST.	2
D30	3'-0"	7'-0"	1 3/4"	F	90 MIN.	STEEL	PAINT	N/A	EXIST.	2
D31	3'-0"	7'-0"	1 3/4"	F	90 MIN.	STEEL	PAINT	N/A	EXIST.	2
W1	4'-0"	7'-0"	N/A	N/A	45 MIN.	STEEL	PAINT	TEMP.	STEEL S2	
A1	2'-0"	6'-8"	N/A	N/A	N/A	N/A	N/A	TEMP.	ALUM. A1	

NOTES:

1. PROVIDE A SMOOTH FRAME WITH CLEAR OPENING OF 5'-0" WIDE BY 7'-0" HIGH WITHOUT DOOR STOPS. PROVIDE 2" JAMBS AND A 4" HEAD.
2. PROVIDE A MEDIUM GRADE COMMERCIAL LOCKSET WITH LEVER HANDLE, MEDIUM COMMERCIAL GRADE HINGES AND MEDIUM COMMERCIAL GRADE CLOSER. RE-USE EXISTING FRAMES. PREPARE EXISTING FRAMES AS REQUIRED TO INSTALL NEW DOORS. PAINT EXISTING FRAMES AS SPECIFIED.

ROOM FINISH SCHEDULE										
NO.	ROOM NAME	BASE MAT'L	FLOOR	WALLS			CEILING		NOTES	
				NORTH	SOUTH	EAST	WEST	MATERIAL		
101	LOBBY	VINYL	LVT	PAINT	PAINT	PAINT	PAINT	LAY-IN/AP1	1	
102	CORRIDOR	VINYL	LVT	PAINT	PAINT	PAINT	PAINT	LAY-IN/AP1	1	
103	RECEPTION	VINYL	LVT	PAINT	PAINT	PAINT	PAINT	LAY-IN/AP1	3	
104	CORRIDOR	VINYL	LVT	PAINT	PAINT	PAINT	PAINT	LAY-IN/AP1	3	
105	OPEN OFFICE AREA	VINYL	LVT	PAINT	PAINT	PAINT	PAINT	LAY-IN/AP1	1	
106	OFFICE	VINYL	LVT	PAINT	PAINT	PAINT	PAINT	LAY-IN/AP1	3	
107	OFFICE	VINYL	LVT	PAINT	PAINT	PAINT	PAINT	LAY-IN/AP1	3	
108	OFFICE	VINYL	LVT	PAINT	PAINT	PAINT	PAINT	LAY-IN/AP1	3	
109	OFFICE	VINYL	LVT	PAINT	PAINT	PAINT	PAINT	LAY-IN/AP1	1	
110	OFFICE	VINYL	LVT	PAINT	PAINT	PAINT	PAINT	LAY-IN/AP1	1	
111	OFFICE	VINYL	LVT	PAINT	PAINT	PAINT	PAINT	LAY-IN/AP1	1	
112	CORRIDOR	VINYL	LVT	PAINT	PAINT	PAINT	PAINT	LAY-IN/AP1	2	
113	OFFICE	VINYL	LVT	PAINT	PAINT	PAINT	PAINT	LAY-IN/AP1	2	
114	OFFICE	VINYL	LVT	PAINT	PAINT	PAINT	PAINT	LAY-IN/AP1	2	
115	OFFICE	VINYL	LVT	PAINT	PAINT	PAINT	PAINT	LAY-IN/AP1	2	
116	OFFICE	VINYL	LVT	PAINT	PAINT	PAINT	PAINT	LAY-IN/AP1	2	
117	CONFERENCE	VINYL	LVT	PAINT	PAINT	PAINT	PAINT	LAY-IN/AP1	2	
118	OFFICE	VINYL	LVT	PAINT	PAINT	PAINT	PAINT	LAY-IN/AP1	2	
119	OFFICE	VINYL	LVT	PAINT	PAINT	PAINT	PAINT	LAY-IN/AP1	3	
120	OFFICE	VINYL	LVT	PAINT	PAINT	PAINT	PAINT	LAY-IN/AP1	1	
121	OFFICE	VINYL	LVT	PAINT	PAINT	PAINT	PAINT	LAY-IN/AP1	1	
122	OFFICE	VINYL	LVT	PAINT	PAINT	PAINT	PAINT	LAY-IN/AP1	2	
123	ELECTRICAL	NO BASE	CONC.	PAINT	PAINT	PAINT	PAINT	EXPOSED		
124	MECHANICAL	NO BASE	CONC.	PAINT	PAINT	PAINT	PAINT	EXPOSED		
125	MEN'S	EXISTING C.T.	EXISTING C.T.	PAINT	PAINT	PAINT	PAINT	LAY-IN/AP2		
126	WOMEN'S	EXISTING C.T.	EXISTING C.T.	PAINT	PAINT	PAINT	PAINT	LAY-IN/AP2		

NOTES:

1. EXISTING COMPOSITE TILE TO REMAIN. INSTALL NEW LUXURY VINYL TILE OVER EXISTING COMPOSITE TILE. REMOVE EXISTING VINYL BASE. PROVIDE AND INSTALL NEW VINYL BASE TO MATCH EXISTING.
2. REMOVE EXISTING CARPET. INSTALL NEW LUXURY VINYL TILE IN AREA EXISTING CARPET WAS REMOVED. REMOVE EXISTING VINYL BASE. PROVIDE AND INSTALL NEW VINYL BASE TO MATCH EXISTING.
3. REMOVE EXISTING CARPET. INSTALL NEW LUXURY VINYL TILE IN AREA EXISTING CARPET WAS REMOVED. EXISTING COMPOSITE TILE TO REMAIN. INSTALL NEW LUXURY VINYL TILE OVER EXISTING COMPOSITE TILE. AS NECESSARY PROVIDE A VINYL TRANSITION STRIP WHERE NEW LUXURY VINYL TILE IS INSTALLED OVER EXISTING COMPOSITE TILE. EXISTING VINYL BASE TO REMAIN. PROVIDE NEW VINYL BASE AT NEW WALLS TO MATCH THE EXISTING VINYL BASE.

GENERAL NOTES:

1. ALL NEW LAY-IN CEILINGS ARE TO BE FIELD DETERMINED TO COORDINATE WITH NEW MECHANICAL AND ELECTRICAL WORK.

DOUGLAS A. NEAL
ARCHITECT, INC.
ARCHITECTURE
MASTER PLANNING
CONSULTING
107 MARINA DRIVE
ST. SIMONS ISLAND, GA
31522
CELL: (912) 602-8127
email: dougnealarch@bellsouth.net

COPYRIGHT 2021



ENGINEER SEAL

PROJECT NAME
CITY OF WAYCROSS
ARMORY
RENOVATIONS

DRAWING TITLE
DOOR AND
FINISH
SCHEDULE,
FRAME
ELEVATIONS
AND DOOR
TYPES

REVISIONS:
1. 09-10-21 REVISED
DOOR AND FINISH
SCHEDULES. ADDENDUM
NO. 1.

DATE
AUGUST 30, 2021

PROJECT NUMBER
2101

CADD FILE NUMBER

A001

