

Addendum 1 Hamilton Road Utilities

1. What is the required completion date: The date is January 23rd, 2023.
2. How many long and short side services will be needed: 6 will need to be bored under Hamilton Road (min 4' deep). There will be two short side.
3. What is the material delivery date: The materials date is tentatively September 16th, 2022.
4. Can roads can be open cut and how is the contractor required to patch: Yes roads will be open cut. Please backfill with 57stone and 810 screening. The City will provide steel plates to put on top.
5. Will there be a trench rock cause: Yes, it has been added to the documents of this addendum. Please use this new sheet in place of the original bid sheet.
6. The GDOT project has cut and fill. What depth is the contractor required to install the pipe for each section along the project: The depths are posted on the cross sections attached to this addendum. The pipe should be approximately four (4) feet below the finished grade.
7. Will there be a GDOT boring report attached: Yes the report is attached on this addendum.
8. Will there be updated drawings: Yes, please see all attached drawings.