

“City of Havelock
Gravity Sewer Manhole & Box Culvert Rehabilitation”

Addendum 1

October 2, 2019

Questions Received

1. We did not note any manhole diameter listed in the in the Scope of Work or shown on the attached drawing.

The Contractor must install 4' Sewer Manhole and Doghouse Manhole to conform to NCDOT standards and specifications. The contractor may refer to Cape Fear Precast concrete manhole drawings for representation.

2. Can we get copies of any design drawings on the existing box culvert installed on Pineview Street. Specifically we would like to see lifting details of the individual box section and weights or at least dimensions so weights can be calculated for the sections.

Attached is the record drawings from 2012 Pineview Box Culvert.

