

ADDENDUM NUMBER 2

**Walker County School System
Former LaFayette High School:
Asbestos Abatement**

Scope of Work Plan GA. Titled:

ACES Project # 2276-101

Dated: November 17, 2020: Plan Date

Addendum Date: December 9, 2020:

Contractor Bidders are advised that the following is hereby made a part of the above referenced plans, specifications or clarifications per the Walker County Board of Education.

IN SPECIFICATIONS:

- 1. No listing on this Addendum per Specifications in Work Plan:**

CLARIFICATIONS:

- 1. Contractors please see attached Drawings outlining Dimensions per presentation at Pre-Bid Meeting.**
- 2. Contractors please note that the Walker County System will provide Dumpster(s) for the Non-ACM Carpet and Material and it will be delivered to the C&D Landfill by Republic Services. The Contractor will as already directed remove and load all designated material.**
- 3. Roof Breezeway Removal: (Flashing and Tar are 3 to 7% Chrysotile): You may cut the steel support post at top of handrail in removal. As expected by the Specs and discussed you will remove the Breezeway in its entirety. The Auditorium Demolition Contractor will proceed as instructed for the stationary remaining handrails.**
- 4. The Breezeway is connected in the back to the Auditorium Wall and it will be demolished. The building facing it and to its left will not be demolished. The building to its right with the slant (45 degrees) is the main building to be renovated. You will remove that portion of the Breezeway in careful manner not damage to the 100 Bldg.**
- 5. Removal of Non-ACM Carpet: During removal of this carpet, the Contractor will relocate any unattached shelving or cabinets in order to remove the carpet and clean the floor. Contractor will not remove any attached shelving or cabinets. You will cut around the furnishings in smooth manner and it will be removed during the renovation.**

- 6. Exception: On 2nd Floor the Contractor will remove the shelving and VCT from room as directed in closet room 22-A. Removal of any obstruction to access the ACM will be expected per specifications.**
- 7. All Contractors per any ACM removal project must have some method of transporting the material to a qualified landfill. We are not recommending nor suggesting any Hauler or Transporter so the listed info is only for your information. SANTEK of Dalton said they would be happy to discuss this issue with you with us being in Georgia: Name of Contact: Page Heywood: 706-277-7188 or Lori in the office at 706-277-7188. There are various Hazardous Landfills in some general direction so this is up to each Contractor to make their own decisions concerning the item.**

END OF ADDENDUM