



Paul R. Nobles/Purchasing Manager  
Office of Purchasing

October 23, 2018

To: All Known Prospective Bidders

**Addendum Number 1:**

Re: Construction Services for Sheriff Range Rehabilitation  
Specification Number: PD 17-18.102

All:

We recently sent you a Request for Proposals on the above-mentioned specification.

This Addendum Number 1 provides for:

1. **Revised Opening Date**

From: ~~RESPONSES WILL BE RECEIVED UNTIL: 2:00 p.m., CDT, October 25, 2018~~  
To: RESPONSES WILL BE RECEIVED UNTIL: 2:00 p.m., CDT, October 30, 2018

2. **Request for Additional Information**

1. What is the design for the new knee wall shown at the existing pistol range? **Knee wall is to be similar to existing railroad tie knee wall.**
2. What is the design, including minimum and maximum heights, for the new retaining wall(s) both ranges? **Minimum height to be 8' and retaining wall to be wooden.**
3. What is the design for the new headwall as indicated on the rifle range? **What headwall are you referring to? There is no mention of headwall in my plan mark ups.**
4. What is the design for the new milled asphalt driving surface? Depth, base? Minimum width? **4" thickness minimum. Drive to be 12' minimum and parking area to be 20'X 30'.**
5. Concerning Lead removal:
  - a. The specifications call for lead removal in the parking lot to what depth and is this for the entire lot **The parking lot will be surface only (Parking area is only because of lead left during the last clean up. Expected 1.5-2").**
  - b. To what depth and height do we clean the berm soil for lead? **It is expected that the top 2.5-3' will contain the majority of the lead present.**
  - c. Once the soil has been removed, cleaned, treated and the new retaining wall built, what happens with the soils left over? **As discussed in the pre-sol, the soils will be utilized to back fill the retaining wall and grading on both site to ensure proper drainage functions.**

6. I understand we are to dismantle and relocate 10 of the existing turning targets and a control box to the rifle range.
  - a. What do we do with the remaining targets and system? **As stated in the pre-sol, remaining targets are to be stockpiled for the SO to store as extra parts.**
  - b. Do the 10 units we relocate to the rifle range require a concrete slab or walkway ? **Concrete slab similar to the existing will be required on the rifle range. No walkways will be required.**
7. What is the design for the concrete paths? **As stated in the pre-sol. it is our intentions to leaving the existing firing lines in place if possible. There will be sections that may have to be removed and repoured based on how you propose to run your new conduit.**
8. Are there any specifications for the new LED lights? **Just an outdoor LED flood light similar to existing.**
9. What are the requirements for the electrical conduit? **I would recommend a 2.5" pipe as a minimum sizing.**
10. Where do we install these conduits, this should be shown on the drawings? **They are notated on both ranges in the supplied drawings.**
11. As I understand we are to relocate a temporary shed to the rifle range, does it require tie downs and if so how many and what size or type? **Yes. Minimal of four.**

This Addendum Number 1 is furnished to all known prospective bidders. Please sign and return one copy of this Addendum, with original signature, with your bid as an acknowledgement of you having received same. You may photo copy for your record.

Sincerely,

Paul R. Nobles  
Purchasing Manager



Acknowledgement of Receipt of Addendum 1:

SIGNED: \_\_\_\_\_

COMPANY: \_\_\_\_\_