

REVISIONS
1. Addendum 1 12/3/18

**PLATTE COUNTY SCHOOL DISTRICT R-III**  
**HIGH SCHOOL AND PAXTON SECURITY UPGRADES**  
1501/1601 BRANCH ST. PLATTE CITY, MO 64079

REVISION	DATE
1 Addendum 1	12/3/18

HEI JOB NO:	1850001749
DATE:	11/6/18
DESIGNED BY:	RNM

SHEET NO.  
**TY101**

**SECURITY PLAN NOTES**

- TY05 RETROFIT PANIC HARDWARE WITH QEL ELECTRONIC LATCHING MECHANISM. RETROFIT PANIC HARDWARE WITH REQUEST TO EXIT AND LATCH BOLT MONITOR. DOOR SHALL BE INDEPENDENTLY RELEASED BY VALID CREDENTIAL.
- TY06 RETROFIT PANIC HARDWARE WITH QEL ELECTRONIC LATCHING MECHANISM. RETROFIT PANIC HARDWARE WITH REQUEST TO EXIT AND LATCH BOLT MONITOR.
- TY08 RETROFIT WITH INTEGRAL REQUEST TO EXIT.
- TY09 RETROFIT WITH INTEGRAL LATCH BOLT MONITOR.
- TY10 RETROFIT PANIC HARDWARE WITH QEL ELECTRONIC LATCHING MECHANISM. RETROFIT PANIC HARDWARE WITH REQUEST TO EXIT AND LATCH BOLT MONITOR. DOOR SHALL BE INDEPENDENTLY RELEASED BY VALID CREDENTIAL. EXTERIOR ADA OPERATOR SHALL REQUIRE VALID CREDENTIAL DURING SECURE SCHEDULE PRIOR TO ACTUATION.
- TY11 EXISTING CAMERA. PROVIDE VMS LICENSE, PROGRAM INTO MAPS, AND INTEGRATE/ASSOCIATE WITH RESPECTIVE DOOR.
- TY12 CONTRACTOR TO DETERMINE EXACT LOCATION OF CAMERA. CAMERA SHALL CAPTURE ALL SEATING IN FIELD OF VIEW. PROVIDE PENDANT OR WALL MOUNTING HARDWARE AS REQUIRED.
- TY13 CONFIRM EXACT PLACEMENT WITH OWNER.
- TY14 COORDINATE PLACEMENT OF PANIC BUTTONS WITH OWNER.
- TY15 CARD READER AT DESK TO ALLOW REMOTE ENTRY RELEASE AND ENROLLMENT OF CREDENTIALS. COORDINATE EXACT PLACEMENT WITH OWNER.
- TY17 REPLACE ARMORED CORD ASSEMBLY
- TY18 REPLACE CARD READER BOX WITH ONE OF APPROPRIATE SIZE.
- TY19 REPLACE DOOR HARDWARE SET WITH VON DUPRIN 98 SERIES WITH QEL. INTEGRAL REQUEST TO EXIT AND LATCH BOLT MONITOR. DOOR SHALL BE INDEPENDENTLY RELEASED BY VALID CREDENTIAL.
- TY20 REPLACE DOOR HARDWARE SET WITH VON DUPRIN 98 SERIES WITH QEL. INTEGRAL REQUEST TO EXIT AND LATCH BOLT MONITOR.
- TY21 REPLACE AND REPAIR MULLION WITH NEW KEYED MULLION.
- TY22 REPLACE DOOR HARDWARE SET WITH VON DUPRIN 98 SERIES WITH INTEGRAL REQUEST TO EXIT AND LATCH BOLT MONITOR.
- TY23 CORRECT RACEWAY AND JUNCTION BOXES.
- TY25 PROVIDE 55" VMS DISPLAY. PROVIDE NEW POWER, PATHWAY, ARTICULATING MOUNT, AND AV CABLE FOR CONNECTION TO OWNER PROVIDED CLIENT WORKSTATION. COORDINATE EXACT LOCATION WITH OWNER.
- TY26 PROVIDE WALL ARM AND CORNER MOUNT BRACKET.



1 HIGH SCHOOL SECURITY PLAN - AREA A  
1/16" = 1'-0"

**NOTE:**

**THESE DRAWINGS ARE SCHEMATIC IN NATURE. EXISTING CONDITIONS ARE FROM GENERAL OBSERVATIONS AND ARE NOT EXHAUSTIVE OF ALL FIELD CONDITIONS.**

**THE LOCATIONS AND DEVICES DEPICTED ON DRAWINGS ARE REPRESENTATIVE. THE CONTRACTOR SHALL SURVEY SITE AND PROVIDE A COMPLETE AND FUNCTIONING SYSTEM MEETING THE MINIMUM REQUIREMENTS THE DISTRICT STANDARDS AND SECURITY DRAWINGS.**

**INSTALLATIONS SHALL COMPLY WITH ALL LOCAL BUILDING, FIRE, AND ELECTRICAL CODES. ALL INSTALLATIONS MUST SATISFY THE AUTHORITY HAVING JURISDICTION.**