

ADDENDUM NUMBER 2 TO THE BID DOCUMENTS

To all bidders of record on the Bid Proposal titled:

“High-Density Polyethylene (HDPE) leachate piping, fittings, manholes, valve boxes and geomembrane and geocomposite materials for the new Phase 3 Class III Landfill leachate collection system for the Solid Waste Department”

CEC Project Number 322-453

Addendum Date: June 6, 2023

A. This Addendum shall be considered part of the bid documents for the above-mentioned project as though it had been issued at the same time and shall be incorporated integrally therewith. Where provisions of the following supplementary data differ from those of the original bid documents, this Addendum shall govern and take precedence.

B. Bidders are hereby notified that they shall make any necessary adjustments in their estimates as a result of this Addendum. It will be construed that each bidder's proposal is submitted with full knowledge of all modifications and supplemental data specified herein.

The bid documents are modified and clarified, as follows.

Addendum Items:


Item #1: Answers to recent questions from potential bidders:

- 1. Bidder to provide manpower to fuse pipe sections. Owner will provide equipment and manpower to excavate trenches and place the pipe in the trench with bedding and backfill.**
- 2. The “void” area referred to in Detail MH-1 is the area to be filled with HDPE resin to prevent pooling of leachate inside the manhole between the inlet and outlet.**
- 3. All valves will be provided by the Owner (including knife gate and butterfly valves).**
- 4. The Owner will excavate and backfill the liner anchor trenches.**
- 5. Additional 4 inch pipe is required from the 4-inch stub-out at MH-3 in order for emergency drain from MH-3 to daylight to the ground surface.**

End of Addendum #2

Engineer Certification:




Kevin B. Wolfe

June 6, 2023

Date