



## ADDENDUM NO. 2

Issue Date: November 2, 2021

Project Name: 6<sup>th</sup> Ave Milling & Resurfacing from US1 to 21<sup>st</sup> St, IRC-1638

Bid Number: 2022008

Bid Opening Date: November 10, 2021

This addendum is being released to answer questions received to date.

The information and documents contained in this addendum are hereby incorporated in the invitation to bid. **This addendum must be acknowledged where indicated on the bid form, or the bid may be declared non-responsive.**

### Questions and Answers

1. Is the stamped asphalt one pattern and one color? **The stamped asphalt is one color. The pattern is matching existing. Bidders should field verify existing conditions. Product(s) submittals from the bidder awarded the contract will need to be from FDOT Approved Products List (APL). Sheet No. 2, Pay Item Note #4 states Pay Item 337 7 83 shall include cost of stamped asphalt.**
2. Can you provide additional information on the number of loops to be replaced on the project as stated on bid item 337 7 83, in note #4 on plan sheet #2. **Based on previous discussion with IRC Traffic Operations, none of the existing traffic loops within the project area are being utilized and are not proposed to be replaced.**
3. The bid item 570 1 2 states Bahia sod. However, note #7 on plan sheet 2 states that the Contractor must match existing. Please clarify. **The majority of turf is assumed to be Bahia. Bidders are encouraged to field verify existing conditions. Should there be areas of Floratam, St. Augustine, or other ornamental type grass, those area will need to be replaced to match exiting. Any increase of cost should be covered in the line item.**
4. Bid item 700 1 11 is for signs up to 12 SF, has a bid quantity of 1 AS. Plans indicate approx. 20 signs under this item. **There are 20 new proposed signs. Updated Itemized Bid Schedule attached**

### Attachments

Updated Itemized Bid Schedule

**ITEMIZED BID SCHEDULE ADDENDUM NO. 2**

**PROJECT NAME: 6TH AVENUE MILLING & RESURFACING FROM U.S. 1/S.R. 5 TO 21ST STREET**

**PROJECT NO: IRC-1638, BID NO. 2022008, FM NO. 438074-1-54-01 \*REVISED 11/2/2021**

**BIDDER'S NAME:** \_\_\_\_\_

| Item No.   | Description  | Unit | Unit Price | Quantity | Amount |
|------------|--|------|------------|----------|--------|
|            | <b>ROADWAY</b>   |      |            |          |        |
| 0101 1     | MOBILIZATION   | LS   |            | 1        |        |
| 0102 1     | MAINTENANCE OF TRAFFIC   | LS   |            | 1        |        |
| 0104 1     | EROSION CONTROL  | LS   |            | 1        |        |
| 0110 1 1   | STANDARD CLEARING & GRUBBING   | AC   |            | 13.5     |        |
| 0110 4 10  | REMOVAL OF EXISTING CONCRETE PAVEMENT/<br>REMOVAL OF EXISTING CONCRETE       | SY   |            | 1,220    |        |
| 0120 1     | REGULAR EXCAVATION   | CY   |            | 313      |        |
| 0120 6     | EMBANKMENT   | CY   |            | 156      |        |
| 0160 4     | STABILIZATION TYPE B   | SY   |            | 20       |        |
| 0286 1     | TURNOUT CONSTRUCTION / DRIVEWAY BASE -<br>OPTIONAL MATERIALS                 | SY   |            | 20       |        |
| 0327 70 6  | MILLING EXISTING ASPHALT PAVEMENT (1-1/2" AVG<br>DEPTH)                      | SY   |            | 39,457   |        |
| 0337 7 83  | ASPHALTIC CONCRETE FRICTION COURSE (TRAFFIC C)<br>(FC 12.5) (PG 76-22)       | TN   |            | 4053.2   |        |
| 0400 0 11  | CONCRETE CLASS NS, GRAVITY WALL  | CY   |            | 1.33     |        |
| 0425 6     | VALVE BOXES, ADJUST  | EA   |            | 15       |        |
| 0425 15 52 | INLET TOP, REPLACE, DITCH BOTTOM INLET                                       | EA   |            | 1        |        |
| 0515 1 2   | PIPE HANDRAIL - GUIDERAIL, ALUMINUM  | LF   |            | 14       |        |
| 0520 1 10  | CONCRETE CURB & GUTTER, TYPE F   | LF   |            | 879      |        |
| 0522 2     | CONCRETE SIDEWALKS & DRIVEWAYS, 6" THICK (3,000<br>PSI FIBERMESH REINFORCED) | SY   |            | 3,158    |        |
| 0527 2     | DETECTABLE WARNINGS  | SF   |            | 948      |        |
| 0570 1 2   | PERFORMANCE TURF, SOD (BAHIA)  | SY   |            | 1,533    |        |
| 0630 2 11  | CONDUIT, FURNISH & INSTALL, OPEN TRENCH                                      | LF   |            | 3,044    |        |
| 0630 2 12  | CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE                                 | LF   |            | 7,870    |        |
| 0632 7 1   | SIGNAL CABLE - NEW OR RECONSTRUCTED<br>INTERSECTION, FURNISH & INSTALL       | PI   |            | 3        |        |
| 0633 1 123 | FIBER OPTIC CABLE, F&I, UNDERGROUND, 49-96 FIBERS                            | LF   |            | 12,918   |        |
| 0635 2 11  | PULL & SPLICE BOX, F&I, 13" X 24" COVER SIZE                                 | EA   |            | 54       |        |

**ITEMIZED BID SCHEDULE ADDENDUM NO. 2**

**PROJECT NAME: 6TH AVENUE MILLING & RESURFACING FROM U.S. 1/S.R. 5 TO 21ST STREET**

**PROJECT NO: IRC-1638, BID NO. 2022008, FM NO. 438074-1-54-01 \*REVISED 11/2/2021**

**BIDDER'S NAME:** \_\_\_\_\_

| Item No.   | Description   | Unit | Unit Price | Quantity | Amount |
|------------|---|------|------------|----------|--------|
| 0635 2 12  | PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE                                | EA   |            | 25       |        |
| 0635 2 13  | PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE       | EA   |            | 7        |        |
| 0646 1 11  | ALUMINUM SIGNALS POLE, PEDESTAL   | EA   |            | 4        |        |
| 0646 1 12  | ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST           | EA   |            | 5        |        |
| 0646 1 60  | ALUMINUM SIGNALS POLE, REMOVE   | EA   |            | 4        |        |
| 0653 1 11  | PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY                   | AS   |            | 7        |        |
| 0653 1 12  | PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS                  | AS   |            | 4        |        |
| 0653 1 60  | PEDESTRIAN SIGNAL, REMOVE PED SIGNAL-POLE/PEDESTAL TO REMAIN                | AS   |            | 9        |        |
| 0665 1 11  | PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD                            | EA   |            | 15       |        |
| 0665 1 40  | PEDESTRIAN DETECTOR, RELOCATE   | EA   |            | 1        |        |
| 0665 1 50  | PEDESTRIAN DETECTOR, ADJUST/MODIFY ON EXISTING POLE                         | EA   |            | 1        |        |
| 0665 1 60  | PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN                        | EA   |            | 8        |        |
| 0676 1500  | TRAFFIC SIGNAL CONTROLLER CABINET, ADJUST/MODIFY                            | EA   |            | 3        |        |
| *0700 1 11 | SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF                             | AS   |            | 20       |        |
| 0700 1 50  | SINGLE POST SIGN, RELOCATE  | AS   |            | 6        |        |
| 0706 1 1   | RAISED PAVEMENT MARKER, TYPE B WITHOUT FINAL SURFACE MARKINGS               | EA   |            | 699      |        |
| 0710 90    | PAINTED PAVEMENT MARKINGS, FINAL SURFACE                                    | LS   |            | 1        |        |
| 0711 11123 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT     | LF   |            | 2,894    |        |
| 0711 11125 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINES AND CROSSWALK     | LF   |            | 674      |        |
| 0711 11160 | THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL                           | EA   |            | 71       |        |
| 0711 11170 | THERMOPLASTIC, STANDARD, WHITE, ARROWS                                      | EA   |            | 34       |        |
| 0711 11224 | THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONALS AND CHEVRONS      | LF   |            | 221      |        |
| 0711 16101 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"                    | GM   |            | 3.410    |        |
| 0711 16131 | THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP | GM   |            | 0.032    |        |

**ITEMIZED BID SCHEDULE ADDENDUM NO. 2**

**PROJECT NAME: 6TH AVENUE MILLING & RESURFACING FROM U.S. 1/S.R. 5 TO 21ST STREET**

**PROJECT NO: IRC-1638, BID NO. 2022008, FM NO. 438074-1-54-01 \*REVISED 11/2/2021**

**BIDDER'S NAME:** \_\_\_\_\_

| Item No.  | Description   | Unit | Unit Price | Quantity     | Amount     |
|---|---|------|------------|--------------|------------|
| 0711 16201  | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6" | GM   |            | 3.444        |            |
| 0711 16231  | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"  | GM   |            | 0.112        |            |
| 1080 21108  | UTILITY FIXTURE, VALVE BOX, FURNISH & INSTALL, 8"         | EA   |            | 41           |            |
| 0999 1  | AS BUILT SURVEY (BY REGISTERED SURVEYOR)                  | LS   |            | 1            |            |
| <b>6th AVENUE MILLING AND RESURFACING FROM U.S. 1/S.R. 5 TO 21st STREET</b> |   |      |            |              |            |
| 0999 25   | <b>FORCE ACCOUNT</b>                                      |      |            |              | 180,000.00 |
| <b>TOTAL BID AMOUNT (INCLUDING FORCE ACCOUNT)</b>                           |   |      |            | <b>TOTAL</b> |            |

LS=Lump Sum AC=Acre SY=Square Yard CY=Cubic Yard TN=Ton EA=Each

LF=Linear Foot SF=Square Foot PI=Per Intersection AS=Assembly GM=Gross Mile

**NOTE: IF THERE IS A DISCREPANCY BETWEEN THE PLANS (SUMMARY OF PAY ITEMS) AND THE ITEMIZED BID SCHEDULE, THE BID SCHEDULE WILL BE UTILIZED FOR BIDDING PURPOSES.**

**TOTAL PROJECT BID AMOUNT IN WORDS** \_\_\_\_\_