

## ADDENDUM NO. 2

DATE: May 19, 2017

TO: All Bidders

FROM: Boyce H. Evans, Purchasing Agent

SUBJECT: Addendum No. 2 – 2017 Neighborhood Drainage Project

PROJECT NO.: 14W-D-0576

BIDS TO BE OPENED: Wednesday, May 31, 2017 at 11:00:00 a.m. Eastern Time

This addendum is being published to respond to a question asked by a potential bidder during the pre-bid meeting for the 2017 Neighborhood Drainage Project. This addendum becomes a part of the Contract Document and modifies the original specifications as noted.

Question #1: The Pay Item for the gabion wall is shown as a lump sum, can you provide an approximate SY volume for this wall?

Response: The volume of the gabion baskets is approximately 76 cubic yards per the table below. The amount of stone volume to fill the gabion cells will be approximately 5% less, or roughly 72 cubic yards.

Block Type	#	Vol per basket (cubic ft)	Vol Total (cubic ft)	
A	12	54	648	
A'	6	54	324	
AH	1	27	27	
B	9	81	729	
D	3	27	81	
E	5	40.5	202.5	
E'	1	40.5	40.5	
		SUM =	2052	Cubic Ft
			76	Cubic Yds

**END OF ADDENDUM NO. 2**