



Spartanburg School District 2
RFB 2001 Install Drain Fill Sewer System at District Office

ADDENDUM 1

August 8, 2019

This Addendum #1 is being released to answer the following questions and make the changes noted below:

1. Will the 6" line be pressure tested? No
2. Is the 6" line SDR 35? No, Schedule 40
3. What is the protocol for the abandonment of the pump station? Leave it in place, take off the manhole cover and fill with dirt. Manhole covers will not be replaced.
4. Are asbuilts necessary? Yes
5. Is a CAD file available? Yes, if needed.

Working hours can be with during work hours if the septic tank is pumped and tied in and toilets can be used.

A tracer wire should be included in this project.

A bid bond of 5% or cashiers check is required.