

**CITY OF GRIFFIN  
SOLOMON PARK UTILITY RELOCATE  
BID TABULATION**

Item	Description	Unit	Quantity	Unit Price	Item Total
<b>GENERAL</b>					
1.	PAYMENT & PERFORMANCE BONDS	LS	1		
2.	GENERAL CONDITIONS	LS	1		
3.	CONSTRUCTION STAKING BY REGISTERED SURVEYOR	LS	1		
4.	WATER & SEWER AS-BUILT SURVEY BY REGISTERED SURVEYOR	LS	1		
<i>General Subtotal =</i>					
<b>WATER MAIN RELOCATION</b>					
5.	16" D.I.P. CLASS 350 WATER MAIN	LF	638		
6.	90° MJ BEND COMPLETE WITH RESTRAINTS AND CONCRETE BLOCKING	EA	3		
7.	45° MJ BEND COMPLETE WITH RESTRAINTS AND CONCRETE BLOCKING	EA	2		
8.	16" MJ GATE VALVE COMPLETE	EA	2		
9.	FIRE HYDRANT ASSEMBLY COMPLETE WITH 16" x 6" TEE	EA	1		
10.	LOCKING GASKETS FOR 16" D.I.P.	EA	37		
11.	"ROD RESTRAINT SYSTEM" TO EXISTING ENCASEMENT INCLUDING CONCRETE COLUMN, PER DETAIL	LS	1		
<i>Water Main Relocation Subtotal =</i>					
<b>SANITARY SEWER MAIN RELOCATION</b>					
12.	8" D.I.P. SEWER MAIN	LF	545		
13.	4' DIAMETER SANITARY SEWER MANHOLE ADDITIONAL VERTICAL FOOTAGE	VF	39		
14.	4' DIAMETER SANITARY SEWER MANHOLE BASE SECTION (4' TALL)	EA	3		
15.	CITY OF GRIFFIN MANHOLE RING & COVER	EA	3		
16.	GROUT FILL ABANDONED SANITARY SEWER MAIN PER PLANS	LS	1		
<i>Sanitary Sewer Main Subtotal =</i>					
<b>EROSION CONTROL</b>					
17.	TYPE 'C' SILT FENCE, INCLUDING MAINTENANCE AND REMOVAL	LF	920		
18.	TEMPORARY GRASSING	AC	1.40		
19.	PERMANENT GRASSING	AC	1.40		
<i>Erosion Control Subtotal =</i>					
<b>MISCELLANEOUS</b>					
20.	SAW CUT STREET - CONCRETE (VARIOUS DEPTHS)	LF	150		
21.	SAW CUT ASPHALT PAVING (VARIOUS DEPTHS)	LF	350		
22.	SAW CUT CONCRETE SIDEWALK/DRIVE (VARIOUS DEPTHS)	LF	20		
23.	CONCRETE STREET DEMOLITION INCLUDING OFF-SITE DISPOSAL	SF	441		
24.	ASPHALT PAVING DEMOLITION INCLUDING OFF-SITE DISPOSAL	SF	660		
25.	SIDEWALK DEMOLITION INCLUDING OFF-SITE DISPOSAL	SF	350		
26.	CLEARING PER PLANS	LS	1		
27.	CONCRETE STREET PATCH PER DETAIL, INCLUDING CURB	SF	441		
28.	ASPHALT PAVING PATCH PER DETAIL	SF	660		
29.	4-INCH THICK CONCRETE SIDEWALK	SF	350		
30.	WATER AND SEWER TESTING COMPLETE PER CITY OF GRIFFIN REQUIREMENTS	LS	1		
31.	VIDEO INSECTION OF EXISTING 16" D.I.P. WATER MAIN IN ENCASEMENT	LS	1		
<i>Miscellaneous Subtotal =</i>					

Item	Description	Unit	Quantity	Unit Price	Item Total
<b>OFF-SITE WATER MAIN</b>					
32.	6" CLASS 350 DIP WATER MAIN	LF	500		
33.	FIRE HYDRANT ASSEMBLY WITH 6" x 6" TEE	LS	1		
34.	10" x 6" TAPPING SLEEVE & VALVE	LS	1		
35.	6" 90° MJ BEND COMPLETE WITH CONCRETE BLOCKING	EA	1		
36.	FLUSH & CHLORINATE WATER MAIN	LS	1		
<i>Off-site Water Main Subtotal=</i>					
<b>TOTAL CONSTRUCTION=</b>					
<b>ADD ALTERNATE</b>					
1.	16" INSERTION VALVE COMPLETE	EA	1		
<i>Add Alternate Subtotal =</i>					
<b>TOTAL CONSTRUCTION=</b>					