



Addendum to Solicitation

Addendum No. RFP _____

1 03-24 Vaping Sensors Project

Here are the questions and answers that have been ask and from the pre-bid meeting/walkthrough. These are made part of the scope of work.:

(1) There are 255 blue-marked locations on the maps, but 2 additional that are shown as green and I believe should be blue. Can you confirm the expectation is 257 total sensors needed, or is there a different number expected? **Fredrick Douglas and Winburn bathrooms were mis-marked. The expectation is for 257 total sensors.**

(1.1) The 2 mis-marked are at Frederick Douglass High School, and Winburn Middle School. **Fredrick Douglas and Winburn bathrooms were mis-marked. The expectation is for 257 total sensors.**

(2) What are the ceiling types in the restrooms, and hallways between the IT Closets and Restroom/Locker Rooms at the listed schools/sites? **Drywall, drop ceilings in halls and RR's, drop ceilings and open in the closets.**

(2.1) What type of mount is expected for the Halo units? **Ceiling mount**

(2.1.1) Ceiling or Wall mounted? **Ceiling mount**

(2.1.2) If ceiling surface mounted with wire mold or conduit need to be run to them, or is the wire to be fed from the back? **wire mold is acceptable, Ceilings in restrooms are usually drywall, ceilings in hallways and some restrooms are drop in, closets are open or drop in.**

(3) What are the ceiling heights in the Restroom/Locker Rooms and in the hallways? **10'-14'**

(4) Are these sensors needing to communicate with any systems other than Audio Enhancement, and if so what systems and what are the licensing requirements? **No**

(4.1) i.e. What is the current video management system in use at Fayette County Schools, and is there an expectation that they report an alarm through that system, or any other connected systems? **Sonitrol, No**

(4.2) Do they need to operate through IPvideo cloud services directly as well? (5) Are bidders to provide the network switches in each network closet, or are these connecting to existing switches? **No**

(5.1) If bidders are providing switches – is there specification on brands or models, number of ports, etc.? **We will be connecting to existing switches that FCPS has provided.**

(5.2) Is there an available fiber back-bone connection in each IT Closet for those, or how will they connect to the IT Network for Fayette County Schools **Because FCPS is providing networking the contractors will NOT need any fiber access.**

(6) Are there existing cable standards for the network runs? **Cat6 Gray plenum cable - Open on brand needs to have 20-25 year warranty on cable.**

(6.1) Cable brand(s)? Cat 5, 5e, 6, etc.? Plenum or Non-Plenum? **Cat6 Gray plenum cable - Open on brand needs to have 20-25 year warranty on cable.**

(7) Are bidders to provide patch panels? **Yes patch panels to be provided where needed. Open slots on existing patch panels can be used but contractor must make sure any FCPS used hardware meets the standard for Cat6 through put.**

(7.1) Are there specific brands or types? **No we have many brands and types in our schools.**

(8) Installation timing: It is noted contractors have to install outside of school hours and can start at 4:35 PM each day. Is there an expected end-time each day? **The buildings auto arm at midnight.**

(8.1) Is there a limitation to how many schools or buildings can be installed at the same time? **No**

(9) For the buildings under construction (CTE Center and Mary E Britton) are there any different site expectations or timelines on the installation at those locations? **These will need to be completed closer to the school opening dates**

(10) Can CAD files be shared for measurement purposes? **We do not have CAD files for a majority of the schools listed**

Will any of this be cloud based? **Eastside, Henry Clay, STEAM, Jessie Clark, Locust Trace, MLK, Dunbar, Southside, TLC. Will need to be cloud based for the present.**

Field house drawings? **We only have 3-4. We can walk those with the winning bidder. The counts are now included.**

Recount restrooms? **This has been done and is included with the addendum.**

Number of devices per area? **2 devices per restroom, 2 per locker room.**

Except as provided in this addendum, all terms and conditions of the solicitation remain unchanged and in full force and effect. A signed copy of the addendum should be included with the bid submission or bid may not be considered.

Name of Firm

Signature

Date

Print Name and Title

		RR	LR	LR RR/ FH
B.S. MIDDLE	1865 Wickland Dr.	10	2	
B.S. Sr.	201 Eastin Rd.	14	4	FB 2LR/2RR BB 1LR/2RR
BEAUMONT	2080 Georgian Way	10	2	
CRAWFORD	1813 Charleston Dr.	8	2	
E.J.HAYES	260 Richardson Pl.	12	2	
EASTSIDE	2208 Liberty Rd.	2		
FREDRICK DOUGLASS	2118 Winchester Rd.	18	4	FB 3LR/2RR
HENRY CLAY	2100 Fontaine Rd.	12	2	FB 2LR/2RR BB 1LR/2RR
HERALD LEADER	Midland Ave.	8		
STEAM	1555 Georgetown Rd.	8	2	
JESSIE CLARK	3341 Clays Mill Rd.	10	2	
L.T.M.S.	350 N. Limestone	10	2	
LAFAYETTE	401 Reed Lane	18	2	FB 2LR/2RR BB 1LR/1RR SB 2L/1RR
LEESTOWN	2010 Leestown Rd.	10	2	
LOCUST TRACE	3591 Leestown Rd.	6		2 are in the barn
M.L.K.	2200 Liberty Rd.	4		
MORTON	1225 Bates Creek Rd.	8	2	
P.L.DUNBAR	1600 Man o'War Blvd.	14	4	FB 2LR/2RR BB 1LR/1RR
POLO CLUB		11	2	
SCAPA	400 Lafayette Pkwy.	10		
SOUTHERN MIDDLE	400 Wilson Downing Rd.	10	2	
SOUTHSIDE	1800 Harrodsburg Rd.	2		
T.C.MIDDLE	1105 Centre Pkwy.	10	2	
T.C.Sr.	1111 Centre Pkwy.	14	10	BB 2LR/2RR
THE LEARNING CENTER	475 Price Rd.	6	2	
WINBURN	1060 Winburn Dr.	10	2	
		261	54	

38

362 areas

