

**ADDENDUM NO. 1 OFFICIAL BID FORM - 5/24/2022**  
**LODGE STREET PARKING LOT IMPROVEMENTS**  
**WILSON, NC**

| DESCRIPTION  | QUANTITY | UNIT | UNIT PRICE | TOTAL |
|--|----------|------|------------|-------|
| MOBILIZATION, BOND, INSURANCE  | 1        | LS   |            |       |
| DEMO & REMOVALS, INCLUDING OFFSITE DISPOSAL  | 1        | LS   |            |       |
| EARTHWORK/FINE GRADING   | 1        | LS   |            |       |
| BARNES STREET (PIPE TRENCH) SAWCUT, REMOVE & REPLACE EXISTING ASPHALT W/ PAVEMENT PATCH (8" CABC, 3" I19.0B, 2" S9.5B) | 395      | SY   |            |       |
| BARNES STREET-REMOVE & SALVAGE EXISITNG GRANITE CURB   | 1        | LS   |            |       |
| BARNES STREET-30" CONCRETE CURB & GUTTER   | 155      | LF   |            |       |
| CONNECT TO EXISTING SD MANHOLE   | 1        | EA   |            |       |
| JUNCTION MANHOLE REPLCEMENT  | 1        | EA   |            |       |
| CATCH BASIN  | 6        | EA   |            |       |
| DROP INLET   | 1        | EA   |            |       |
| SD MANHOLE   | 2        | EA   |            |       |
| 15" RCP  | 383      | LF   |            |       |
| 18" RCP  | 338      | LF   |            |       |
| 24" RCP  | 216      | LF   |            |       |
| 3" S9.5B ASPHALT PAVING (2-LIFTS)  | 850      | TN   |            |       |
| 8" CABC STONE BASE   | 1,140    | TN   |            |       |
| ADDITIONAL PIPE TRENCH STABILIZATION STONE   | 100      | TN   |            |       |
| SELECT TRENCH BACKFILL (INCLUDES DISPOSAL OF UNSUITABLE MATERIAL)  | 500      | CY   |            |       |
| GEOGRID STABILIZATION  | 300      | SY   |            |       |
| 30" CONCRETE CURB & GUTTER   | 990      | LF   |            |       |
| CONCRETE WHEEL STOPS   | 22       | EA   |            |       |
| 4" THICK CONCRETE SIDEWALK   | 135      | SY   |            |       |
| 6" THICK CONCRETE DRIVE APRON  | 300      | SY   |            |       |
| 4" WHITE THERMOPLASTIC 90 MIL STRIPING   | 2,142    | LF   |            |       |
| THERMOPLASTIC PAVEMENT MARKING SYMBOLS   | 1        | LS   |            |       |
| ADJUST EXISTING DRAINAGE LIDS/FRAMES TO FINISH GRADE   | 6        | EA   |            |       |
| VALVE BOX ADJUSTMENTS TO FINISH GRADE  | 1        | LS   |            |       |

**ADDENDUM NO. 1 OFFICIAL BID FORM - 5/24/2022**  
**LODGE STREET PARKING LOT IMPROVEMENTS**  
**WILSON, NC**

| DESCRIPTION                                      | QUANTITY | UNIT | UNIT PRICE   | TOTAL |
|--|----------|------|--------------|-------|
| SIGNAGE(4-STOP SIGNS & REQ'D. ADA PARKING SIGNS) | 1        | LS   |              |       |
| TRAFFIC CONTROL                                  | 1        | LS   |              |       |
| TEMPORARY 25' X 50' CONSTRUCTION ENTRANCE        | 1        | EA   |              |       |
| TEMPORARY CONCRETE WASHOUT                       | 1        | EA   |              |       |
| SILT FENCE                                       | 860      | LF   |              |       |
| DRAIN INLET PROTECTION                           | 9        | EA   |              |       |
|  |          |      | <b>TOTAL</b> |       |

ONLY BIDS SUBMITTED ON THIS FORM WILL BE CONSIDERED BY THE CITY OF WILSON.

CONTRACTOR: \_\_\_\_\_

ADDRESS: \_\_\_\_\_ PHONE \_\_\_\_\_ Email \_\_\_\_\_

SIGNATURE: \_\_\_\_\_

TITLE: \_\_\_\_\_ DATE: \_\_\_\_\_

ADDENDUM NUMBERS ACKNOWLEDGED: \_\_\_\_\_