

Addendum 2

City of Canton, Ohio
Purchasing Department
218 Cleveland Ave. SW, 4th floor
Canton, Ohio 44702

18th St. SW Storm Sewer CIPP Project, GP1386

Item/Project

Engineering Department

Responsible Department

2:00:00 PM, 3/5/2024

Bids Due

Bid Proposal Submitted By:

Company Name

Street Address

City

State

Zip

Contact Person

Phone No.

Email Address

Question:

Is there a location to discharge cure water and/or emergency bypass?

Answer:

Cure water associated with non-styrene resin liners, may be discharged slowly, after cooling, to the storm sewer system. Cure water associated with styrene resin liners, may be discharged slowly, after cooling, to nearby sanitary sewer system. There is no parallel storm system for emergency bypass pumping.

Question:

I am wondering if you could send an extended storm and sanitary sewer map so we can plan for emergency rain events?

Answer:

Refer to the plans for existing storm and sanitary sewer locations.

Question:

Is there flow data available for the pipes being rehabilitated?

Answer:

Flow data is not available for the storm sewer system. The plans identify an observed flow depth of 3" in September 2022 (page 1/21). Actual flows vary seasonally and during wet weather events. The contractor is responsible for all flow control measures regardless of the amount of flow at the time of construction. All associated costs shall be included in Reference No. 2 - 48" Diameter Cured-In-Place-Pipe Liner, Per ODOT SS 899.