July 26, 2024



# NOTICE OF SOLICITATION – INVITATION TO BID: Bulloch County Board of Commissioners Engineering Department and the Office of Capital Projects

DESCRIPTION OF PROJECT: The Bulloch County Board of Commissioners is accepting sealed bids from qualified contractors for this project: FY25-CP-E02 Two Chop Road & Banks Creek Church Road Paving Project. The project is located along Two Chop Road from Rocky Ford Road to US Highway 25 for a total length of 3.052 miles and along Banks Creek Church Road from Two Chop Road to just north of the Banks Creek Church property for a total length of 0.457 miles. Project scope consists of clearing and grubbing operations, coordination and relocation of existing utilities, grading & earthwork operations, drainage work, subgrade construction, graded aggregate base construction, and asphalt paving work.

#### Addendum #1

Changes have been made to the above-mentioned bid document. The changes are as follows:

- 1. Page 3 Hussey, Gay, Bell dated June 21, 2024 and subsequently revised July 26, 2024
- Refer to the project plans produced by <u>Hussey, Gay, Bell dated June 21, 2024 and subsequently revised July 26, 2024</u>, by going to the Bulloch County website: <u>Two Chop Road & Banks Creek Church Road Plans</u>.
- 3. Attachment A has been revised. The attached Form A Bid Form must be used in the submission package or your submission will not be considered for this project.
- 4. Refer to the attached Questions & Reponses Round 4.

Signature	 Date	
Company Name	_	

Addendum #1 must be signed and included in the submitted bid.

#### ATTACHMENT A: REQUIRED FORMS

FORM A: BID FORM

0045

0050

0055

0060

0065

0070

Water Quality Inspections

Temporary Silt Fence, Type A

Temporary Silt Fence, Type C

Foundation Backfill Material, Type II

Clearing and Grubbing

**Grading Complete** 

171-0010

171-0030

201-1500

207-0203

210-0100

TO: Bulloch County Board of Commissioners

115 North Main Street Statesboro, Georgia 30458 ATTN: Procurement Manager

Proposal **Unit Price Bid Amount** Approximate Item ID Line Quantity & **Dollars and Cents Dollars and Cents** Description Number Units 109-0300 \$ 0001 **TBD TBD** Price Adjustment Asphalt Cement (+/-) 150-1000 1.00 0005 Traffic Control LS 163-0232 15.00 0010 **Temporary Grassing** AC 163-0240 30.00 0015 **Temporary Mulch** ΤN 163-0528 1,800.00 0020 Construct and Remove Fabric Check LF Dam, Type C Silt Fence 165-0010 26,000.00 0025 Maintenance of Temporary Silt Fence, LF Type A 165-0030 1,400.00 0030 Maintenance of Temporary Silt Fence, LF Type C 165-0041 Maintenance of Fabric Check 1,800.00 0035 Dam – Type C Silt Fence LF 167-1000 10.00 0040 Water Quality Monitoring and Sampling EΑ 167-1500 18.00

MO

1,400.00

LF

1.00

26,000.00

10

Proposal	Item ID Description	Approximate	Unit Price	Bid Amount
Line		Quantity &	Dollars and Cents	Dollars and Cents
Number		Units		
0075	310-5060	51,000.00		
	Graded Aggregate Base, 6 Inch,	SY		
	Including Material			
	402-3113			
0080	Recycled Asphalt Concrete, 12.5 MM	6,710.00		
	SUPERPAVE, GP 1 or 2, Including	TN		
	Bituminous Material and H Lime	F7.00		
0085	413-0750	57.00		
	Bituminous Tack Coat	GL		
0090	441-0014	35.00		
	Driveway Concrete, 4 Inch Thick	SY		
0005	500-3600	125.00		
0095	Class A Concrete, Special Design	LF		
	Concrete Header, 15 Inch X 12 Inch 500-3800			
0100	Class A Concrete, Including	63.00		
0100	Reinforcing Steel	CY		
	550-3415			
0105	Safety End Section 15 Inch, Side	16.00		
0105	Drain, 4:1 Slope	EA		
	550-3418			
0110	Safety End Section 18 Inch, Side	64.00		
0110	Drain, 4:1 Slope	EA		
	550-3424			
0115	Safety End Section 24 Inch, Side	4.00		
	Drain, 4:1 Slope	EA		
	550-4218	0.00		
0120	Flared End Section 18 Inch, Storm	8.00		
	Drain	EA		
	550-4224	4.00		
0125	Flared End Section 24 Inch, Storm	4.00 EA		
	Drain	LA		
	550-4230	4.00		
0130	Flared End Section 30 Inch, Storm	EA		
	Drain			
0135 0140	550-5150	328.00		
	Storm Drain Pipe, 15 Inch, Class III	LF		
	550-5181	1,687.00		
	Storm Drain Pipe, 18 Inch, Class III	LF		
0145	550-5240	201.00		
	Storm Drain Pipe, 24 Inch, Class III	LF		
0150	550-5300	115.00		
	Storm Drain Pipe, 30 Inch, Class III	LF		

Proposal	Item ID Description	Approximate	Unit Price	Bid Amount
Line		Quantity &	Dollars and Cents	Dollars and Cents
Number		Units		
0155	550-5600	294.00		
0155	Storm Drain Pipe, 60 Inch, Class III	LF		
	603-2180	1,300.00		
0160	Stone Dumped Rip Rap, Type 3, 12	1,300.00 SY		
	Inch	31		
	643-0010	2,220.00		
0165	Field Fence Woven Wire, Metal Posts	2,220.00 LF		
	& 3 Strands Barbed Wire			
0170	643-8050	1.00		
0170	Gate – Special Design, 20 FT	EA		
0175	643-8050	1.00		
0173	Gate – Special Design, 30 FT	EA		
	653-2501	7.00		
0180	Thermoplastic Solid Traffic Stripe, 5	LM		
	Inch, White	LIVI		
	653-2502	7.00		
0185	Thermoplastic Solid Traffic Stripe, 5	LM		
	Inch, Yellow	LIVI		
	653-1704	90.00		
0190	Thermoplastic Solid Traffic Stripe, 24	LF		
	Inch, White			
	636-1033	50.00		
0195	Highway Signs, Type 1 Material,	SF		
	Reflective Sheeting, Type 9	_		
	636-1036	96.10		
0200	Highway Signs, Type X Material,	SF		
	Reflective Sheeting, Type 9			
0205	636-2070	349.82		
	Galvanized Steel Posts, Type 7	LF		
0210	700-0001	15.00		
	Permanent Grassing Complete	AC		
0015	999-0310	1.00		
0215	Construction Material Testing	LS		
	Complete – Contractor Provided			

#### TOTAL BASE BID IN THE AMOUNT OF:

\$	
Dollars and Cents	
\$	
In Words	

All bids submitted shall be subject to acceptance or rejection and Bulloch County specifically reserves the right to accept or reject any or all bids, and to waive any technicalities or informalities in the process. The undersigned understands that any conditions stated above, clarifications made to the above or information other than that requested should be under separate cover and will be considered only at the discretion of the County Manager.

FIRM NAME:		
SIGNATURE:		
TITLE:		
ADDRESS:		
TELPHONE:		
EMAIL:		
Subscribed and sworn to before me this	day of	20
NOTARY PUBLIC		



#### Bulloch County Board of Commissioners Engineering Department and the Office of Capital Projects

**DATE:** 07/26/2024

PROJECT: FY25-CP-E02, Two Chop Road & Banks Creek Church Road Paving Project

QUESTIONS/RESPONSES: Round 4

NO.	QUESTION	RESPONSE	REMARKS			
1	The link to the Project Plans is not working.	The link to the Project Plans has been restored and resent via email 07/11/2024 4:29 PM EDT.	Issue closed.			
2	Since the bid item for Grading Complete is 1 LS, will it be possible to get a Cadd file or some cross sections that provide information for the grading scope? Cadd file will be preferred as it will allow us to create an earthwork file and get a good estimate on the earthwork quantities.	The Engineer's CADD files have been posted to Bulloch County website. Please use the below link to access the CADD files: Two Chop Road & Banks Creek Church Road CADD Files	Question closed.			
3	With the Bid Submission Date being August 1, 2024 there is a bit of an issue. GDOT does not post the August 2024 Asphalt Cement Index until sometime between August 1-5 so we will not know the AC Index for August at the time of submission. Should we use the July 2024 GDOT Asphalt Cement Index (\$606.00) as the starting Index for this project? Or will the bid due date be pushed off long enough to allow GDOT to post the August GDOT Asphalt Cement Index?	The July 2024 GDOT Asphalt Cement Index will be the Monthly Asphalt Cement Price (Georgia Base Asphalt Price) for this project. No change to Notice of Solicitation: Invitation to Bid #FY25-CP-E02.	Question closed.			
4	Can you please provide cross sections for this project?	Cross-Sections will not be provided.	Question closed.			

NO.	QUESTION	RESPONSE	REMARKS			
5	Trying to find the 4" Driveway concrete in the reference drawings without success. Can you point me to the correct sheet number where it is called out?	The only concrete driveway is located on the plans near Station 135+25 Right. The plans will be revised to reflect this change. Also, Attachment A – Bid Form will be revised to change the concrete driveway quantity to 35 SY. Addendum will be posted 07/26/2024.	Question closed.			
6	Will this project fall under the new 5% retainage requirement? Proposal has 10% listed.	No change to the Notice of Solicitation – Invitation to Bid.	Question closed.			
7	The Geotechnical Report recommends a couple of different options for subgrade soil stabilization: Undercut, Stabilization Fabric, Cement Treatment. How is any subgrade stabilization work going to be covered in the Contract? Will this work, if required, be added to the contract price?	In the event that unsuitable material is encountered during construction the provisions as outlined in Section 210-Grading Complete shall govern.	Question closed.			
8	Are there any burning restrictions related to burning the clearing debris?	The Georgia Forestry Commission regulates land clearing burns.	Question closed.			
9	The Bid Docs indicate that work must commence within 15 calendar days after the issuance of an NTP. Do you have an estimated date that the NTP will be issued?	Issuance of NTP is anticipated in mid- September 2024.	Question closed.			
10	Using the cadd file I have prepared an earthwork model used to calculate the cut/fill volumes. The volumes that I have come up with differ from those that are provided in the plans on Sheet C0.2. Should our 1 LS Grading Complete item be based on the volumes that are provided in the plans?	The quantities shown on the plans and bid form are estimated for bidding purposes only.	Question closed.			
11	The general notes advise to install prime on the GABC and reference a pay item that is not provided on the proposal. Can we wave the prime requirement or add the pay item for pricing purposes?	No change to the Notice of Solicitation – Invitation to Bid.	Question closed.			