

ADDENDUM NO. 2

| | |
|---------------------------------|--|
| DATE OF ISSUANCE: | February 3, 2022 |
| PROJECT: | Portage – Northern High School – Campus Storage Barns 1000 Idaho Avenue Portage, MI 49024 |
| OWNER: | Owner's Name |
| ARCHITECT'S PROJECT NO.: | 20-200.00 |
| ORIGINAL BID ISSUE DATE: | January 20, 2022 |

SCOPE OF WORK

This Addendum includes changes to, or clarifications of, the original Bidding Documents and any previously issued addenda, and shall be included in the Bid. All of these Addendum items form a part of the Contract Documents. The Bidder shall acknowledge receipt of this Addendum in the appropriate space provided on the Bid Form. Failure to do so may result in disqualification of the Bid.

DOCUMENTS INCLUDED IN THIS ADDENDUM

This Addendum includes **[2] two** pages of text and the following documents:

- Bidding Documents: **none.**
- Contract Conditions: **none.**
- Specification Sections: **none.**
- Drawings: **none.**

CHANGES TO PREVIOUSLY ISSUED ADDENDA

None.

CHANGES TO BIDDING REQUIREMENTS

None.

CHANGES TO CONTRACT CONDITIONS

None.

CHANGES TO SPECIFICATIONS

ADD-2 Item No. S-1 - Clarifications between specification and drawings

1. BUILDING FRAME COLUMNS SHALL BE 6X6 TREATED POSTS PER DRAWINGS
2. SKIRT BOARD SHALL BE 2X6 TREATED T&G PER DRAWINGS
3. WALL GIRTS SHALL BE 2X4 UNIFORMLY SPACES AT 24" PER DRAWINGS
4. NO BASE REINFORCEMENT REQUIRED
5. PROVIDE CONCRETE SLAB REINFORCING (INTERIOR): WWF 6X6-W1.4XW1.4 WWF, NONE ON EXTERIOR CONCRETE.
6. PROVIDE CONCRETE PIER REINFORCING PER DRAWINGS: SIX (6) VERTICAL #5 BARS AND #4 STIRRUPS SPACED AT 12"
7. VAPOR RETARDER IN WALLS IS NOT REQUIRED
8. VAPOR RETARDER UNDER FLOOR SLAB IS REQUIRED
9. FLOOR SLAB, OMIT HARDENER SPECIFIED IN 32 1313, PROVIDE FLOOR TREATMENT PER 03 3000
10. OWNER WILL PROVIDE CONSTRUCTION TESTING SERVICES

CHANGES TO DRAWINGS

None.

END OF ADDENDUM.