

## ADDENDUM

**Posted Date:** March 1, 2024

**Solicitation No.:** 24-51

**Solicitation Name:** Cable Infrastructure Installation for Tyner Middle High School

**Subject:** Addendum Number 2

The following represents clarification, additions, deletions, and/or modifications to the above referenced solicitation. This addendum shall hereafter be regarded as part of the solicitation. Items not referenced herein remain unchanged, including the response date. Words, phrases, or sentences with a strikethrough represent deletions to the original solicitation. Underlined words and bolded phrases or sentences represent additions to the original solicitation.

1. **ATTACHMENT: NONE**

2. **QUESTIONS/ANSWERS**

1.	Page 9 states that Errors and Omissions insurance is required. This is typically only required for architects and engineers who are doing design builds. Can this requirement be waived if all other insurance requirements are met?
<b>Answer</b>	<b>Yes, Not necessary for this work</b>

2.	Section 2.6B states "The contractor must minimize and coordinate downtime of the existing network equipment when performing this work." Can more detail be given on exactly what is expected? Is the goal to have the old and new networks running simultaneously?
<b>Answer</b>	<b>Will not pertain to this work. This will be HCS IT responsibility</b>

3.	2.6F states that "All Sleeves and wall penetrations shall be installed w/fire stop & bushings." In the past, the electrical firm furnished and installed EZ Paths going into each room. Is this section stating that the LV vendor is responsible for supplying all of the EZ Paths or is this referring to any sleeves needed other than the EZ Paths?
<b>Answer</b>	<b>There maybe a few instances of a need, other than a EZ Path, like a small sleeve, or fire caulking. The electrical GC is still required to supply and install from the General Contract</b>

4.	Is a bid or performance bond required for this project?
<b>Answer</b>	<b>If not stated in the RFP, then none is required</b>

5.	Is any demolition or removal of any existing cabling required
<b>Answer</b>	<b>No demolition is involved</b>

6.	On E.321 Both markups and the E prints show "WAP" on the walls, however, the WAP cable is marked not on the walls. Where do those cables need to go? On the wall or extended out from the wall?
----	---

---

<b>Answer</b>	IGNORE THE FULL BID PRINTS WAP markings, These will need to go where they are located as the dots on the MARKUP print
---------------	---

7.	Which drawing takes priority in the case of discrepancies? The markup provided or the "Full Bid Prints"?
<b>Answer</b>	THE MARKUP; full bid prints were for footage /pathway only

8.	What type of fiber do we need to use as the backbone between IDFs? OM3 or OS1? The specifications are telling us two separate things.
<b>Answer</b>	OM3 is the backbone, OS1 is for video distribution btw closets..

9.	Do all the cat6A cables need to be terminated on cat6A jacks? The spec is saying they should be terminated on cat6
<b>Answer</b>	YES Cat6A jacks for Cat6A cable

---

**BIDDER/PROPOSER IS ADVISED, YOU ARE REQUIRED TO ACKNOWLEDGE RECEIPT OF THIS ADDENDUM WHEN SUBMITTING A BID/PROPOSAL. FAILURE TO COMPLY WITH THIS REQUIREMENT MAY RESULT IN THE BIDDER/PROPOSER BEING CONSIDERED NON-RESPONSIVE.**

**ALL OTHER TERMS AND CONDITIONS OF THE SOLICITATION DOCUMENTS ARE AND SHALL REMAIN THE SAME.**

*Steven Hodgen*

---

Steven Hodgen  
Purchasing Supervisor