



CITY OF CONROE

Est. 1904

City of Conroe
PO Box 3066
Conroe, Texas 77305

ADDENDUM NO. 3

DATE ISSUED: 4/12/2021

PROJECT NAME: 0408-2021 Network Cabling – Conroe Central Waste Water Treatment Plant

This revision shall be considered part of the contract documents for the above named project, and shall be incorporated integrally with the previously issued documents. Wherein provisions of the revisions differ from the provisions of the original documents and/or the provisions of previously issued addendum, the provisions of this revision shall govern and take precedence.

See attached Q&A. This will be the last addendum for this project. Q&A is cutoff for this project.

By the signature affixed below, Addendum No. 3 is hereby incorporated into and made a part of the above referenced solicitation.

ACKNOWLEDGED:

Authorized Signature

Printed Name

Respondent/Contractor

Date

Kristina Colville, Purchasing manager

Questions Network Cabling bid for Conroe Central Wastewater Treatment Plant RFP v3

4/12/21

Scope Clarification Questions

- If all (5) cable runs do not homerun back to #1 Admin Building, do Cable Run (1) and (2) Terminate at #1 Admin Building and Cable Runs (3), (4) and (5) Terminate at #4 Maint Building with a backbone 12ct from #4 Maint Building to #1 Admin Building?
 - Yes

- How many (LC, SMF, 1GB) Media Converters is the contractor required to provide?
 - There should be a minimum of 8 converters in the maintenance building (pg 11 of the RFP).

- It looks like it would require (8) remote media converters and would these need to be hardened for outdoor J-Boxes?
 - J-Box media converters are provided by the security contractor.

- There are (5) cable Runs. Do all (5) cable runs homerun back to #1 Admin Building?
 - No. The fiber run from #1 to #4 (red on attached drawing) connects the Admin building to the Maintenance building. All fiber runs from #4 - #18 (green and blue on the attached drawing) will terminate in the Maintenance building.

- Termination panel details
 - 3 (12) strand termination panels in the Maintenance bldg. or can use 1 (36).
 - 3 (12) strand termination panels in the Administration bldg. or can use 1 (36).