

City of Tallmadge
Department of Public Service
2019 Concrete Maintenance & Repair

Addendum No. 1 to Bidding Documents

March 22, 2019

This addendum is for Item J, #1 in Bid Specifications (page 27). Item J, # 1 shall read:

J. ITEM 452 - 8" NON-REINGORCED CONCRETE PAVEMENT

1. DESCRIPTION:

This work includes the furnishing of all labor, material, tools, and equipment necessary to remove and replace 8" thick non-reinforced PCC pavement in the locations designated in the bid as instructed by the City of Tallmadge inspector. Also included in this item is the installation 4" thick 304 limestone aggregate base. Integral curb shall be included in this item. All joint locations, reinforcement and hook bolt placement shall be approved by the City of Tallmadge inspector prior to ordering concrete. This item shall conform to the same requirements prescribed in ODOT CMS Item 451 with the exceptions in ODOT CMS 452. All concrete installed in this Item shall be moderate setting (MS) concrete.

This addendum is for Item P, #1 in Bid Specifications (page 29). Item P, # 1 shall read:

P. ITEM 712.14 - DETECTABLE WARNING DEVICE

1. DESCRIPTION:

This work includes the excavation, removal, forming, placing and finishing, and curing curb ramps per the current version of ODOT CMS and Federal and State ADA requirements (ADA Wheelchair Ramp).

This work includes the placing and finishing of DETECTABLE WARNING DEVICES for handicap curb ramps per the current version of ODOT CMS and Federal and State ADA requirements.

I acknowledge the receipt of Addendum No. 1:

Company Name

Officer's Name

Officer's Signature

Date

THIS COMPLETED FORM MUST BE SUBMITTED WITH BID PROPOSAL