

ALBANY AVENUE
WIDENING AND RESURFACING
TRANSPORTATION INVESTMENT ACT OF 2010
PROJECT SGRC-153, P.I. 0016312
CONTRACT ID: IGTIA2000541

CITY OF WAYCROSS, GEORGIA
BID NO. FY 21-17

BIDS DUE March 30, 2021; 2:00 PM Local Time

ADDENDUM NO. 3
March 25, 2021
12:00 NOON

THE PLANS, SPECIFICATIONS AND BIDDING DOCUMENTS FOR THE PROJECT NAMED ABOVE ARE HEREBY AMENDED AS DESCRIBED ON THE FOLLOWING PAGES. THE BIDDER MUST ACKNOWLEDGE RECEIPT OF THIS ADDENDUM IN THE SPACES PROVIDED ON THE BID FORM. FAILURE TO DO SO MAY RESULT IN REJECTION OF THE BID.

CLARIFICATIONS

The bid Opening will be held at the time and place previously provided in the 1st Floor commission chambers of the Waycross City Hall.

The following clarification is offered in response to a question received since the non-mandatory Pre-Bid Meeting:

Question: Is the long line striping paint? I'm assuming all the handwork is thermoplastic. The roadway striping is usually paint unless it specifies thermoplastic.

Response: See Specification Section 02761 titled "PAVEMENT MARKINGS" Page 2 of 4 which seems clear on this – all linework is paint. The stop bars can be thermoplastic.

SPECIFICATIONS

SECTION 00200 INSTRUCTIONS TO BIDDERS

On Page 2 of 4 under paragraph 5.0 titled "BID FORM"

Delete the last sentence which reads:

Bidders are requested to review bid alternates, if any, as outlined on the bid form.

Substitute the following in its place:

Bidders shall enter a bid price for all items indicated on the bid form including alternates.

On **Page 4 of 4** under the paragraph 9.0 titled **“CONTRACT TIME”**

Delete the paragraph which reads:

All work associated with Divisions 1 and 2 must be completed within 270 consecutive calendar days from receipt of written Notice to Proceed. All work associated with Division 2 (if awarded separately) must be completed within 210 consecutive calendar days from receipt of written Notice to Proceed.

Substitute the following in its place:

All work associated with Divisions 1 and 2 must be completed within 360 consecutive calendar days from receipt of written Notice to Proceed. The Notice to Proceed for Division One may be delayed until such time as Division Two work has progressed to the point that allows Division One work to proceed without hindrance.

SECTION 00410 BID FORM

Delete this section in its entirety and insert SECTION 00410 (Revised per Addendum No. 3) attached herewith in its place.

SECTION 01110 SUMMARY OF WORK

On Page 1 of 2 under paragraph 1.1 titled **“DESCRIPTION”**

Delete the last paragraph which reads:

*All work associated with Divisions 1 and 2 must be completed within **270** consecutive calendar days. All work associated with Division 2 (if awarded separately) must be completed within **210** consecutive calendar days from receipt of written Notice to Proceed. If Division 2 is awarded separately, the Division 1 Notice to Proceed may be delayed up to 210 days or until completion of Division 2. In such instance the time for completion of Division 1 would be 60 days from receipt of written Notice to Proceed.*

Substitute the following in its place:

All work associated with Divisions 1 and 2 must be completed within 360 consecutive calendar days from receipt of written Notice to Proceed. The Notice to Proceed for Division One may be delayed until such time as Division Two work has progressed to the point that allows Division One work to proceed without hindrance.

SECTION 01150 SPECIAL PROVISIONS

On Page 1 of 4 under paragraph 1.3 titled **“PROJECT SCHEDULE”**

Delete the first paragraph which reads:

*All work associated with Divisions 1 and 2 must be completed within **270** consecutive calendar days. All work associated with Division 2 (if awarded separately) must be completed within **210** consecutive calendar days from receipt of written Notice to Proceed. If Division 2 is awarded separately, the Division 1 Notice to Proceed may be delayed up to 210 days or until completion of Division 2. In such instance the time for completion of Division 1 would be 60 days from receipt of written Notice to Proceed.*

Substitute the following in its place:

All work associated with Divisions 1 and 2 must be completed within 360 consecutive calendar days from receipt of written Notice to Proceed. The Notice to Proceed for Division One may be delayed until such time as Division Two work has progressed to the point that allows Division One work to proceed without hindrance.

SECTION 02510 WATER DISTRIBUTION

On Page 7 of 16 under sub-paragraph 2.5.1 titled **“Gate Valves”**

In the first paragraph add **AVK** as an acceptable manufacturer of gate valves along with **Mueller and M&H**.

On Page 7 of 16 under sub-paragraph 2.5.2 titled **“Fire Hydrants”**

In the last paragraph add **AVK** as an acceptable manufacturer of fire hydrants along with **Mueller and M&H**.

ATTACHMENTS

SPECIFICATION SECTION 00410 – BID FORM (REVISED PER ADDENDUM NO. 3)

END OF ADDENDUM NO. 3

SECTION 00410
BID FORM
BID NO. FY 21-17
ALBANY AVENUE WIDENING AND RESURFACING
TRANSPORTATION INVESTMENT ACT OF 2010
PROJECT SGRC-153, P.I. 0016312
CONTRACT ID: IGTA2000541

WAYCROSS, GEORGIA

SUBMITTED TO:

City of Waycross
417 Pendleton Street
Waycross, Georgia 31502

SUBMITTED BY:

Company Name:

Address:

Georgia Utility Contractor's License Number:

Acknowledge Receipt of Addenda Numbers:

The undersigned as **BIDDER** hereby declares that the only person or persons interested in the Proposal as principal or principals is or are named herein and that no other person than herein mentioned has any interest in the proposal or in the Contract to be entered into; that this Proposal is made without connection with any other person or parties making a Proposal, and that it is in all respects fair and in good faith without collusion or fraud.

The **BIDDER** declares that he has examined the site of the work and informed himself fully regarding all conditions pertaining to the place where the work is to be done; that he has examined the plans and specifications for the work and the documents relative thereto; and has read all General Conditions, and Supplementary Conditions furnished prior to the opening of bids; that he has satisfied himself relative to the work to be performed.

The **BIDDER** proposes and agrees, if the Proposal is accepted, to contract with the **City of Waycross, Georgia** to furnish all necessary materials, equipment, machinery, tools, apparatus, means of transportation and labor to complete the work in full and complete accordance with the shown, noted, described and reasonably intended requirements of the plans, specifications and contract documents to the full and entire satisfaction of the **City of Waycross, Georgia** with a definite understanding that no

money will be allowed for extra work except as set forth in the attached General Conditions and contract documents for the prices set forth on the following pages.

DIVISION 1 – STREET RESURFACING

Furnish all labor, materials, and equipment necessary for street resurfacing beginning at the intersection of Plant Avenue and continuing west along **Albany Avenue** approximately **7,100 LF** to the Waycross City Limits east of Waller Street. More specifically the work of **Division 1** includes, but is not limited to, mobilization/demobilization; asphalt milling and re-surfacing; grade adjustments at affected manhole and valve box covers; traffic control; pavement markings; raised reflective pavement markers and stop bars; complete surface restoration; and all other work and appurtenances required for the following prices:

ITEM	QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL PRICE
1.1			STREET RESURFACING		
a	31500	SY	Full Width Variable Depth Asphalt Milling (2.5" Minimum)	\$	\$
b	29250	SY	Bituminous Single Surface Treatment	\$	\$
c	4730	TNS	12.5 mm HMA SuperPave	\$	\$
d	1800	GAL	Bituminous Tack Coat	\$	\$
e	15900	LF	5" Single Solid White Pavement Stripe	\$	\$
f	6970	LF	5" Single Solid Yellow Pavement Stripe w/Raised Pvmt Markers	\$	\$
g	3280	LF	5" Double Yellow Solid Pavement Stripe w/Raised Pvmt Markers	\$	\$
h	7100	LF	5" Skip Yellow Stripe 10' Seg 30' Gap w/Raised Pvmt Markers	\$	\$
i	400	LF	5" Skip White Stripe 2' Seg 6' Gap	\$	\$
j	450	LF	24" Wide Solid White Thermoplastic Stop Bar	\$	\$
k	40	LF	5" Skip White Stripe 10' Seg 30' Gap w/Raised Pvmt Markers	\$	\$
l	3	EA	Railroad Crossing Pavement Markings	\$	\$
m	425	SY	GDOT T-11A Pedestrian Crosswalk Markings	\$	\$
n	22	EA	GDOT T-12B Turn Arrows	\$	\$
o	65	SY	Cross Hatching GDOT T-14 Diagonal Yellow Detail B	\$	\$
p	1	EA	GDOT T-13A Type 1 Pavement Marking Words	\$	\$
q	24	EA	Adjust Existing Valve Box Covers to Match New Pavement	\$	\$
r	2	EA	Traffic Loop Connection & Restoration	\$	\$
s	7	EA	Adjust Existing SSMH Covers to Match New Pavement	\$	\$
SUB-TOTAL DIVISION 1 ITEM 1.1 – STREET RESURFACING					\$

ITEM	QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL PRICE
1.2			EXTRA WORK IF ORDERED BY OWNER		
a	100	SY	Remove & Replace Concrete Sidewalk	\$	\$
b	100	SY	Remove & Replace Concrete Driveway	\$	\$
c	100	LF	Remove & Replace Concrete Curb & Gutter or Valley Gutter	\$	\$
d	30	SY	Complete Asphalt & Subgrade Repair	\$	\$
e	1	EA	Rebuild Catchbasin Top & Throat	\$	\$
SUB-TOTAL DIVISION 1 ITEM 1.2 – EXTRA WORK IF ORDERED BY OWNER					\$

TOTAL AMOUNT OF BID - DIVISION 1 BID ITEMS 1.1 THROUGH 1.2	\$

Dollars	

DIVISION 1 – DEDUCTIVE ALTERNATIVE

If the OWNER provides the necessary labor and equipment to collect from the jobsite, transport and keep the asphalt millings, the Bidder agrees to provide the following deduct from the total amount bid for Division 1:

TOTAL AMOUNT OF DEDUCTION:	\$

Dollars	

The **BIDDER** understands that items listed under **ITEM 1.2 – EXTRA WORK IF ORDERED BY OWNER** are intended to provide a basis of payment for performance of any work required or correcting work associated with any unforeseen circumstances encountered during construction and are to be performed only upon the written authorization of the **OWNER**. The **BIDDER** must enter a price for each line item and for the Division 1 Deductive Alternate

DIVISION 2 – DRAINAGE, WATER DISTRIBUTION AND SANTARY SEWER IMPROVEMENTS

Furnish all labor, materials, and equipment necessary for constructing drainage, water distribution and sanitary sewer improvements beginning at the intersection of Plant Avenue and continuing west along **Albany Avenue** approximately **7,100 LF** to the Waycross City Limits east of Waller Street. More specifically the work of Division 2 includes, but is not limited to, mobilization/demobilization; traffic control; demolition of existing storm and sanitary sewer systems; removal and replacement of damaged curb & gutter and sidewalks; installation of new concrete curb & gutter and valley gutters; installation of ADA

compliant curb ramps; installation of approximately 50 new storm drain structures; installation of approximately 2500 LF of new RCP storm drain pipe ranging in size from 125" to 30"; installation of approximately 5950 LF of new 8" PVC water main with related valves, fittings and appurtenances; installation of approximately 3200 LF of new 8" and 10" PVC sewer mains with associated manholes and appurtenances; re-establishment of water and sewer services; complete surface restoration; and all other work and appurtenances required, for the following prices:

-CONTINUED ON FOLLOWING PAGE-

ITEM	QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL PRICE
2.1			DRAINAGE IMPROVEMENTS		
a	1850	LF	Saw Cut and Remove Existing Concrete Curb & Gutter	\$	\$
b	1500	SY	Saw Cut and Remove Existing Asphalt Pavement	\$	\$
c	450	SY	Saw Cut and Remove Existing Concrete Sidewalk/Driveway	\$	\$
d	31	EA	Remove Existing Drainage Structure	\$	\$
e	65	LF	Remove Existing 12" Clay Pipe Culvert	\$	\$
f	50	LF	Remove Existing 12" CMP Culvert	\$	\$
g	120	LF	Remove Existing 12" RCP Culvert	\$	\$
h	60	LF	Remove Existing 15" Clay Pipe Culvert	\$	\$
i	360	LF	Remove Existing 15' RCP Culvert	\$	\$
j	75	LF	Remove Existing 18" CMP Culvert	\$	\$
k	450	LF	Remove Existing 18" RCP Culvert	\$	\$
l	6	EA	Cut & Plug Existing 15" RCP Culvert to be Abandoned	\$	\$
m	1	EA	Cut & Plug Existing 24" RCP Culvert to be Abandoned	\$	\$
n	1	EA	Connect New 18" RCP Culvert to Existing Curb Inlet	\$	\$
o	4100	LF	Install New Concrete Curb & Gutter	\$	\$
p	750	SY	Install New Concrete Sidewalk/Driveway	\$	\$
q	4000	LF	Install New Concrete Valley Gutter	\$	\$
r	29	EA	Install New ADA Compliant Curb Ramps	\$	\$
s	15	LF	Install New 12" RCP Culvert	\$	\$
t	330	LF	Install New 15" RCP Culvert	\$	\$
u	290	LF	Install New 12" x 18" Elliptical RCP Culvert W/4" Conc Encasement	\$	\$
v	710	LF	Install New 18" RCP Culvert	\$	\$
w	1020	LF	Install New 24" RCP Culvert	\$	\$
x	350	LF	Install New 30" RCP Culvert	\$	\$
y	25	EA	Install New Type 1 Curb Inlet	\$	\$
z	4	EA	Install New Type 2 Curb Inlet	\$	\$
aa	8	EA	Install New Type 3 Curb Inlet	\$	\$
bb	1	EA	Install New Type 1 Junction Box	\$	\$
cc	4	EA	Install New Type 2 Junction Box	\$	\$
dd	3	EA	Install New Type 1 Gutter Inlet	\$	\$
ee	1	EA	Install New Type 2 Gutter Inlet	\$	\$
ff	3	EA	Install New Drop Inlet	\$	\$
gg	1	EA	Install New 15" GDOT Standard 1120 Flared End Section	\$	\$
SUB-TOTAL DIVISION 2 ITEM 2.1 – DRAINAGE IMPROVEMENTS					\$

ITEM	QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL PRICE
2.2			WATER DISTRIBUTION IMPROVEMENTS		
a	25	EA	Cut and Plug Existing 4" Pipe to be Abandoned	\$	\$
b	1	EA	Cut and Plug Existing 6" Pipe to be Abandoned	\$	\$
c	2	EA	Connect New 8" PVC to Existing 12"	\$	\$
d	1	EA	Connect New 8" PVC to Existing 10"	\$	\$
e	1	EA	Connect New 8" PVC to Existing 6"	\$	\$
f	2	EA	Connect New 8" PVC to Existing 8"	\$	\$
g	10	EA	Connect New 6" PVC to Existing 6"	\$	\$
h	2	EA	Connect New 4" PVC to Existing 4"	\$	\$
i	5950	LF	Install New 8" AWWA C900 PVC Water Main w/Harness Restraints	\$	\$
j	80	LF	Install New 8" Ductile Iron Water Main w/Harness Restraints	\$	\$
k	265	LF	Install New 6" AWWA C900 PVC Water Main w/Harness Restraints	\$	\$
l	100	LF	Install New 4" AWWA C900 PVC Water Main w/Harness Restraints	\$	\$
m	1615	SY	Remove and Replace Asphalt Base and Pavement	\$	\$
n	39	EA	Re-Establish Long Side Water Services	\$	\$
o	43	EA	Re-Establish Short Side Water Services	\$	\$
p	2	EA	Install New 4" MJ Gate Valve & Valve Box	\$	\$
q	8	EA	Install New 6" MJ Gate Valve & Valve Box	\$	\$
r	34	EA	Install New 8" MJ Gate Valve & Valve Box	\$	\$
s	5	EA	Remove Existing Fire Hydrant Assemblies	\$	\$
t	5	EA	Re-Connect Existing Fire Hydrant Assemblies to New 8" Main	\$	\$
u	5	EA	Install New Fire Hydrant Assemblies	\$	\$
v	5	EA	Install 8"x8" MJ Tee with Restrained Joints	\$	\$
w	1	EA	Install 8"x6" MJ Cross with Restrained Joints	\$	\$
x	8	EA	Install 8"x6" MJ Tee with Restrained Joints	\$	\$
y	2	EA	Install 8"x4" MJ Tee with Restrained Joints	\$	\$
z	33	EA	Install 8" MJ 45° Bend with Restrained Joints	\$	\$
aa	1	EA	Install 6" MJ 45° Bend with Restrained Joints	\$	\$
bb	2	EA	Install 4" MJ 45° Bend with Restrained Joints	\$	\$
cc	3	EA	Install 8" MJ Sleeve with Restrained Joints	\$	\$
dd	10	EA	Install 6" MJ Sleeve with Restrained Joints	\$	\$
ee	4	EA	Install 4" MJ Sleeve with Restrained Joints	\$	\$
ff	1	LS	Testing and Disinfection	\$	\$
SUB-TOTAL DIVISION 2 ITEM 2.2 – WATER DISTRIBUTION IMPROVEMENTS					\$

ITEM	QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL PRICE
2.3A			SANITARY SEWER IMPROVEMENTS – EXCAVATE & REPLACE		
a	435	LF	Heavy Clean & CCTV Existing 8" Sewer	\$	\$
b	3200	LF	Remove Existing 8" VCP Sewer Conflicting w/New Sewer	\$	\$
c	7	EA	Remove Existing SSMH	\$	\$
d	13	EA	4'-0" Diameter Standard Precast Manhole Base	\$	\$
e	1	EA	4'-0" Diameter Precast Outside Drop Manhole Base	\$	\$
f	85	LF	4'-0" Diameter Precast Manhole Riser Section	\$	\$
g	14	EA	Cast Iron Manhole Frame and Cover	\$	\$
h	4	EA	Re-Connect Existing 8" Sewer to New SSMH	\$	\$
i	2	EA	Re-Connect Existing 10" Sewer to New SSMH	\$	\$
j	1	EA	Connect New 8" SDR-26 PVC Sewer to Existing 8" PVC Sewer	\$	\$
k	2	EA	Connect New 8" SDR-26 PVC Sewer to Existing 8" VCP Sewer	\$	\$
l	82	EA	Re-Establish Sewer Services	\$	\$
m	130	LF	8" SDR-26 PVC Sewer Main 0' to 6' Cut	\$	\$
n	60	LF	10" SDR-26 PVC Sewer Main 0' to 6' Cut	\$	\$
o	1300	LF	10" SDR-26 PVC Sewer Main 6' to 8' Cut	\$	\$
p	1710	LF	10" SDR-26 PVC Sewer Main 8' to 10' Cut	\$	\$
q	1	EA	Storm Sewer Conflict Box (36" RCP)	\$	\$
r	2840	SY	Remove & Replace Asphalt Base and Pavement	\$	\$
s	130	LF	CCTV Inspection of New 8" PVC Sewer	\$	\$
t	3070	LF	CCTV Inspection of New 10" PVC Sewer	\$	\$
u	1	LS	Low Pressure Air Testing	\$	\$
SUB-TOTAL DIVISION 2 ITEM 2.3A – SANITARY SEWER IMPROVEMENTS – EXCAVATE & REPLACE					\$

-CONTINUED ON FOLLOWING PAGE-

ITEM	QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL PRICE
2.3B			SANITARY SEWER IMPROVEMENTS – PIPE BURST & REHAB		
a	435	LF	Heavy Clean & CCTV Existing 8" Sewer	\$	\$
b	3200	LF	Pipe Burst from Existing 8" VCP to 10" with HDPE Pipe	\$	\$
c	82	EA	Re-Establish Sewer Services	\$	\$
d	12	EA	Point Repairs	\$	\$
e	14	EA	Clean, Line & Coat Existing SSMH	\$	\$
f	14	EA	Replace Existing Manhole Frames & Covers	\$	\$
g	3100	LF	CCTV Inspection of New 10" HDPE Sewer	\$	\$
h	1	LS	By-Pass Pumping	\$	\$
SUB-TOTAL DIVISION 2 ITEM 2.3B – SANITARY SEWER IMPROVEMENTS – PIPE BURST & REHAB					\$

ITEM	QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL PRICE
2.4			EROSION AND SEDIMENT CONTROL		
a	3700	SY	Disturbed Area Stabilization – Type Ds1, Ds2, & Ds3	\$	\$
d	3170	LF	Silt Fence – Type Sd1-NS	\$	\$
c	44	EA	Inlet Protection – Sd2	\$	\$
d	3	EA	Storm Drain Outlet Protection - St	\$	\$
SUBTOTAL DIVISION 2 BID ITEM 2.4 – EROSION AND SEDIMENT CONTROL					\$

ITEM	QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL PRICE
2.5			EXTRA WORK IF ORDERED BY OWNER		
a	5	EA	Relocate Existing Water Meter	\$	\$
d	40	EA	Sewer Service Cleanouts at Property Line	\$	\$
c	1	EA	Rebuild Catch Basin Top and Throat	\$	\$
d	1	LS	Utility Relocation Allowance		\$ 100,000.00
SUBTOTAL DIVISION 2 BID ITEM 2.5 - EXTRA WORK IF ORDERED BY OWNER					\$

TOTAL AMOUNT OF BID - DIVISION 2 USING BID ITEMS 2.1, 2.2, 2.3A, 2.4 and 2.5 <hr style="border: 0; border-top: 1px solid black; margin-bottom: 5px;"/> <hr style="border: 0; border-top: 1px solid black; margin-bottom: 5px;"/> <div style="text-align: right; margin-bottom: 5px;">Dollars</div>	\$
---	----

TOTAL AMOUNT OF BID - DIVISION 2 USING BID ITEMS 2.1, 2.2, 2.3B, 2.4 and 2.5 <hr style="border: 0; border-top: 1px solid black; margin-bottom: 5px;"/> <hr style="border: 0; border-top: 1px solid black; margin-bottom: 5px;"/> <div style="text-align: right; margin-bottom: 5px;">Dollars</div>	\$
---	----

The **BIDDER** understands that items listed under **ITEM 2.5 – EXTRA WORK IF ORDERED BY OWNER** are intended to provide a basis of payment for performance of any work required or correcting work associated with any unforeseen circumstances encountered during construction and are to be performed only upon the written authorization of the **OWNER**. The **BIDDER** must enter a price for each line item. The Owner reserves the right to select either item **2.3A** or **2.3B**.

The **BIDDER** agrees to perform all work for the unit price or lump sum prices stated above. Items of work not listed but required for a complete installation shall be included in the price of related items. The **BIDDER** further agrees and understands that the quantities shown for unit price items are approximate and, as such, are subject to either increase or decrease, and that the **BIDDER** will be paid for actual quantities installed at the unit prices stated in the bid form. Lump sum prices stated above are subject to increase or decrease only by a properly executed change order.

Bidders may bid Division 1 only, Division 2 only, or both Divisions 1 and 2. The **BIDDER** understands that City of Waycross reserves the right to delete one or more Bid Items for the purpose of making an award; the right to award each division independently; the right to select either item **2.3A** or **2.3B** under Division 2 and the right to reject any or all bids including without limitation, the right to reject any or all nonconforming, nonresponsive, unbalanced or conditional Bids; and to make an award in the best interest of the City of Waycross.

The **BIDDER** further proposes and agrees to commence work under this contract, with adequate force and equipment, on a date to be specified in a written order of the Owner. All work associated with Divisions 1 and 2 must be completed within **360** consecutive calendar days. If Division 2 is awarded separately, the successful Bidder for Division 1 understands that a Division 1 Notice to Proceed may be delayed until such time as Division 2 work has progressed to the point that allows Division 1 work to proceed without hindrance and agrees to hold pricing for 360 days.

The undersigned **BIDDER** further agrees that, in case of failure on his part to execute the said Contract and Bonds within fifteen (15) consecutive calendar days after written notice being given of the award of the Contract, the check or bid bond accompanying this Bid and the monies payable thereto, shall be paid

into the funds of the *City of Waycross, Georgia* as liquidated damages for such failure, otherwise, the check or bid bond accompanying this Bid shall be returned to the undersigned.

The undersigned agrees to abide by all conditions of this Advertisement for Bids and certifies that he/she is authorized to sign this Bid for the **BIDDER**.

This the _____ day of _____, 2021.

Company Name (Please type or Print):

Person Authorized to Sign:

Name: _____

Name: _____

Street: _____

Signature: _____

City: _____

Title: _____

State: _____ Zip: _____

Telephone: _____

Fax: _____

E-Mail: _____

RELEVANT PROJECT EXPERIENCE:

Please provide relevant project experience information on the following page. Project experience should be reflective of the work proposed under this contract. Please limit projects to those completed within the past ten (10) years and provide all information requested. Do not list more than three (3) relevant projects.

NAME OF PROJECT: _____

DESCRIPTION OF WORK PERFORMED: _____

CONTRACT AMOUNT: _____

COMPLETION DATE: _____

OWNER'S NAME AND CONTACT: _____

ENGINEER'S NAME AND CONTACT: _____

NAME OF PROJECT: _____

DESCRIPTION OF WORK PERFORMED: _____

CONTRACT AMOUNT: _____

COMPLETION DATE: _____

OWNER'S NAME AND CONTACT: _____

ENGINEER'S NAME AND CONTACT: _____

NAME OF PROJECT: _____

DESCRIPTION OF WORK PERFORMED: _____

CONTRACT AMOUNT: _____

COMPLETION DATE: _____

OWNER'S NAME AND CONTACT: _____

ENGINEER'S NAME AND CONTACT: _____