



Georgetown County, South Carolina

129 Screven Street, Suite 239
Post Office Drawer 421270
Georgetown, SC 29442-4200
(843) 545-3083 • Fax (843) 545-3500
E-Mail • JBullard@gtcounty.org
Website • <http://www.gtcounty.org>

ADDENDUM #3 TO BID #22-022

BID NUMBER: 22-022

ISSUE DATE: Wednesday, July 6, 2022

OPENING DATE: Wednesday, July 13, 2022

OPENING TIME: 3:00 PM

Pre-Bid Site Inspection: [Independent – On Own]

PROCUREMENT FOR: User Fee Road Construction – Corner Loop, Belladonna Court, Kidneywood Way, & Soldierwood Lane

This addendum will amend **RFP #22-022, User Road Construction-Corner Loop, Belladonna Court, Kidneywood Way, & Soldierwood Lane** originally issued on Wednesday, June 15, 2022. This clarification is being provided to all known and registered correspondents in response to questions received. All addenda and original bid documents are also available online at: www.gtcounty.org, select “Bid Opportunities” from the Quick Links section.

Question 1: Regarding the Unit Price Schedule, there is a group of items and quantities at the bottom that do not have a road name listed. I assume these were included in error. They show up in the Excel and the Specifications?

Response: Yes the last table was included in error. Please use the "Grand Total" box to sum up all costs on the Unit Price Schedule. Attached is the revised excel version as well.



ADDENDUM ACKNOWLEDGEMENT

BID #22-022

User Road Construction-Corner Loop, Belladonna Court, Kidneywood Way, & Soldierwood Lane Submittal Form

To be returned with the final proposal submission to Georgetown County.

COMPANY NAME: _____

- Addendum #1 Received Date: _____ Initialed By: _____
- Addendum #2 Received Date: _____ Initialed By: _____
- Addendum #3 Received Date: _____ Initialed By: _____
- Addendum #4 Received Date: _____ Initialed By: _____
- Addendum #5 Received Date: _____ Initialed By: _____
- Addendum #6 Received Date: _____ Initialed By: _____

Georgetown County
Corner Loop and Belladonna Court & Kidneywood Way and Soldierwood Lane Paving
Project

As of: 7/6/22

Construction Cost Estimate

<u>Item No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Units</u>	<u>Unit Price</u>	<u>Total Price</u>
Corner Loop					
1031000	Mobilization	1	LS		
1050800	Construction Stakes, Lines & Grades	1	EA		
1050810	As-Built Surveys	1	LS		
1052000	Utility Relocation Allowance	1	LS	\$10,000.00	\$10,000.00
1071000	Traffic Control	1	LS		
2012000	Clearing & Grubbing within Roadway	3.3	ACRE		
2031000	Unclassified Excavation	1,919	CY		
2033000	Contingent Borrow Excavation	365	CY		
2034000	Contingent Muck Excavation	146	CY		
2036000	Contingent Geotextile for Separation of Subgrade & Subbase	146	SY		
2037010	Contingent Geogrid Reinforcement (Biaxial)	146	SY		
2052010	Contingent Stone Bridge Lift Material	110	TON		
2081001	Fine Grading	9,578	SY		
3050106	Graded Aggregate Base Course (8" Uniform)	8,074	SY		
3069900	Contingent Maintenance Stone	51	TON		
4011004	Liquid Asphalt Binder PG64-22	84	TON		
4030320	Hot Mix Asphalt Surface Course Type C	1,606	TON		
6051120	Permanent Construction Signs (Ground Mounted)	67	SF		
6271025	24" White Solid Lines (Stop/Diag Lines) - Thermo-125Mil	33	LF		
6301100	Permanent Yellow Pavement Markers - Bi-Dir 4x4	256	EA		
6510105	Flat Sheet Sign, Type III, Fixed Sz. & Msg.	29	SF		
6531210	U-Section Post for Sign Supports - 3P	62	LF		
7011852	Concrete Key	62	LF		
7143618	18" RC Pipe	602	LF		
8041020	Rip-Rap (Class B)	158	TON		
8048205	Geotextile for Erosion Control Under Riprap	182	SY		
8081000	Moving Item	1	EA		
8100100	Permanent Cover	3.3	ACRE		
8100200	Temporary Cover BY SEEDING	1.5	ACRE		
8151151	Turf Reinforcement Matting (TRM) Type 1	3,796	SY		
8152007	Sediment Tubes for Ditch Checks	337	LF		
8153000	Silt Fence	2,959	LF		

Construction Cost Estimate

<u>Item No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Units</u>	<u>Unit Price</u>	<u>Total Price</u>
Belladonna Court					
1031000	Mobilization	1	LS		
1050800	Construction Stakes, Lines & Grades	1	EA		
1050810	As-Built Surveys	1	LS		
1052000	Utility Relocation Allowance	1	LS	\$5,000.00	\$5,000.00
1071000	Traffic Control	1	LS		
2012000	Clearing & Grubbing within Roadway	1.2	ACRE		
2031000	Unclassified Excavation	710	CY		
2033000	Contingent Borrow Excavation	135	CY		
2034000	Contingent Muck Excavation	54	CY		
2036000	Contingent Geotextile for Separation of Subgrade & Subbase	54	SY		
2037010	Contingent Geogrid Reinforcement (Biaxial)	54	SY		
2052010	Contingent Stone Bridge Lift Material	41	TON		
2081001	Fine Grading	3,542	SY		
3050106	Graded Aggregate Base Course (8" Uniform)	2,986	SY		

3069900	Contingent Maintenance Stone	19	TON		
4011004	Liquid Asphalt Binder PG64-22	31	TON		
4030320	Hot Mix Asphalt Surface Course Type C	594	TON		
6051120	Permanent Construction Signs (Ground Mounted)	25	SF		
6271025	24" White Solid Lines (Stop/Diag Lines) - Thermo-125Mil	12	LF		
6301100	Permanent Yellow Pavement Markers - Bi-Dir 4x4	95	EA		
6510105	Flat Sheet Sign, Type III, Fixed Sz. & Msg.	11	SF		
6531210	U-Section Post for Sign Supports - 3P	23	LF		
7143618	18" RC Pipe	339	LF		
8041020	Rip-Rap (Class B)	59	TON		
8048205	Geotextile for Erosion Control Under Riprap	67	SY		
8081000	Moving Item	1	EA		
8100100	Permanent Cover	1.2	ACRE		
8100200	Temporary Cover BY SEEDING	0.5	ACRE		
8151151	Turf Reinforcement Matting (TRM) Type 1	1,404	SY		
8152007	Sediment Tubes for Ditch Checks	118	LF		
8153000	Silt Fence	1,094	LF		

Construction Cost Estimate

<u>Item No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Units</u>	<u>Unit Price</u>	<u>Total Price</u>
	Kidneywood Way				
1031000	Mobilization	1	LS		
1050800	Construction Stakes, Lines & Grades	1	EA		
1050810	As-Built Surveys	1	LS		
1052000	Utility Relocation Allowance	1	LS	\$10,000.00	\$10,000.00
1071000	Traffic Control	1	LS		
2012000	Clearing & Grubbing within Roadway	0.5	ACRE		
2031000	Unclassified Excavation	398	CY		
2033000	Contingent Borrow Excavation	71	CY		
2034000	Contingent Muck Excavation	71	CY		
2036000	Contingent Geotextile for Separation of Subgrade & Subbase	71	SY		
2037010	Contingent Geogrid Reinforcement (Biaxial)	71	SY		
2052010	Contingent Stone Bridge Lift Material	53	TON		
2081001	Fine Grading	2,407	SY		
3050106	Graded Aggregate Base Course (8" Uniform)	2,241	SY		
3069900	Contingent Maintenance Stone	14	TON		
4011004	Liquid Asphalt Binder PG64-22	18	TON		
4030320	Hot Mix Asphalt Surface Course Type C	298	TON		
6051120	Permanent Construction Signs (Ground Mounted)	34	SF		
6271025	24" White Solid Lines (Stop/Diag Lines) - Thermo-125Mil	34	LF		
6301100	Permanent Yellow Pavement Markers - Bi-Dir 4x4	19	EA		
6510105	Flat Sheet Sign, Type III, Fixed Sz. & Msg.	9	SF		
6531210	U-Section Post for Sign Supports - 3P	17	LF		
7143618	18" RC Pipe	104	LF		
8081000	Moving Item	1	EA		
8100100	Permanent Cover	0.5	ACRE		
8151151	Turf Reinforcement Matting (TRM) Type 1	568	SY		
8152007	Sediment Tubes for Ditch Checks	95	LF		
8153000	Silt Fence	327	LF		

Construction Cost Estimate

<u>Item No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Units</u>	<u>Unit Price</u>	<u>Total Price</u>
	Soldierwood Lane				
1031000	Mobilization	1	LS		
1050800	Construction Stakes, Lines & Grades	1	EA		
1050810	As-Built Surveys	1	LS		
1052000	Utility Relocation Allowance	1	LS	\$5,000.00	\$5,000.00
1071000	Traffic Control	1	LS		
2012000	Clearing & Grubbing within Roadway	0.2	ACRE		
2031000	Unclassified Excavation	163	CY		

2033000	Contingent Borrow Excavation	29	CY		
2034000	Contingent Muck Excavation	29	CY		
2036000	Contingent Geotextile for Separation of Subgrade & Subbase	29	SY		
2037010	Contingent Geogrid Reinforcement (Biaxial)	29	SY		
2052010	Contingent Stone Bridge Lift Material	22	TON		
2081001	Fine Grading	983	SY		
3050106	Graded Aggregate Base Course (8" Uniform)	915	SY		
3069900	Contingent Maintenance Stone	6	TON		
4011004	Liquid Asphalt Binder PG64-22	7	TON		
4030320	Hot Mix Asphalt Surface Course Type C	122	TON		
6051120	Permanent Construction Signs (Ground Mounted)	14	SF		
6271025	24" White Solid Lines (Stop/Diag Lines) - Thermo-125Mil	14	LF		
6301100	Permanent Yellow Pavement Markers - Bi-Dir 4x4	8	EA		
6510105	Flat Sheet Sign, Type III, Fixed Sz. & Msg.	4	SF		
6531210	U-Section Post for Sign Supports - 3P	7	LF		
7143618	18" RC Pipe	32	LF		
8081000	Moving Item	1	EA		
8100100	Permanent Cover	0.2	ACRE		
8151151	Turf Reinforcement Matting (TRM) Type 1	232	SY		
8152007	Sediment Tubes for Ditch Checks	25	LF		
8153000	Silt Fence	133	LF		
GRAND TOTAL:					