



Date: September 10, 2019

RE: Bid No.: 19-2234 Levings Park Accessible Path Construction
Opening: Tuesday, September 17, 2019 at 2:00 p.m., Rockford
Park District, Webbs Norman Center Board Room, 401
S. Main St., Rockford, IL 61101

ADDENDUM NUMBER ONE

This addendum is issued to modify, clarify or correct the original Project Manual and/or Drawings and is hereby made a part of the contract documents. Please attach this addendum to the Project Manuals and Drawings in your possession. Include acknowledgement of this addendum in your bid. Omission of acknowledgement may be cause for rejection of bid. Bidders shall review changes to all portions of work, as changes to one portion may affect work of another.

The following were in attendance at the September 10, 2019 Pre-Bid Conference:

Ryan Hathaway	N-TRAK
Nolan Schlie	Stenstrom
Greg Kolb	William Charles
Ken Klowky.....	William Charles
Doug Wenzel.....	Rockford Park District
Tom Lind	Rockford Park District
Tamara Ray.....	Rockford Park District
Debbie Brooks.....	Rockford Park District

A. INFORMATION:

1. Requests for Information (RFI's) are to be submitted in writing to debbiebrooks@rockfordparkdistrict.org by 12:00 p.m. on Thursday, September 12, 2019. Responses will be published by way of addendum.

B. CLARIFICATIONS TO THE PROJECT MANUAL:

C. CLARIFICATIONS TO THE PROJECT DRAWINGS:

1. No formal SWPPP is required, but contractor is to install and maintain erosion control as shown on the plans.
2. Refer to the "Typical Section" on sheet C2. Omit the aglime surface and reduce the aggregate base course width to 10'.
3. Contractor is to provide an as-built survey upon completion.
4. RPD will remove the two existing trees closest to the path, near the bath house.

5. Concrete walk thickness is to be 5".
6. No new chain link gates are included in this project. Refer to the plan view on sheet C3 and disregard note 2.
7. Earthwork clarification:
 - a. The earthwork (cut and fill) amounts shown on the plans reflect the difference from existing ground elevations to proposed ground elevations. This is calculated for computing the volume of fill in the floodplain only. The volume includes topsoil, paving, and stone.
 - b. There will be haul-off to outside of the Levings Lake floodplain. The compensatory basin area is meant to balance the volume of fill placed by the new path above. This volume must leave the floodplain to maintain a net zero fill condition.

END OF ADDENDUM NUMBER ONE