



1211 Merchant Way
Suite 201
Statesboro, GA 30458
Phone: (912) 764-7022
Fax: (912) 233-4580
www.emc-eng.com

ENGINEERS SUPPLEMENTAL INFORMATION ADDENDUM NO. 1

PROJECT: Hood Road Paving Project
EMC Project No. 20-2048

OWNER: Bulloch County Board of Commissioners

ENGINEER: EMC Engineering Services, Inc.

DATE ISSUED: August 26, 2021

BID DOCUMENTS DATED AUGUST 02, 2021 ARE HEREBY AMENDED AS NOTED HEREIN. CHANGES AND CLARIFICATIONS PROVIDED ARE BASED ON QUESTIONS AS DOCUMENTED BELOW. CONTRACTOR TO ACKNOWLEDGE RECEIPT OF ADDENDUM ON BID PROPOSAL. FAILURE TO DO SO MAY, AT THE OWNER'S DISCRETION, SUBJECT THE BIDDER TO DISQUALIFICATION.

REQUEST FOR INFORMATION

- 1) RFI 01:
 - a. DATE RECEIVED: 08/26/2021
 - b. CONTRACTOR: R.B. Baker Construction
 - c. QUESTION: Will measurement and payment for removal and replacement of unsuitable material be made per GDOT standard specification 210?
 - d. ANSWER: Grading Complete is to be paid as a lump sum and is to include all items listed in Section 210.1 of the GDOT Standard Specifications, including removal and replacement of undesirable materials.

- 2) RFI 02:
 - a. DATE RECEIVED: 08/26/2021
 - b. CONTRACTOR: R.B. Baker Construction
 - c. QUESTION: What is the expectation for the "vegetation removal" shown on the demolition plans? Is the contractor to completely clear and grub these areas or just trim any trees overhanging the roadway?
 - d. ANSWER: "Vegetation Removal" includes the clearing and grubbing of all vegetation as required for back slope / ditch grading.

- 3) RFI 03:
 - a. DATE RECEIVED: 08/26/2021
 - b. CONTRACTOR: R.B. Baker Construction
 - c. QUESTION: Would the County add an allowance item for the removal/relocation of the GSU irrigation system since the overall scope cannot be determined at this time?



1211 Merchant Way
Suite 201
Statesboro, GA 30458
Phone: (912) 764-7022
Fax: (912) 233-4580
www.emc-eng.com

- d. ANSWER: The University may potentially relocate the irrigation system in-house. Coordination efforts between the EMC, the County and University are still underway to determine if this relocation will be a part of the Contractor's work. As this has yet to be decided, Line Item 766-7021 "Irrigation System Removal / Relocation" has been added to the Bid Schedule.

CHANGES TO THE CONSTRUCTION DOCUMENTS:

- 1) The Bid Form has been revised to add Line Item 766-7021 "Irrigation System Removal / Relocation (Allowance)" as an Add Alternate.

BID date has not changed. BIDs remain due on August 31, 2021 at 3:00 PM.

ATTACHMENTS:

1. Revised Bid Form (dated 08/26/2021).

END OF ADDENDUM NO. 1

BID FORM

Proposal of _____ (hereinafter called "BIDDER"), organized and existing under the laws of the State of _____ Doing business as* _____.

To the Bulloch County Board of Commissioners (hereinafter called "OWNER").

In compliance with your Advertisement for Bids, BIDDER hereby proposes to perform all WORK for the construction of Hood Road Paving Project in strict accordance with the CONTRACT DOCUMENTS, within the time set forth therein, and at the prices stated below.

By submission of this BID, each BIDDER certifies, and in the case of a joint BID each party thereto certifies as to his own organization, that this BID has been arrived at independently, without consultation, communication, or agreement as to any matter relating to this BID with any other BIDDER or with any competitor.

BIDDER hereby agrees to commence WORK under this contract on or before a date to be specified in the NOTICE TO PROCEED and to fully complete the PROJECT within 150 consecutive calendar days thereafter. BIDDER further agrees to pay as liquidated damages, the sum of \$100.00 for each consecutive calendar day thereafter as provided in Section 15 of the General Conditions.

BIDDER acknowledges receipt of the following ADDENDUM:

Addendum 01: Issued 08/26/2021

It is the sole responsibility of the BIDDER to ensure all ADDENDUMS have been received and incorporated into the bid documents.

*Insert "a corporation", "a partnership", or "an individual" as applicable.

BID SCHEDULE**HOOD ROAD PAVING PROJECT**

EMC PROJECT NO.: 20-2048

BULLOCH COUNTY, GEORGIA

Prepared For:

BULLOCH COUNTY BOARD OF COMMISSIONERS

EMC Engineering Services, Inc.

1211 Merchant Way, Suite 201

Statesboro, GA 30458

(912) 764-7022

www.emc-eng.com

DATE: 08/26/2021

BASE ROAD QUANTITIES

NO.	ITEM NO.	ITEM DESCRIPTION	QTY.	UNIT	UNIT PRICE	TOTAL
1	150-1000	TRAFFIC CONTROL	1.00	LS		
2	163-0232	TEMPORARY GRASSING	8.32	AC		
3	163-0240	MULCH (STRAW/HAY)	16.64	TN		
4	163-0300	CONSTRUCTION EXIT	2.00	EA		
5	163-0529	CONSTRUCT AND REMOVE BALED STRAW CHECK DAM	1215.00	LF		
6	171-0010	TEMPORARY SILT FENCE, TYPE A (NON SENSITIVE)	10796.00	LF		
7	210-0100	GRADING COMPLETE	1.00	LS		
8	310-5060	GR AGGR BASE CRS, INCL MATL & PRIME (6 IN, ROADWAY)	8265.00	TN		
9	310-5061	GR AGGR BASE CRS, INCL MATL & PRIME (4 IN, DRIVEWAYS)	302.00	TN		
10	402-3114	REC ASPH CONC 12.5 MM SP, GP 1 / 2, INCL BITUM MATL & LIME (220-LB/SY)	2698.00	TN		
11	550-1180	STORM DRAIN PIPE, 18 IN, H 1-10, RCP	44.00	LF		
12	550-3000	ELLIPTICAL STORM DRAIN PIPE, 19-INx30-IN, H 1-10, RCP	200.00	LF		
13	550-2150	SIDE DRAIN PIPE, 15 IN, H 1-10, RCP	224.00	LF		
14	550-2180	SIDE DRAIN PIPE, 18 IN, H 1-10, RCP	408.00	LF		
15	550-2240	SIDE DRAIN PIPE, 24 IN, H 1-10, RCP	336.00	LF		
16	550-4218	FLARED END SECTION, 18 IN, CONCRETE	2.00	EA		
17	550-4299	FLARED END SECTION, 19-INx30-IN, CONCRETE	10.00	EA		

18	603-2180	STN DUMPED RIP RAP, TP 3, 12 IN	78.00	SY		
19	603-7000	PLASTIC FILTER FABRIC	78.00	SY		
20	611-8056	REMOVE/REPLACE/RESET STANDARD MAILBOX	25.00	EA		
21	611-8057	REMOVE/REPLACE/RESET MASONRY MAILBOX	0.00	EA		
22	636-1033	HIGHWAY SIGNS,TP 1 MATL, REFL SHEETING, TP 9	62.00	SF		
23	636-2070	GALV STEEL POSTS, TP 7	182.00	LF		
24	643-8300	3.5-FT TALL SPLIT RAIL VINYL FENCE	442.00	LF		
25	652-2501	SOLID TRAFFIC STRIPE, 5 IN, WHITE	3.73	LM		
26	652-2502	SOLID TRAFFIC STRIPE, 5 IN, YELLOW	0.92	LM		
27	652-3502	SKIP TRAFFIC STRIPE, 5-IN, YELLOW	1.55	GLM		
28	653-1704	THERMOPLASTIC SOLID TRAFFIC STRIPE, 24 IN, WHITE (STOP BAR)	61.00	LF		
29	700-6910	PERMANENT GRASSING	8.32	AC		
30	700-7000	AGRICULTURAL LIME	12.50	TN		
31	700-8000	FERTILIZER MIXED GRADE	4.16	TN		
32	716-2000	EC MATS, SLOPES (Ss-B2: COCO MAT - NAG ERONET SC150)	1380.00	SY		
32	716-2001	EC MATS, SLOPES (Ss-B2: COCO MAT - NAG ERONET SC150) - SIDE DRAINS	495.00	SY		
33	999-1000	CONSTRUCTION STAKING	1.00	LS		
34	999-2000	CONSTRUCTION MATERIAL TESTING	1.00	LS		
BASE ROAD TOTAL						

BASE OFF SITE DRAINAGE QUANTITIES

NO.	ITEM NO.	ITEM DESCRIPTION	QTY.	UNIT	UNIT PRICE	TOTAL
35	163-0232	TEMPORARY GRASSING	2.53	AC		
36	163-0529	CONSTRUCT AND REMOVE BALED STRAW CHECK DAM	141.00	LF		

37	210-0100	GRADING COMPLETE	1.00	LS		
38	310-5061	GR AGGR BASE CRS, INCL MATL & PRIME (4 IN, DRIVEWAYS)	8.25	TN		
39	603-2180	STN DUMPED RIP RAP, TP 3, 12 IN	124.00	SY		
40	603-7000	PLASTIC FILTER FABRIC	124.00	SY		
41	550-1240	STORM DRAIN PIPE, 24 IN, H 1-10, RCP	32.00	LF		
42	550-1300	STORM DRAIN PIPE, 30 IN, H 1-10, RCP	48.00	LF		
43	550-4224	FLARED END SECTION 24 IN, STORM DRAIN	4.00	EA		
44	550-4230	FLARED END SECTION 30 IN, STORM DRAIN	4.00	EA		
45	700-6910	PERMANENT GRASSING	2.53	AC		
46	700-7000	AGRICULTURAL LIME	3.80	TN		
47	700-8000	FERTILIZER MIXED GRADE	1.30	TN		
48	716-2000	EC MATS, SLOPES (Ss-B2: COCO MAT - NAG ERONET SC150)	365.00	SY		
BASE OFF SITE DRAINAGE TOTAL						

ADD ALTERNATE

NO.	ITEM NO.	ITEM DESCRIPTION	QTY.	UNIT	UNIT PRICE	TOTAL
49	654-1001	RAISED PAVEMENT MARKERS, TP 1 (RAISED REFLECTIVE)	299.00	EA		
50	766-7021	IRRIGATION SYSTEM REMOVAL / RELOCATION (ALLOWANCE)	1	LS		
ADD ALTERNATE TOTAL						

CONSTRUCTION GRAND TOTAL w/ ADD ALTERNATE

SUBMITTED BY: _____ TITLE: _____

COMPANY : _____ DATE: _____

SIGNATURE : _____