

BOARD OF COMMISSIONERS

Meetings Second Tuesday

MARTIN H. MOSELEY, JR.
Chairman

SHANITA BRYANT

BETTY C. HILL

ROY LEWIS

WADE YODER

MICHAELA JONES
County Administrator

APRIL H. HODGES
County Clerk

Peach County

213 Persons Street
Fort Valley, Georgia 31030
Phone 478-825-2535
Fax 478-825-2678

COUNTY OFFICIALS

KIM WILSON
Probate Judge

JOE WILDER
Clerk of Superior Court

TERRY DEESE
Sheriff

W. L. BROWN
Tax Commissioner

KERRY ROOKS
Coroner

LAURENS C. LEE
Magistrate

ADVERTISEMENT REQUEST FOR BIDS

RFB No. 19-015

Restore and Resurface Tennis Courts and Basketball Courts

Addendum No. 3

Date: September 13, 2019

This document serves as an Addendum to the RFB No. 19-015 advertised on August 9, 2019 by the Peach County Board of Commissioners. This Addendum is made to address questions and changes on Sections 3.0.1, 3.03.3 and 8.0 as follows:

QUESTIONS AND ANSWERS

Question: "Per the scope of work, it calls for the Hot Mix Asphalt to be free of reclaimed asphalt shingles and reclaimed asphalt pavement. Please confirm that you are looking for "virgin" asphalt on this project.

Answer: No, Remove all references to "free of reclaimed asphalt shingles and reclaimed asphalt pavement" in the specifications and follow GDOT specifications concerning reclaimed material in the asphalt concrete.

The existing basketball goals are not sleeved. The basketball goals will not be able to be adjusted to the new asphalt overlay elevation without the complete removal of the goal and the goal footing. This will cause the resetting of all of the existing basketball goals.

Answer: change

***NORTH PEACH PARK AND SOUTH PEACH PARK – 8 BASKETBALL
COURTS***

3.0.1 to say: Remove basket posts and foundations as needed for paving equipment access.

3.03.3 to say: Reinstall basketball posts in new foundations with depth and size equal to the existing depth and size removed. Height of basketball rim shall be in accordance with NBA/WNBA specifications.

The existing basketball posts are galvanized. Are you sure that you want the existing basketball posts primed and painted?

Answer: Delete NORTH PEACH PARK AND SOUTH PEACH PARK – 8 BASKETBALL COURTS

~~3.03.2 All existing basket posts shall be sanded and one coat of primer and three coats of paint that is classified for use on metal surface applied.~~

The bid package states that the contractor shall not subcontract work in excess of 10%. I cannot meet this this requirement. Can this requirement be waived?

Answer: Change CONTRACT GENERAL CONDITIONS

8.0 to say: All subcontracts in the amount of \$5,000 or more shall include the provisions set forth in this Agreement.

The bid package states that the contractor is responsible for arranging, obtaining and paying for all cost related to testing. Please provide the specific materials and scope of work that the County will require testing on.

Answer: One compaction test for every 500 square yards or installed asphalt.

The bid package references erosion control. If this is required, please provide the scope of work that the contractor is to carry related to this item.

Answer: Adequate erosion control must be in place to prevent sediment from leaving the work site.

I have attached product literature for the Riteway Crack Repair System for approval in lieu of the Armor Crack Repair System.

Answer: Riteway Crack Repair System is approved for substitution of Armor Crack Repair System

Request to substitute DecoCOLOR for Elite Coating Suystem is approved

**All remaining terms and conditions of the solicitation remain unchanged.*