



THE CITY OF DAYTONA BEACH  
OFFICE OF THE PURCHASING AGENT

Post Office Box 2451  
Daytona Beach, Florida 32115-2451

Phone (386) 671-8080  
Fax (386) 671-8085

**ADDENDUM NO. 2**

DATE: November 13, 2019

PROJECT: ITB 20133  
BETHUNE POINT SHORELINE STABILIZATION

OPENING DATE: December 2, 2019

This addendum is hereby incorporated into the Bid Documents for the project referenced above. The following items are clarifications, corrections, additions, deletions and/or revisions to and shall take precedence over the original documents. Additions are indicated by underlining, deletions are indicated by ~~strikethrough~~.

**RFI #3**

1. Could you please specify what is required for as-built drawings and submission and whether they are required to be done by a registered surveyor or on our own?

**A: *The signed and sealed As-Built survey is to show the extent of the new Tri-Lock installation, provide Topographical information, and document the utility penetrations. Topo running north-south can be collected every 25 Ft and running east-west include the Top of bank, Toe of Slope and the approximate middle of the slope. Need 5 hard copies and 1 electronic copy to be submitted.***

2. We were to be provided specific permit requirements and the cost of to include the bid, will you still be providing?

**A: *The bid schedule has been revised to include an allowance for the City's permit. All other permits are contained in the bid documents (Appendix F). Bidder's must use the latest version of the bid schedule, which includes the allowance for the permit fee, in order to be responsive.***

3. The question regarding geo-technical was whether it had been done for the site and we understood it had and that the report would be provided to us, instead a line item has been added for it. If no testing has been done what specifically are we to include for so that all bidders can bid the same thing?

**A: *A geotechnical report had been completed for the project and is included in Appendix E. Please note, eight (8) Modified Proctor maximum dry density geotechnical test as determined by ASTM Standard D-1557 will be required to verify compaction requirements have been meet as outlined in Section 6.2 - General Site Preparation of the geotechnical report.***

4. Could you specify exactly what we are to include for the added fence line item? Repair? New? Linear footage to include for?

**A: *Remove 60 LF of the dilapidated fence along the northern boundary starting in the river headed west 60 LF and replace it with 60 LF of new 6-Ft tall chain link fence.***

5. All other items shall remain the same.

The Bidder shall acknowledge receipt of this addendum in Section 7 of the Bid Proposal Form.

The City of Daytona Beach

Kirk Zimmerman, CPPB  
Buyer