



## THE CITY OF DAYTONA BEACH OFFICE OF THE PURCHASING AGENT

Post Office Box 2451  
Daytona Beach, Florida 32115-2451

Phone (386) 671-8080  
Fax (386) 671-8085

### ADDENDUM NO. 2

DATE: October 22, 2019

PROJECT: CYPRESS AQUATIC CENTER POOL RESURFACING  
20053

OPENING DATE: November 1, 2019

This addendum is hereby incorporated into the Bid Documents for the project referenced above. The following items are clarifications, corrections, additions, deletions and/or revisions to and shall take precedence over the original documents. Additions are indicated by underlining, deletions are indicated by ~~strike through~~.

1. The Scope of Work is hereby REPLACED with the Revised Scope of Work, attached.
2. All other terms and conditions remain the same.

The Bidder shall acknowledge receipt of this addendum in Section 7 of the Bid Proposal Form.

The City of Daytona Beach

Joanne Flick, CPPO, CPPB  
Purchasing Agent

Cypress Aquatic Center  
Pool Resurfacing  
Project #2019-059  
981 George Engram Blvd.

**REVISED**  
**Scope of Work**

Contractor shall abide by and satisfy all Volusia County Health Department permit requirements for all items listed below to complete this resurfacing project per Florida Administrative Code 64E-9 thru to 64E-9.005(2)(a) through (g), FAC". (Attachment A) and the most recent edition of the "Florida Pool Code" (Attachment B).

1. File and receive a permit from the Volusia County Health Department and the City of Daytona Beach for this pool resurfacing project (approximately 150,100 gallon pool) prior to beginning the work, including paying all permit application and Florida Surcharge fees. Complete any punch-list items need to begin and complete this project.
2. Provide non-invasive leak detection and repair for all related pool system plumbing lines, concrete shell, pool lights, drains and surge tanks. Submit leak detection and repair scope-of-work to City of Daytona Beach Technical Service's Division that lists the means and methods to be used prior to resurfacing.
3. Remove pool ladders, lights, railings, ropes, floats, and any broken tile and check for leaks, chips and cracks in pool shell. (Existing fountain water features to be removed by the City of Daytona Beach).
4. Provide cleaning and clearing of all foreign debris at all deck and gutter drain locations to ensure positive flow. Perform leak pressure testing at each drain line prior to reinstallation and pool resurfacing.
5. Prepare a Dewatering Groundwater Control Plan for the pool and submit to the City's Technical Services Department for approval.
6. Implement the approved Dewatering Plan before draining pool.
7. Drain the pool.
8. Examine and identify hollow spots by sounding existing pool substrate (outer finish) surfaces and remove any condition that will interfere with any bond coating and new finish applications to include: algae, mold, mildew, loose dirt, paint, mortar, tile and cracked plaster finish surfaces.
9. Remove all hollow and delaminated pool finish surfaces by sawing/cutting or chipping per manufacturer's surface preparation guidelines and directions.

10. Repair 65 hairline cracked 24" x 36" Coping Stone Block Tiles prior to resurfacing using a City approved Hairline Crack filler and sealer, exercising extreme care to avoid damaging adjoining Coping Stone block tiles and existing depth markers. Paint repaired Coping Stones with epoxy anti-slip coating as manufactured by Sherwin-Williams or equal, to match the existing color of adjoining Coping Stones.
11. Remove the 37 existing 5.5" x 2.5" scum gutters and frames and install 37 new scum gutter grates and frames of the same size, matching the existing gutter grates and frames current locations per the codes referenced above.
12. Remove 6 existing 18" x 18" drain grates on pool bottom and replace with size matching stain-free drain grates per City codes and Attachments A and B.
13. Remove 13 - 4" round return drains in the "Kiddie Pool" and 24 - 4" round return drains in the "Competition Pool". Replace all drains removed with new size matching stain-free grates per City and Attachments A and B.
14. Install the 6 new 18" x 18" drain grates back in the previous drain locations to match the previous pool bottom drain grate dimensions per the codes referenced above.
15. Reinstall all previously removed pool ladders, lights, railings, ropes, and floats per City codes and on Attachments A and B.
16. Replace all broken scum gutter tile in the Competition Pool only including any broken swim lane tiles to be waterproof and non-slip to match the current color scheme per the codes attached and listed above.
17. Furnish and reinstall any depth and "no diving" marking or signs previously removed from around the pool per the codes listed above.
18. Submit the New Pebble Finish system product data sheet from (CLI, SGM, Pebble Tech, or Florida Stucco) submittal listing the preparation and installation guidelines and physical properties, including the required substrate preparation and bonding coat products for review and approval by the City's Technical Services Department prior to beginning the work.
19. Apply New Pebble Finish system strictly following manufacturer's desired and best practices installation guidelines and directions. The New Pebble Finish to have a minimum 15-year material warranty and a 2-year labor warranty. (City of Daytona Beach to select color.)
20. Pool resurfacing work to receive final approvals from both the Volusia County Health Department and the City's Technical Services Department.