



## *Georgetown County, South Carolina*

129 Screven Street, Suite 239  
Post Office Drawer 421270  
Georgetown, SC 29442-4200  
(843) 545-3083 • Fax (843) 545-3500  
E-Mail • [purch@gtcounty.org](mailto:purch@gtcounty.org)  
Website • <http://www.gtcounty.org>

### ADDENDUM #4 TO BID #20-020

BID NUMBER: 20-020

ISSUE DATE: Thursday, May 7, 2020

OPENING DATE: **Wednesday, May 13, 2020**

OPENING TIME: **3:30 PM ET**

Pre-Bid Site Inspection and/or Conference: [None]

**PROCUREMENT FOR: Garden City Drainage Improvements Sites 1, 5 and 8**

---

---

This addendum will amend **Bid #20-020, Garden City Drainage Improvements Sites 1, 5 and 8** originally issued on Wednesday, April 8, 2020. This clarification is being provided to all known and registered correspondents in response to questions received. All addenda and original bid documents are also available online at: [www.gtcounty.org](http://www.gtcounty.org), select “Bid Opportunities” from the Quick Links section and “View Current Bid Solicitations.”

---

**REVISION: See revised drawings for Site 5 from engineers posted to the website labeled “Bid20020DrawingsSite5REVISED05072020”.**

---

**REVISION: Please use the (REVISED) Exhibit H-Unit Price Schedule on the following pages in your bid submittal. Item numbers 44, 51, and 52 are new.**

---

**(REVISED) EXHIBIT H**

**UNIT PRICE SCHEDULE**  
**MANDATORY BID SUBMISSION FORM**

**BID # 20-020, GARDEN CITY DRAINAGE IMPROVEMENTS SITES 1, 5 AND 8**

When changes in the work are ordered by the Owner, and such changes involve the following items, the following unit prices will be used to calculate adjustments to the Contract Sum. These unit prices shall be for the Work as specified, including all labor, materials, equipment, accessories, shipping, preparation, insurance, testing, overhead, profit, applicable taxes, permits, fees, warranties and all other associated costs for the finished and completed Work. All unit prices for utility conduits shall include sweeps, bends, couplings, caps, fittings, etc. which shall be included in the unit price per linear foot. Unit prices for undercut soils shall include material in place, surveyed and compacted pursuant to the Contract Documents.

Submit unit price and proposal amount for the following items. This list may not include all components necessary to provide a completed product, therefore any applicable items necessary to provide a completed product should be considered in your unit price response.

In case of errors in the extension of prices, unit price governs. In case of error in summations, corrected bid amounts will be totaled and will govern.

Contractor shall be responsible for all necessary electric and water hookups.

Contractor shall make quantity take-offs using drawings to determine quantities to his satisfaction, reporting promptly any discrepancies which may affect bidding. This is not a comprehensive list of items included in the contract documents, and represents only a portion of the project total.

**UNIT PRICE SCHEDULE**

<b>SITE 1 UNIT PRICE SCHEDULE</b>					
<b>Item</b>	<b>Description</b>	<b>Unit</b>	<b>Quantity</b>	<b>Unit Price</b>	<b>Total Cost</b>
1	Mobilization/staking/general conditions/Project Sign 1 for all 3 Sites	LS	1		
2	Traffic Control	LS	1		
3	Remove 18" RCP Stormwater Pipe	LF	291		
4	Remove/Replace Concrete Driveway and Sidewalk	SF	1300		
5	Misc. Demolition (clearing, tree removal, SW Struct. Removal, etc.)	LS	1		

6	Abandon in Place 18"RCP with Flowable Fill	LF	31		
7	Tree Protection	LF	50		
8	Hydroseeding	SF	11850		
9	Silt Fence	LF	781		
10	Concrete Washout	EA	1		
11	Inlet Protection	EA	7		
12	18" RCP Drainage Pipe	LF	546		
13	15" RCP Drainage Pipe	LF	8		
14	Installation of 18" Inline Checkvalve	EA	1		
15	Catch Basin Concrete Collars	EA	7		
16	Catch Basins	EA	7		
17	Curb Inlets (SCDOT Type 9)	EA	2		
18	Fine Grading (Spillway Area and Access)	SY	416		
19	Full Depth Repair	SF	2		
20	Mill and Replace	SF	5710		
21	Water Service Relocation (est.)	EA	10		
22	Sewer Forcemain Relocation Assume 4"	EA	1		
23	Sanitary Sewer Service Relocation (est.)	EA	5		
24	Bulk head design and replacement	LS	1		
25	Misc. relocations, working around exist. Utilities, shoring (est.)	LS	1		
26	Geotechnical Testing Allowance	LS	1	\$1000.00	\$1000.00
			<b>Site 1 Total</b>		

(Continued on Next Page)

<b>SITE 5 UNIT PRICE SCHEDULE</b>					
<b>Item</b>	<b>Description</b>	<b>Unit</b>	<b>Quantity</b>	<b>Unit Price</b>	<b>Total Cost</b>
26	Mobilization/staking/general conditions	LS	1		
27	Traffic Control	LS	1		
28	Demo Existing Sidewalk (4.5 wide)	LF	299		
29	Demo gravel parking area	SF	3100		
30	Demo Concrete Driveway	SF	1235		
31	Remove/Replace Existing Wood Bulkhead (includes Anti Seep Collar)	LS	1		
32	Hydroseeding	SF	26645		
33	Concrete Washout	EA	1		
34	Inlet Protection	EA	11		
35	18" RCP Drainage Pipe	LF	407		
36	24" RCP Drainage Pipe	LF	463		
37	Installation of 24" Inline Checkvalve	EA	1		
38	Catch Basin Concrete Collars	EA	12		
39	Catch Basin	EA	12		
40	Fine Grading	LS	1		
41	2" Mill and Overlay (Match Ex. Elevation)	SF	12605		
42	Full Depth Patch Saw Cut and Replacement of Asphalt	SF	6723		
43	2' Valley Gutter	LF	125		
44	6" Stand Up Curb	LF	138		
45	Installation of Pervious Concrete	SY	300		
46	Pavement Markings and Raised Pavement Markers	LS	1		
47	Concrete Wheel Stops	EA	12		
48	Concrete Driveways	SF	1220		
49	Concrete Public Access Drive	SF	1180		
50	5' Concrete Sidewalk	LF	299		
51	Landscaping	SF	1625		

52	No Parking Signs	EA	2		
53	Water Main (8" DIP) Relocation	LF	450		
54	Water Service Relocation (est.)	EA	7		
55	8" Gate Valve	EA	1		
56	Sanitary Sewer Service Relocation (est.)	EA	7		
57	Misc. utility relocations (power poles, shoring, etc)	LS	1		
58	Geotechnical Testing Allowance	LS	1	\$3000.00	\$3000.00
<b>Site 5 Total</b>					

<b>SITE 8 UNIT PRICE SCHEDULE</b>					
<b>Item</b>	<b>Description</b>	<b>Unit</b>	<b>Quantity</b>	<b>Unit Price</b>	<b>Total Cost</b>
58	Mobilization/staking/general conditions	LS	1		
59	Traffic Control	LS	1		
60	Remove/Replace Ex. Concrete Driveways	SF	1410		
61	Remove/Replace Ex. Fence	LF	140		
62	Hydroseeding	SF	9680		
63	Concrete Washout	EA	1		
64	Inlet Protection	EA	2		
65	Silt Fence	LF	591		
66	Double Silt Fence	LF	77		
67	Tree Protection	LF	50		
68	Sediment Tube	EA	1		
69	18" RCP Drainage Pipe	LF	14		
70	24" RCP Drainage Pipe	LF	158		
71	Installation of 24" Inline Checkvalve	EA	1		
72	Beveled Pipe Ends inc. Riprap & Geotextile Fabric	EA	1		
73	Fine Grading	LS	1		

74	Catchbasins	EA	2		
75	Catch Basin Concrete Collars	EA	2		
76	Mill and Overlay w/ Grading Corrections	SF	3760		
77	2' Valley Gutter	LF	113		
78	Pavement Markings and Raised Pavement Markers	LS	1		
79	Raise Ex Sewer Manhole RIM	EA	1		
80	Misc. utility relocations (underground power/cable, power poles, shoring, etc)	LS	1		
81	Geotechnical Testing Allowance	LS	1	\$1000.00	\$1000.00
				<b>Site 8 Total</b>	
				<b>Sites 1, 5 and 8 Total</b>	

Bidder/Proposer: \_\_\_\_\_

Signature: \_\_\_\_\_

Title: \_\_\_\_\_

Dated: \_\_\_\_\_

END OF REVISED EXHIBIT H