



Board of County Commissioners • Escambia County, Florida

Paul R. Nobles/Purchasing Manager  
Office of Purchasing

August 22, 2018

To: All Known Prospective Bidders

**Addendum Number 1:**

Re: CR 295A North Old Corry Field Road Sidewalk & Drainage Improvements; FPID:  
425745-5-58-01; Federal-Aid Project Number: 9044-032-C; Specification Number PD  
17-18.053

All:

We recently sent you an Invitation to Bid on the above-mentioned specification.

This Addendum Number 1 provides for:

**Handout from Pre-Solicitation Meeting and Clarifications**

Attached is the North Old Corry Pre-Bid Conference – Important Items Handout provided at the Pre-Solicitation Meeting as well as clarifications from jehle-halstead, inc.

This Addendum Number 1 is furnished to all known prospective bidders. Please sign and return one copy of this Addendum, with original signature, with your bid as an acknowledgement of you having received same. You may photo copy for your record.

Sincerely,

A handwritten signature in blue ink that reads "Emily D. Weddington".

Emily D. Weddington, CPPB  
Purchasing Coordinator

Acknowledgement of Receipt of Addendum 1:

SIGNED: \_\_\_\_\_

COMPANY: \_\_\_\_\_

## **North Old Corry Pre-Bid Conference – Important Items**

1. Bid tab is separated into “Reimbursable by FDOT” and “Non-reimbursable by FDOT” work. This is for billing purposes only. The contractor should look at it as a single non-separated bid and bid it as such.
2. Maintenance of Traffic bid items include (2) Variable Message Boards for 28 days each. *(14 days prior to starting construction and 14 days for any notices required prior to lane closures and/or detours)*
3. Gas Main will be relocated by Pensacola Energy prior to starting construction.
4. **General Note #25 – Sheet 2:** Pipe lengths in the plans do not include the length of pipe that must be installed with the mitered end section. All pipe lengths associated with mitered end sections must be paid for in the unit cost of the mitered end section line item.
5. **General Note #28 – Sheet 2:** For driveways extending into license agreement area, contractor must end new permanent concrete work at the back of the new sidewalk. The new driveway between the back of the new sidewalk and the right-of-way line must be constructed in accordance with the temporary driveway detail on Sheet No. 44 between the right-of-way line and where the driveway slopes tie back to existing grades. The driveway must be constructed of only compacted fill material stabilized in accordance with the contract documents. Pavement for driveway work will be included in bid item #9. Escambia County reserves the right to construct permanent concrete driveways as depicted in the plans after completion of this contract.
6. **Utility Note #35 – Sheet 2:** Certain utilities are to remain and be protected during construction. Necessary repairs will be considered incidental to other pay items and must be to the satisfaction of utility owners.
7. **Drainage Improvement Note – Sheet 16:** Contractor is responsible for sizing new drainage structure bottoms to accommodate proposed pipe connections and structure tops. Graphics that depict structure dimensions varying from the stated top and flowline

elevations and/or from the dimensions stated in the referenced FDOT standard index do not override the stated elevations or referenced standards. Contract intent is for structure bottoms to be the minimum size required to facilitate proposed connections.

8. **Structure S-7 Note – Sheet 17:** Contractor must include in his bid, as work incidental to bid item #33, the removal and replacement of a +/-8' wide section of the existing CMU block wall within the adjacent license agreement area to facilitate installation (by Gulf Power) of a temporary bracing pole. Also included as incidental must be the saw cut, removal and patch of a 2' x 2' area of the existing parking lot to facilitate installation (by Gulf Power) of a temporary anchor. Coordinate exact locations of described work in the field with Gulf Power.
9. **Sheet 19 Note - "Sawcut existing 18" RCP cross drain pipe at limits of construction and install water-tight permanent plug":** This work will be included as part of bid item #19 "Clearing & Grubbing"
10. **Lane Closure Restrictions – Sheet #42, Note 2:** LANE CLOSURE RESTRICTIONS: A LANE MAY ONLY BE CLOSED DURING AN ACTIVE WORK PERIOD. LANE CLOSURES ARE PROHIBITED FROM 5:30 A.M. TO 8:00 P.M. SEVEN (7) DAYS A WEEK.
11. **Trees along right-of-way line – Bid Item #21:** All trees outside of R/W line must be protected. Contractor must use hand excavation within all driplines until such depths that allow roots to be saw-cut and treated with asphalt emulsion (typical of entire project area).

**ADDENDUM #1 - CIVIL**

August 22, 2018

**CR 295A North Old Corry Field Road Sidewalk & Drainage Improvements (LAP)**  
**FPID: 425745-5-58-01, Federal-Aid Project Number: 9044-032-C**

jehle-halstead, inc.

THIS ADDENDUM IS ISSUED FOR THE PURPOSE OF MODIFYING AND/OR CLARIFYING THE ORIGINAL PLANS AND SPECIFICATIONS AND IS TO BE CONSTRUED AS BEING THEREIN.

**CLARIFICATIONS:**

- Item 1:** Regarding the sequence of construction and relocation of ECUA's 6" water main, the location of the proposed water main in the plans is intended to be representative, and final location can be adjusted if necessary based on the Contractor's intended sequencing. Utility coordination efforts concluded that the general intent is for the new ECUA water main to be relocated closest to the edge of the roadway, for Pensacola Energy's new gas main to be outside ECUA, for new drainage pipe to be outside Pensacola Energy, and for Gulf Power's poles to be outside the new drainage pipe. Further, where new cross drain pipes are required, the intent is for new gas/water lines to go over the new storm lines with 30" cover and 6" minimum clearance to the storm pipes for maintenance. The exact location of the water main relocation is to be determined by the Contractor in coordination with ECUA's field inspector.
- Item 2:** Regarding the graphic depiction on Sheet 30 of the EX 6" PE SUE (B) GAS line at Sta. 29+07.68, utility coordination efforts concluded that the existing gas main is installed just beneath the concrete headwall on the north side of Jackson Creek. The graphic depiction of the line in the section view is based on the closest available SUE verified depth, just south of Idlewood Drive.
- Item 3:** Gulf Power will be responsible for the temporary bracing of power poles during construction.

**SPECIFICATIONS:**

No changes.

**DRAWINGS:**

- Item 4: Sheet 2 GENERAL NOTES**  
Revise note #28 to read, in part, "PAYMENT FOR ALL DRIVEWAY WORK WILL BE INCLUDED IN BID ITEM 9."
- Item 5: Sheet 2 GENERAL NOTES**  
Revise note #37 to read, "PAY ITEM 44 REGARDING RELOCATION OF ECUA'S WATER LINE IS NON-REIMBURSABLE BY FDOT AND WILL BE PAID FOR BY ESCAMBIA COUNTY."
- Item 6: Sheet 7 SUMMARY OF PAY ITEMS**

Delete this sheet from the Contract Documents. Contractor must utilize revised bid tab provided by the County as part of the bid package.

**Item 7: Sheet 17 DRAINAGE IMPROVEMENTS**

Regarding plan annotation describing work required of Contractor to facilitate pole bracing by Gulf Power, revise annotation to read, in part, "CONTRACTOR MUST INCLUDE IN HIS BID, AS WORK INCIDENTAL TO BID ITEM 33..."

**Item 8: Sheet 30 CROSS SECTIONS**

Add the following note, applicable to all cross-section sheets, "GRAPHIC DEPICTIONS ARE PROVIDED FOR UTILITIES THAT WERE IDENTIFIED BY THE SUE INVESTIGATION. ELEVATIONS SHOULD BE CONSIDERED AN APPROXIMATION BASED ON SUE DATA IN PROXIMITY TO THE CROSS-SECTION STATION. NO DIRECT CONFLICTS BETWEEN EXISTING UTILITIES AND EXISTING FEATURES HAVE BEEN OBSERVED IN THE FIELD."

**Item 9: Sheet 42 TEMPORARY TRAFFIC CONTROL GENERAL NOTES**

Delete Note #2. There are no lane closure restrictions for this project.

**END OF ADDENDUM #1**