

“City of Havelock
Gray Fox Road Infrastructure Improvements”

Addendum 1

May 25, 2023

Questions Received

1. Will there be a pre-bid meeting for this project?

No, there will be no pre-bid meeting. You may ask any questions you may have via email to lsaleeby@hazenandsawyer.com and cc bids@havelocknc.us.

2. Traffic control, C01/note 13 suggests one lane traffic. Would it be safe to assume that we can shut the street down for the duration of the project with an appropriately designed Traffic Control Plan?

Note 13 on drawing C01 has been edited to allow full road closure. Drawing C13 has been added to the drawing set as a suggested traffic control plan. Email lsaleeby@hazenandsawyer.com to request Addendum 1 drawings.

3. Bypass pumping, clearwater diversion C08. This detail shows what appears to be a gravity bypass. Are we not allowed to pump around with an appropriately sized pump?

Pumping with an appropriately sized pump is allowed for CWD. Gravity can also be used if appropriate.

4. Silt fence, C08. The detail shows stone behind the silt fence. Please clarify, does the stone run the entire length of silt fence? Also, the steel post are spaced on 2' intervals, while the NCDOT allows 8' intervals with wire backing. Is 2' intervals the intent? Continuing with the silt fence detail, is 3' of filter fabric on the front side to be stapled?

Silt fence detail has been replaced with detail C-31-0400 (Silt Fence) on sheet C08 and C-31-0433 (Stabilized Outlet For Silt Fence) on sheet C09. Follow post spacing as shown on details. Filter fabric should be wired to posts. Email lsaleeby@hazenandsawyer.com to request Addendum 1 drawings.

Changes to Project Manual

Email lsaleeby@hazenandsawyer.com to request Addendum 1 Specifications.

1. 00 11 00 – Advertisement for Bids

Page 1: Sealed bids will be opened in **Room 107** at City Hall.

2. 00 20 00 – Instruction to Bidders

Article 7.1: **No pre-bid conference will be held. Any questions should be directed to lsaleby@hazenandsawyer.com with bids@havelocknc.us copied as a recipient.**

3. 00 40 00 – Bid Form

Article 2.1: This bid will remain subject to acceptance for **60** days after the Bid opening, or for such longer period of time that Bidder may agree to in writing upon request of Owner.

4. 01 55 26 – Traffic Control

Part 1.1.A: The Contractor shall follow the construction procedure and maintenance of traffic as shown on **Drawing Numbers C01 & C13** unless an alternative plan is agreed to by the Engineer prior to or during the prosecution of work.

5. 31 13 20 – Wood for Streamwork

Remove section.

6. 31 37 20 – Stone for Streamwork

Section added.

7. 31 52 00 – Stream Diversion and Cofferdams

Part 1.04 A: All work required for construction and maintenance of temporary stream diversions and cofferdams shall be included in the Contractor's lump sum price, **Pay Item SP-6, Water Handling**.

8. 33 41 13 – Foundation Drainage Systems

Remove section.

9. 40 05 51 – Valves, General

Parts 1.03, 2.05, 2.06, 2.07: Parts were removed.

10. 40 05 57 – Valve Operators and Electric Valve Actuators

Parts 2.01, 2.02, 2.03, 3.01, 3.03, 3.04: Portions or entirety of parts were removed.

11. 40 05 63 – Ball Valves

Remove section.