

City of Havelock
Webb Blvd and Hwy 70 Water Line Leak Repair
Addendum 1
July 12, 2017


On page 5 under Location, delete in entirety and insert item #4 with the following:

Scope of repairs include replacing existing 8" x 8" x 6" tee and existing 8" valve with a straight run of pipe and new 8" gate valve using C900 with two (2) 8" mechanical joint ductile iron sleeves and appropriate grip rings to convert from SDR 21 to C900 on either side of the sleeves. Existing suspected 6" inch gate valve and suspected 6" pipe stub out may be abandoned in place after proper capping of the open ends.

Please insert attachment 1 and 2 after page 6 in Bid Packet.

Thank you for your continued interest in our project.

CITY OF HAVELOCK



Lee W. Tillman

Finance Director