



January 11, 2019

Addendum No. 1

Project Name: 18-42001-003 Glenwood Springs Road over Little River (Bridge Repair)

The following change has been made to the overall completion for the contract:

Contract Time for the overall project duration had been changed from 120 Calendar days to a Completion Date of August 31, 2019.

For contractors' information:

Q: Is it the engineer's intent to encase all of the piles in bent 5, except for pile #4, after the type II backfill has been placed to correct the stream bank erosion?

R: *The intent is to encase all piles except for pile #4 after the backfill has been placed to correct the stream bank erosion.*

Q: Per Section 547, pile encasements are paid per linear foot, to include concrete and reinforcing steel. Is the intent for the pile encasements to be paid for under the "Class A Concrete" pay item?

R: *The intent is to include all quantities for pile encasement under "Class A Concrete" and "Bar Reinf Steel" because the pile encasements are a special configuration.*

Q: Is it the county's intent for the bidder to include all work related to correcting the cap risers, other than the structural steel items, in the bid item "Raise Existing Bridge, STA 424+62"?:

R: *Quantities for correcting the cap risers (except for structural steel items) are included in "Class A Concrete" and "Bar Reinf Steel"*

Bidder must acknowledge receipt on Page I-4 of the bidding documents.

FAILURE TO ACKNOWLEDGE THE ADDENDUM MAY RESULT IN REJECTION OF YOUR BID.

RECEIPT OF BIDS REMAINS UNCHANGED: 10:00 AM LOCAL TIME, THURSDAY, JANUARY 17, 2019