

**ADDENDUM NO. 2**

DATE: August 2, 2018  
TO: All Bidders  
FROM: Boyce H. Evans, Purchasing Agent  
SUBJECT: Addendum No. 2 – Gleason Drive Sidewalk Project  
BIDS TO BE OPENED: August 8, 2018, at 11:00 a.m. (Eastern)

*One for Bids*

This addendum is being published to respond to questions asked by potential bidders regarding the Gleason Drive Sidewalk Project. This addendum becomes a part of the Contract Document and modifies the original specifications as noted.

**Question 1:** Item 20.14 18" R.C.P. - Can this item be moved to be located under sidewalks? Due to the cut elevation for flow line it would be much safer to have it relocated, because lane width is 8 1/2 ft or less

Response: No, the proposed 18" R.C.P. was designed to avoid conflicts with the KUB gas line that is located underneath the back of the sidewalk. There should be approximately 10' of travel lane between the centerline and the lip of gutter as shown in the plans.

**Question 2:** Item 20.14 18" R.C.P. - Can the flow line elevation be raised?

Response: No, the depth of the 18" R.C.P. is designed to provide the proper amount of cover due to the vertical curve in the roadway.

**Question 3:** Should the ditch be shaped flat bottom the whole length of the project with liner and rip rap?

Response: Plan Sheet 4 includes two details that show the proposed geometries and stations of the ditch that is impacted by this project. Any disturbed areas shall be covered with topsoil and seed.

**END OF ADDENDUM NO. 2**