

**ADDENDUM FOUR  
PARK ADA IMPROVEMENTS  
CONTRACT NO. R-15-021-201  
CITY OF CHATTANOOGA, TENNESSEE**

The following changes shall be made to the Contract Documents, Specifications, and Drawings:

**I. Contract Documents**

Replace Bid Schedule pages 301-3A2 through 301-5A2 with new pages 301-3A4 through 301-5A4. Bid item 3-05B, Vertical Wall Curb, is added to the bid schedule.

**II. Questions**

Question: There is no line item for the curb wall on drawing C 10.2 and has a detail on drawing C 0.2. Can we have a line item for curb?

Answer: A bid item for Vertical Curb Wall is added to the new bid item list mentioned above.

Question: Where is the detail 2452-7B special signage? I have looked through the bid book as well as the drawings?

Answer: Bid item 2452-7B Special Signage refers to the special sign detail shown on sheet C10.1 (left side of sheet). Sign should be green background with white lettering, installed 7' above pavement with standard sign T-post.

March 22, 2019

---

/s/ Justin C. Holland, Administrator  
City of Chattanooga  
Department of Public Works

**BID SCHEDULE**  
**PARK ADA IMPROVEMENTS**  
**Project No. R-15-021-201**  
**City of Chattanooga, Tennessee**

Item No.	Description	Unit	Quantity	Unit Price	Total
<b>Group-A</b>					
1-01A	Common Excavation and Embankment including compaction (complete-in-place)	LS	1		
1-02A	Overexcavation of unsuitable areas as directed by the engineer	CY	7		
1-03A	Backfill and Compact overexcavated areas with mineral aggregate base (TDOT 303-01)	CY	7		
3-01A	Concrete Sidewalk and ADA ramps - contiguous areas 200 SF or more - Type-A, includes 4" concrete depth and 2' bedding stone depth. (complete-in-place)	SF	2345		
3-02A	Concrete Sidewalk and ADA ramps - isolated areas less than 200 SF - Type-A, includes 4" concrete depth and 2' bedding stone depth. (complete-in-place)	SF	5600		
15-01A	Demolition of existing sidewalk and handicap ramps as shown on plans or directed by the engineer. Includes sawcutting as required.	SF	7230		
15-02A	Demolition of other incidentals as required to complete the project, including curb, handrails, sawcutting etc.	LS	1		
33-01A	Adjust manhole frames and covers	EA	1		
35-01A	Topsoil, Seeding and Mulching (3" min. topsoil depth) (complete-in-place including any additional areas disturbed by construction activities)	LS	1		
35-02A	Sod, only as directed by the engineer (match adjacent species and variety)	SF	1000		
74-01A	Handrail assembly, ADA compliant, measured along top rail. Submittal required	LF	22		
98-01A	Erosion Control (complete-in-place)	LS	1		
717-1A	Mobilization, including bid bond, performance bond, payment bond, all applicable permits, etc.	LS	1		
2452-1A	Pavement Marking - standard parking space, paint	EA	2		
2452-2A	Pavement Marking - ADA parking space, paint	EA	4		
2452-3A	Pavement Marking - Hatch areas, ADA and other, paint	SF	880		
2452-4A	ADA Parking Sign - supply and install new sign and T-post	EA	4		
2452-5A	ADA Van Placard - supply and install new placard	EA	4		
2452-6A	ADA Parking Sign - adjust height of existing sign	EA	1		
<b>Group-A Subtotal</b>					

**BID SCHEDULE**  
**PARK ADA IMPROVEMENTS**  
**Project No. R-15-021-201**  
**City of Chattanooga, Tennessee**

Item No.	Description	Unit	Quantity	Unit Price	Total
Group-B					
1-01B	Common Excavation and Embankment including compaction (complete-in-place)	LS	1		
1-02B	Overexcavation of unsuitable areas as directed by the engineer	CY	7		
1-03B	Backfill and Compact overexcavated areas with mineral aggregate base (TDOT 303-01)	CY	7		
3-01B	Concrete Sidewalk and ADA ramps - contiguous areas 200 SF or more - Type-A, includes 4" concrete depth and 2' bedding stone depth. (complete-in-place)	SF	4050		
3-02B	Concrete Sidewalk and ADA ramps - isolated areas less than 200 SF - Type-A, includes 4" concrete depth and 2' bedding stone depth. (complete-in-place)	SF	2485		
3-03B	Concrete Driveway Apron, includes 6" concrete depth rebar and 2' bedding stone depth. (complete-in-place per City Std.)	SF	300		
3-05B	Vertical Wall Curb - Per Detail 4, Sheet C0.2, Type-A Concrete, #4 Rebar (complete-in-place)	LF	22		
12-01B	Asphalt Surface Grading E (1.5" depth (min.) in <u>slope adjustment areas</u> ) include cost of tack coat at 0.5 gal/SY	Ton	175		
12-02B	Asphalt Surface Grading E (1.5" depth in <u>new paved areas</u> ) include cost of tack coat at 0.5 gal/SY	SF	2010		
12-03B	Asphalt Binder Grading B-Mod (2.5" depth) include cost of prime coat at 0.35 gal/SY	SF	2010		
14-01B	Mineral Aggregate Base (6" depth) Type-A Grading-D, TDOT 303-01	SF	2010		
15-01B	Demolition of existing sidewalk and handicap ramps as shown on plans or directed by the engineer. Includes sawcutting as required.	SF	3900		
15-02B	Demolition of other incidentals as required to complete the project, including curb, handrails, sawcutting etc.	LS	1		
33-01B	Adjust manhole frames and covers	EA	1		
35-01B	Topsoil, Seeding and Mulching (3" min. topsoil depth) (complete-in-place including any additional areas disturbed by construction activities)	LS	1		
35-02B	Sod, only as directed by the engineer (match adjacent species and variety)	SF	500		
74-01B	Handrail assembly, ADA compliant, measured along top rail. Submittal required	LF	160		

**BID SCHEDULE**  
**PARK ADA IMPROVEMENTS**  
**Project No. R-15-021-201**  
**City of Chattanooga, Tennessee**

Item No.	Description	Unit	Quantity	Unit Price	Total
75-01B	Milling of asphalt pavement 1.5" Depth (max) including butt-joints	SF	5125		
98-01B	Erosion Control (complete-in-place)	LS	1		
717-1B	Mobilization, including bid bond, performance bond, payment bond, all applicable permits, etc.	LS	1		
2452-1B	Pavement Marking - standard parking space, paint	EA	11		
2452-2B	Pavement Marking - ADA parking space, paint	EA	16		
2452-3B	Pavement Marking - Hatch areas, ADA and other, paint	SF	2096		
2452-4B	ADA Parking Sign - supply and install new sign and T-post	EA	7		
2452-5B	ADA Van Placard - supply and install new placard	EA	6		
2452-6B	ADA Parking Sign - adjust height of existing sign	EA	1		
2452-7B	Special Signage	SF	3		
<b>Group-B Subtotal</b>					
<b>Total Base Bid</b>					

<b><u>ADD / DEDUCT ALTERNATES</u></b>					
3-04C	Concrete Sidewalk and ADA ramps outside the contract area, but same park only - Type-A, includes 4" concrete depth and 2' bedding stone depth. (complete-in-place)	SF	520		
15-01C	Demolition of existing sidewalk and handicap ramps outside the contract area, but same park only. Includes sawcutting as required.	SF	520		
74-02C	Handrail modification to bring handrails at John A Patton Park into compliance. (Lower height, and add 4" wheel stop at bottom, both ramps and stairs).	LS	1		