

ITB #2020-007 TSPLOST Asphalt Leveling and Resurfacing Various County Roads QUESTIONS & ANSWERS CLARIFICATION ON SPECIFICATIONS ADDENDUM 1

Return to: Lumpkin County Board of Commissioners

Ryan McDuffie, Purchasing Agent

99 Courthouse Hill, Suite D Dahlonega, GA 30533

Bid Closing Date: January 19, 2021 at 2:30 PM, EST

Bid Issue Date: December 16, 2020

Addendum Issue Date: January 12, 2021 at 5:00 PM, EST

Pages: 4

By: Ryan McDuffie, Purchasing Agent

| Vendor Name: | |
|---------------------|--|
| | |

(A copy must be attached to the Addenda Acknowledgement)

QUESTIONS

- 1. Can the County tell us what the allowable work hours will be on this project?
 - a. Daylight to dark is preferred.
- 2. Does the County intend to use 9.5MM TP1 for the leveling as in prior years?
 - a. No. Type of material to be used will be determined by the engineer.
- 3. Will the County allow the contractor to use portable advance warning signs on tripods or will the County require the use of post mounted signs?
 - a. Tripod signs are allowed.
- 4. Will the County require the contractor to pave back to the radius points at side roads and driveways or are we to pave straight through them?
 - a. Pave drives with a lip but some side roads will need to be paved back to the radius.
- 5. Will the 19MM be used for patching?
 - a. Yes, on Red Oak Flats Road.
- 6. Will the contractor be allowed to pave the roads that are 16' wide in one (1) pull instead of two (2)?
 - a. Yes.
- 7. Will the contractor be required to perform any milling on any of the streets listed in the proposal?



- a. Yes, Red Oak Flats Road.
- 8. There was mention that the 19MM patching would only be on McDonald Road in the pre-bid meeting. If so, what is the depth and spread rate that the patching will be?
 - a. No patching on McDonald Road.
- 9. Will this be paid as needed or will we get paid for full amount on bid list?
 - a. Pay will be paid by unit prices and for quantity used. No lump sum payment.
- 10. Will all the patching be at least 7 feet in width?
 - a. Yes.
- 11. Was there a spread rate for the leveling for each street since it just states as needed in the bid items?
 - a. No more than 55 lbs.
- 12. There were 4 sets of warning strips on McDonald Road leading to Porter Springs Road stop sign. Will those need to be replaced in kind as there is no bid item for them?
 - a. Rumble strips are being added to the bid item sheet.
- 13. On the bid schedule you have 19MM Asphalt and on the "Description of work" it is not listed. I am assuming this is for asphalt patching, if so, can you tell me what roads get the 19MM and how much for each road?
 - a. Red Oak Flats Road and estimated at 200 tons.
- 14. Is the centerline single or double centerline?
 - a. Double yellow on center line and single line on edge lines. Lines will be paid as single lines per line mile.
- 15. Can you provide a detail and/or better description of what you expect for shoulder construction?
 - a. Shoulder width will vary on each road but the shoulder needs to be a safe shoulder that is at grade with the pavement and sloping away from the road.
- 16. When do you expect to issue the NTP?
 - a. Soon after the notice of award is given to the successful contractor. Work can begin in early spring.



| 2020 T SPLOST BID ITEM SUMMARY | | | | | | | | |
|--------------------------------|--------------------------|---------------------------|------------------------|-----------------|--|---|--|--|
| DOAD | BEGIN | END | LENGTH (Miles) | WIDTH (FEET) | DESCRIPTION OF WORK | | | |
| ROAD NAME | | | | | ASPHALT REQUIREMENTS | STRIPING REQUIREMENTS | | |
| Lady slipper lane | Holly Springs Road | Azalea Ct. | .20 | 21 | Spot level and Overlay with 175 #/sqyd of 12.5 mm | Stop Bar | | |
| Brady Edge Rd. | Cavender Creek Rd. | .60 mile | .60 | 20 | Spot level and Overlay with 175 #/sq.yd of 12.5 mm | Stop Bar | | |
| Brady Edge Road | .60 Mile | End of Pavement. | .65 | 14 | Spot level and Overlay with 175 #/sq.yd. of 12.5 mm | None | | |
| Foothills Drive | Emory Stephens Rd. | End | .30 | 20 | Spot level and Overlay with 175 #/sq.yd. of 12.5 mm | Stop Bar | | |
| Francis Smith Rd | SR 115 | End Pavement | .30 | 15 | Spot level and Overlay with 175 #/sq.yd. of 12.5 mm | | | |
| Red Oak Flats Rd | SR 60 | Animal Shelter Dr. | 1.45 | 25 | Spot level and Overlay with 175 #/sq.yd. of 12.5 mm | Centerline and Edge line Stop Bar | | |
| McDonald Rd. | SR 9 | Porter Springs Road | 2.90 | 20 | Spot level and Overlay with 175 #/sq.yd. of 12.5 mm | Centerline and Edge Line, Rumble Strips, And Stop Bars. | | |
| | | | 6.40 Miles Total | | | | | |

Rumble strips added to McDonald Road.



LUMPKIN COUNTY CONTRACT SCHEDULE

VARIOUS COUNTY ROADS CONTRACT ID: 2020-007

PROJECT: TSPLOST ITB 2020-007

| FROJECT. | 13FLO31 11B 2020-007 | | | |
|----------|--|---------------------|---------------|---------------|
| | | ESTIMATED | | |
| | ITEM | QUANTITY | UNIT PRICE | TOTAL |
| LINE NO | DESCRIPTION | AND UNITS | DOLLARS/CENTS | DOLLARS/CENTS |
| | 150-3110 Traffic | | | |
| 0005 | Control for LMIG-01 | Lump Sum | | |
| | 402 2120 Decycled Acab Cone | ' | | |
| | 402-3130 Recycled Asph. Conc. 19 MM Super Pave Gp 2 | 200 | | |
| 0010 | only incl. Bitum Matl. And H lime | Ton | | |
| 0010 | 402-1812 Recycled Asphalt Conc. | 953 | | |
| | Leveling incl Bitum Material and H | 955 | | |
| 0015 | lime | Ton | | |
| 0013 | | Ton 6677 | | |
| | 402-3130 Recycled Asph. Conc. | 00// | | |
| 0020 | 12.5 MM Super Pave Gp 2 | Ton | | |
| 0020 | only incl. Bitum Matl. And H lime | Ton | | |
| | | 6200 | | |
| 0035 | 413-1000 Bitum. Tack Coat | CAL | | |
| 0025 | 413-1000 Bitum. Tack Coat | GAL 8.90 | | |
| | | 8.90 | | |
| 0030 | 652- Solid Traffic Stripe, 5" White | LM | | |
| | | 8.90 | | |
| | | | | |
| 0035 | 652- Solid Traffic Stripe, 5" Yellow | LM | | |
| | · . | 0.5 | | |
| | | | | |
| 0040 | 652- Skip Traffic Stripe, 5" White | GLM | | |
| | | 0.5 | | |
| | | | | |
| 0045 | 652- Skip Traffic Stripe, 5" Yellow | GLM | | |
| | 216-Unpaved Shoulder Const. | 1920 | | |
| 0050 | Select Material | Ton | | |
| | | | | |
| | 429- Rumble Strips | | | |
| 0055 | (Thermoplastic) | <mark>3 each</mark> | | |
| | | | | |
| | | | | |
| | | | Total Bid | |