



Georgetown County, South Carolina

129 Screven Street, Suite 239
Post Office Drawer 421270
Georgetown, SC 29442-4200
(843) 545-3083 • Fax (843) 545-3500
E-Mail • purch@gtcounty.org
Website • <http://www.gtcounty.org>

ADDENDUM #2 TO BID #19-083

BID NUMBER: 19-083

ISSUE DATE: Tuesday, November 26, 2019

OPENING DATE: Wednesday, December 4, 2019 **OPENING TIME: 3:00 PM (ET)**

Bid Opening Location: Georgetown County Courthouse, Suite #239, (Purchasing Conference Room)

Pre-Bid Conference/Site Inspection:-CLOSED-Mandatory, Wednesday, November 20, 2019, 3:00 PM

PROCUREMENT FOR: Deloach Trail Roadway & Drainage Improvements

This addendum will amend **Bid #19-083, Deloach Trail Roadway & Drainage Improvements** originally issued on Wednesday, November 6, 2019. This clarification is being provided to all known and registered correspondents in response to questions received. All addenda and original bid documents are also available online at: www.gtcounty.org, select Quick Links, “Bid Opportunities” and “View Current Bid Solicitations.”

Question 1: Regarding Addendum 1 – Waterline Replacement: Will Georgetown County provide detailed drawings to show bidders the footprint of the 4” waterline, short and long water services, etc.?

Response: Per Addendum No. 1, the 4” waterline will be replaced in its entirety. The County will not provide a separate design drawing for the new 4” waterline. However, it will be installed approximately 3’ behind the proposed back of curb. GCWSD will be responsible for installing and transferring the water service taps.

Question 2: Is it the intent to remove or abandon the existing water main once services

have been restored?

Response: The existing 4” water main shall be abandoned in place.

Question 3: Are bidders to include new service lines, water meters and meter boxes?

Response: No. GCWSD will be responsible for installing and transferring the water service taps, meters and meter boxes as required.

Question 4: Please confirm chlorination will be paid under the Allowance.

Response: Chlorination and pressure testing should be included under the unit price for the waterline installation. However, bacteriological testing will be paid under the allowance.

Question 5: Well Pointing: Based on our experience with the high water table in the area, well pointing may be needed for installation of the storm drain system. Please confirm well pointing will be paid under Bid Item 14 - Dewatering in lieu of the Bid Items for RCP drainage.

Response: Correct Any dewatering required in the project should be shown in line item 14.

Question 6: Drawings C-2 & C-4 – Tree Removal: Approximately 51 trees are shown to be removed. Please confirm others will be responsible for the removal of the trees shown on drawing C-4.

Response: No, the successful bidder will be responsible for removal of the trees. This number should be included in Line Item 2 (Demolition).

Question 7: Drawings C-4 – Pavement Markings: Please confirm stop bars for DeLoach Trail are the only pavement markings required for the project.

Response: Stop Bars are the only Pavement Markings required. There are 2 stop bars, one on each end of DeLoach.

[THE REMAINDER OF THIS PAGE IS INTENTIONALLY LEFT BLANK]