



Project: Concrete for CTE Welding

From: The Office of the Construction Manager – GCE Construction

This Addendum forms part of the Contract Documents. It supplements and modifies them as follows:

A. Questions & Answers:

1. Have the PEMB foundation sizes been confirmed?
 - a. Install all foundations per the plans. Any potential requested or required changes to foundations per the PEMB provider, will be addressed via a RFP and potential Change Order.
2. Will a templates be provided for column Anchor bolts?
 - a. Yes.
3. Will gridlines setout be provided by others?
 - a. Any gridlines required by this scope are to be in a layout provided via submittal by the concrete contractor.
4. Is it your intention to have the asphalt subcontractor handle the concrete curbs?
 - a. Asphalt contractor will handle curbs that are outside of sidewalks. If sidewalk detail depicts a faux curb then concrete contractor is to provide that item.
5. Will WR Meadows Concrete Densifier and Hardener be approved?
 - a. Specification Section 03 30 00 CAST-IN-PLACE CONCRETE , Part 2.04 RELATED MATERIALS, ITEM K. LIQUID DENSIFIER/SEALER, provides that Liqui-Hard by W.R. Meadows is one of the approved items to be used. Take note of Item K.1, which depicts that densifiers/sealers called for in areas which are to receive a special concrete finish (i.e., staining, polishing, etc.) shall take precedence over densifiers/sealers specified herein solely for those areas to receive such finish.

B. Drawings – No revised drawings.

C. Specifications – No spec sections.