



Electric and Public Works Departments Fencing Request for Bid (RFB)

Date: April 17, 2024

ADDENDUM 2

Questions

1. Will grounding be required? If yes, can a grounding detail be provided?
NO
2. Will any surveying or staking be required?
YES, Survey work is required to verify that newly installed fence is within the City Property.
3. Will any cleaning or grading of the fence line be required?
YES. Small area behind Building B, along adjacent property line with the cemetery.
4. Can we get a layout or marked up google earth image for the proposed fence line and new gate locations?
See attached conceptual site plan.
5. Will the gates be roll gates (not recommended with gate operator) or cantilever slide gates? **The gates will be manual roll gates**
6. Will the gates need operators (nor or future use)?, if yes, how will vehicles enter – keypad, remote, etc.? **NO**
7. Will any core drilling be required? **This will be General Contractor means and methods. It is anticipated that the installation would require core drill thru the existing asphalt and then auger.**



8. Will the concrete need to be removed? **This will be General Contractor means and methods.**
9. How many barbed wire strands do you need? We recommend 3 strands.
Three (3) strands
10. Is there a point of contact on site or is there a drawing to show the outline of the fence? **See attached conceptual site plan.**
11. Are we simply replacing all of the perimeter fence at the 2520 Highmarket street location? **See attached conceptual site plan. All existing fencing shall be removed from the site and disposed of properly.**
12. Also, the bid form is only 2 pages long but it stated 1 of 3 and 2 of 3 on the bottom of the pages we downloaded and printed.
Answer: See updated Bid form
13. Is the Fence 9 gauge 13 core or 9 gauge core?
8 gauge finish and 9 gauge core. All new fencing shall be fused and bonded. The weight of the posts shall be 40 weight.
14. Electrical will need to be cut off from the fence before the demo? **NO**
15. Will the conduit attached to the wood fence be removed before the demo?
YES
16. Will there be an area to secure the materials? If not, will we be allowed to put a temporary fence to secure our materials? **General Contractor preference.**
17. Will there need to be tension wire on the bottom of the fence? **YES**