

BIBB COUNTY SCHOOL DISTRICT
PROCUREMENT OFFICE
IFB 18-28

Bid No: 18-28

Date: 01/16/18

ADDENDUM #1

RFP 18-28 – Page #5 Section 1- The original RFP states that each school will receive 4 Five Ton units which is incorrect, quantities vary between schools. The drawings indicate the correct quantities for each location. Replace the original RFP 18-28 section 1 with the revised listed below:

New Section #1:

1. GENERAL: TURNKEY INSTALLATION TO INSTALL AND WIRE FIVE-TON WALL HUNG HEAT PUMPS IN THE GYM AREA AT EACH SITE. LOCATE TO AVOID CONFLICT WITH STRUCTURAL COLUMNS. FIELD VERIFY EXACT LOCATION OF UNITS WITH OWNER, EVALUATE AND VERIFY EXISTING CONDITIONS AND ELEVATIONS WITH OWNER PRIOR TO DEMOLITION. MAX HEIGHT OF TOP OF UNIT SHALL BE 10' 0".