

Site Monitor during loading without the approval of Highlands County.

- (h) The Debris Removal Contractor shall supply all Load Tickets for the use of tracking the loads into the DDM sites. The DDM Site Management Contractor shall supply all Load Tickets for the use of tracking the final haul out of processed debris.
- (i) A Highlands County Dump Site Monitor will determine the total cubic yards of material received by visual inspection of the load. Based on predetermined truck bed measurements, Trucks with less than full capacity or partial loads will be adjusted down during this visual inspection by Highlands County or designated monitoring contractor. Truck bed measurements will not be adjusted upward. Load measurements will be documented on Load Tickets.
- (j) Debris removal Contractor shall not in any way interfere with the load assessment determination and truck certification processes conducted by the debris monitoring contractor.
- (k) The Contractor shall keep a daily updated log, in each DDM site inspection tower, of all loads received, including the total volume of debris in each load.
- (l) The Contractor shall provide a copy of all daily log sheets at the end of each business day.

Section 5.06 DUMP/TIPPING FEES

- (a) Dump/tipping fees will be reimbursed at their actual cost with proper documentation, consisting of invoice and signed payment receipt from landfills other than Highlands County Solid Waste facilities. ~~Management Center located at 12700 Arbuckle Creek Road or other County approved landfills or disposal sites~~

Section 5.07 TRAFFIC CONTROL

- (a) The Contractor shall be responsible for control of pedestrian and vehicular traffic in the work area. The Contractor shall provide all flag persons, signs, equipment, and other devices necessary to meet federal, state, and local requirements. The traffic control personnel and equipment shall be in addition to the personnel and equipment required in other parts of this contract. At a minimum, one flag person shall be posted at each entrance to the work area to direct traffic.
- (b) The Contractor shall be responsible for traffic control during operations performed by the Contractor's personnel and/or subcontractors. Traffic control shall be in conformance with the Federal Highway Administration, Manual on Uniform Traffic Control Devices, latest edition and the Florida Department of Transportation Roadway and Traffic Design Standards, latest edition.
- (c) The Contractor must be qualified and provide Highlands County with copies of certifications to conduct traffic control operations on roads in Highlands County.
- (d) The foregoing requirements are to be considered as minimum and the Contractor's compliance shall in no way relieve the Contractor of final responsibility for providing adequate traffic control devices and methods for the protection of the public and employees throughout the work areas.

Section 5.08 DEBRIS MANAGEMENT PLAN