



BID ADDENDUM #2

BID 16-022

PROJECT / BID NUMBER: 16-022

PROJECT NAME: Emergency Generators

ADDENDUM NO: 2

ISSUE DATE: 4/18/16

TO ALL BIDDERS: This addendum is issued for the purposes of modifying the original Bid, through addition, deletion, clarification or correction as outlined herein. The information provided in this addendum supersedes any information previously provided in the referenced document(s). This addendum and the information contained herein shall be used in the preparation of any bid submitted by the Bidder and shall become an integral part of the contract documents for any contract awarded for the project specified. Please inform all concerned that the Request is modified by this Addendum.

ADD/CHANGE/DELETE:

CHANGE/REPLACE: Item 1.2 (page 5):

1. **Change** ALL references that specify the deadline, due date or open date to: "Tuesday, April 26, 2016 @ 10:00AM". The location will remain the same. These references are found in the ITB document on the cover page, pages 2, 4 and 17.

QUESTIONS:

Q1. What is the proper due date?

A1. The correct due date for the ITB is Tuesday, April 26, 2016 by 10:00AM. The date was changed to allow for this addendum to be issued. **REPLACE** the date in the following places with **Tuesday, April 26, 2016 @ 10:00AM:**

- Cover;
- Submittal label
- Dates, in section 1.2, page 4;
- Submittal Deadline, page 17.

Q2. Will I, as a potential generator vendor, be responsible for the installation of the generators?

A2. No. The generator vendor will only be responsible to the point of delivery. The Project Contractor will unload and be responsible for the installation. See item #1 on the attached document.

Q3. Who is responsible for the bank tests of the generators?

A3. The Project Contractor will perform the bank tests on each of the generators once they are fully installed. See item #2 on the attached document.

Q4. Do I need to provide an automatic transfer switch?

A4. Yes. Switch shall be Caterpillar CTS Automatic Transfer Switch or approved equal as per item #3 on the attached document.

END



2300 Lake Park Drive
Suite 250
Smyrna, GA 30080
770-458-3005
Fax 770-458-8388

April 18, 2016

Electrical Addendum Information

Emergency Generator – Potato Creek WPWC Expansion from 2.0 to 3.0 MGD
W & A Project No. 14046

The following changes are to be made to Section 16231 – Emergency Generator for the above project Specifications:

1. Paragraph 16231-1.1 – A - Revise to read as follows:

The Vendor shall provide two engine driven generator sets and one automatic transfer switch that have been prototype tested, factory built, production tested and site testing as specified herein. All equipment shall be new and of current production by an international firm which manufactures the generator and controls. The Contractor shall receive, unload and install the two (2) emergency generators and the automatic transfer switch and site test all equipment as per the Specifications. The Contractor shall provide all required fluids for the generator, including a full tank of diesel fuel after acceptance of the generator and all testing is complete.

2. Paragraph 16231- 1.4 – B-6 – Revise to read as follows:

The Contractor shall provide a four (4) hour full load (100% rating of the generators) bank test of each generator and provide the Owner with written certification that the generator meets all required requirements and is 100% ready for use on this project. This test shall be performed on site once the generator and associated equipment is fully installed.

3. Add Paragraph 16231 -2.5 – I – To read:

- I. Provide automatic transfer switch as indicated on the drawings and specified herein. Switch shall be Caterpillar CTS Automatic Transfer Switch with MX250 Controller, 600 Amp, 3 Pole in NEMA Type 3R Enclosure with Ethernet Communication Adaptor or prior approved equal. Provide optional Exerciser – MEXE package on the ATS. Unit to be fully rated 25 KAIC.