

REVISED BID FORM

**ITB#20-014 CDBG#: 19DB-ON-07-38-02-N16
NEIGHBORHOOD REVITALIZATION OF THE SOUTH ORANGE STREET,
VIOLET AVENUE, GRAND AVENUE, AND NASTURTIUM AVENUE AREAS**

The undersigned declares that they have examined the complete specifications and agree to supply all equipment, labor, and supplies to complete the work required in accordance with the complete specifications. The undersigned further agrees to accept, as payment in full the price as stated in the following schedule and all work specified must be in the total amount listed below. Bid price shall be good for 120 days.

This bid should be considered a lump sum bid for the work designated. The bids are itemized for intermediate pay request purposes and in the event there are any deletions or additions to the work. Quantities shown are engineer's estimates of the work to be done. Bidders should make their own evaluation and make a note of the Bidder's quantities on the bid sheet. There are blank lines at the end, if the bidder feels additional items should be included, they should be added and included in your bid. The City of Sebring reserves the right to remove an item or items from the work for budgetary or other considerations.

ITEMIZED BID

Item	Description	QUANTITY	UNITS	UNIT COST	COST
1	MOBILIZATION	1	EA	\$	\$
2	100 PERCENT PAYMENT & PERFORMANCE BOND(S)	1	EA	\$	\$
3	CLEARING/SITE PREP NEW SIDEWALK	1	LS	\$	\$
4	MILLING AND HAUL EXISTING ROAD ASPHALT	6,301	SY	\$	\$
5	REMOVE AND REPLACE CURB TYPE 'F'	4,738	LF	\$	\$
6	REMOVE/REPLACE 4.0" D X 5.0' W SIDEWALK	4,738	LF	\$	\$
7	NEW ROAD SURFACE - 1.5" MIN	6,301	SY	\$	\$
8	REMOVE AND REPLACE CONCRETE DRIVEWAY 6"	995	SY	\$	\$
9	ADA DETECTABLE WARNING STRIPS (24" WIDE)	80	LF	\$	\$
10	WHITE THERMOPLAST ARROW & LETTERING	1	LS	\$	\$

11	6 INCH THERMOPLAST YELLOW STRIPE	420	LF	\$		\$	
12	24 INCH THERMOPLAST WHITE STRIPE	66	LF	\$		\$	
13	12 INCH THERMOPLAST WHITE (CROSSWALK)	385	LF	\$		\$	
14	TYPE 'C' INLET, TOP & GRATE	2	EA	\$		\$	
15	TYPE 'E' INLET, TOP & GRATE	4	EA	\$		\$	
16	24 INCH FRENCH DRAIN	140	LF	\$		\$	
17	24 INCH HDPE (DUAL WALL)	20	LF	\$		\$	
18	12"x18" RCP	50	LF	\$		\$	
19	FRENCH DRAIN RESTORATION	240	SY	\$		\$	
20	SOD	4,750	SY	\$		\$	
21	TESTING	1	LS	\$		\$	
22	SURVEYING	1	LS	\$		\$	
23	MOT	1	LS	\$		\$	
24	AS-BUILT PLANS & CERTIFICATION	1	LS	\$		\$	
25	INSPECTIONS & SUPERVISION	1	LS	\$		\$	
26	EROSION CONTROL	1	LS	\$		\$	
27	REMOVAL OF EXISTING FRENCH DRAINS	3	EA	\$		\$	
28	VALLEY CURB	185	LF	\$		\$	
29	Grand Avenue Lift Station Improvements (Pumps, Rails, Valves, New Raised Top, Curb)	1	LS	\$		\$	
TOTAL						\$	