

ADDENDUM NUMBER ONE  
IMPROVEMENTS, SHULER THEATER

June 21, 2019 Page 1 of 2

The Project Manual dated June 10, 2019 and the Plans dated April 22, 2019 are revised as described in this Addendum. When in conflict with other information issued prior to the date of this addendum this addendum takes precedence. All cost and schedule implications of these revisions are to be incorporated into the Bid.

**Project Manual**

Page 3

At the Project Schedule change the construction start date from ~~around July 1~~ to "around July 22".

Page 5

At the Door description add the note:

"New wood doors can instead be hollow metal doors at the contractor's option. Hollow metal doors and frames will be equal to Rocky Mountain or Southwestern. Replace existing frames and hardware if needed for new hollow metal doors."

Page 8

At the Toilet Room #2 Lavatory and Cabinet description second paragraph after the cabinet size 18"x18" add "or 24 inch x 24 inch".

Page 9

At the fluorescent lighting replacement description change ~~12 fluorescent light fixtures shown to~~ "12 fluorescent existing light fixtures shown plus 4 identical existing fixtures at the stairs and north hall". Change other references in the same paragraph from ~~12~~ fixtures to 16 fixtures.

Page 10

At the awning light bulb replacement description change ~~automotive grade electric putty~~ to "automotive grade electric putty or similar oxide inhibitor".

Page 11

At the first line of text on this page change the heading ~~below stage~~ to "outside of the stage area" since pages 10 and 11 apply to the areas not shown on the floor plan.

Page 12

Add the following paragraph about work at the Poster Display frames:

"At the two poster display frames constructed of aluminum frames and glass fronts located under the entry awning and seen in the photo on the cover of the Project Manual, drill then install new round grommets manufactured with insect screens to the bottom of the existing aluminum frames to reduce the condensation that sometimes forms on the interior. Coordinate details with the architect."

**Plan**

In Toilet Room #2 change the label "~~Replace existing sink with new~~" to "Replace existing vanity base with new."

At the dashed area in the alley add the note "Existing steel loading dock to remain. No work required."

END OF ADDENDUM NO. 1