



# St. Johns River

## Water Management District

Ann B. Shortelle, Ph.D., Executive Director

---

525 Community College Parkway S.E. • Palm Bay, FL 32909 • 321-984-4940  
On the internet at [www.sjrwmd.com](http://www.sjrwmd.com).

DATE: February 16, 2018  
TO: Prospective Respondents  
FROM: Amy Lucey, Contracts Administrator  
SUBJECT: Addendum #1 to IFB 32726, Purchase Coquina or Limerock

The following clarifications/changes are provided for your information. Please make all appropriate changes to your bid / proposal documents. Note: changes are reflected with original language shown with strike-through and new language is underlined.

For clarification, the District is seeking to receive bids for FDOT Road Base material.

Statement of Work, Section III, Scope of Work, is revised as follows:

### III. SCOPE OF WORK

Contractor shall provide coquina or limerock (material), labor and equipment to load material onto District vehicles (18-20 ton dump trucks) and issue certified weight tickets at the time of loading. The material should generally meet Florida Department of Transportation Specifications for ~~stabilized~~ **FDOT** road base but does not need to be FDOT certified. However, the moisture content and the gradation schedule shall be met as defined below. The District reserves the right to inspect the material to ensure the quantity and quality meets the District's minimum requirements prior to award.

**NOTE:** The Bid due date has been extended to at 2:00 p.m., Tuesday, March 13, 2018.

Please acknowledge receipt of this Addendum on the **BID FORM** provided in the bid package.

If you have any questions, please e-mail me at [alucey@sjrwmd.com](mailto:alucey@sjrwmd.com).

---

#### GOVERNING BOARD

John A. Miklos, CHAIRMAN  
ORLANDO

Fred N. Roberts Jr., VICE CHAIRMAN  
OCALA

Chuck Drake, SECRETARY  
ORLANDO

Ron Howse, TREASURER  
COCOA

Douglas C. Bourmiquet  
VERO BEACH

Douglas Burnett  
ST. AUGUSTINE

Susan Dolan  
SANFORD

Janet Price  
FERNANDINA BEACH

**STATEMENT OF WORK  
Coquina and/or Limerock Purchase**

**I. INTRODUCTION BACKGROUND**

The flood protection system in the Upper St Johns River Basin has over 105 miles of established levees and approximately 300 miles of roads. The levees identified for present and future use require they be maintained at established elevation with a 12-18 feet wide stabilized travel surface. This stabilized travel surface has deteriorated over the years and needs to be reconstructed. The District has undertaken a five-year plan to reestablish the travel surfaces.

**II. OBJECTIVE**

The objective of this work is for vendors to supply coquina and or limerock to the District. The District anticipates purchasing 15,000-17,000 tons of coquina or limerock to refurbish travel surfaces of several levee systems in the Upper Basin including L74, L75, L77, L78 and L79.

**III. SCOPE OF WORK**

Contractor shall provide coquina or limerock (material), labor and equipment to load material onto District vehicles (18-20 ton dump trucks) and issue certified weight tickets at the time of loading. The material should generally meet Florida Department of Transportation Specifications for ~~stabilized~~ **FDOT** road base but does not need to be FDOT certified. However, the moisture content and the gradation schedule shall be met as defined below. The District reserves the right to inspect the material to ensure the quantity and quality meets the District's minimum requirements prior to award.

**IV. TASK IDENTIFICATION**

**Contractor Responsibilities**

- Provide coquina or limerock per the following minimum requirements:  
The coquina and or limerock shall not exceed 15% moisture content at the time of shipment loading.  
Loads exceeding 15% moisture content shall not be accepted.

General distribution guidelines for gradations:

SIEVE SIZE	GRADATION PERCENT PASSING
3 ½ inch	100
1 ½ inch	95-100
¾ inch	65-90
3/8 inch	40-85
No. 4	25-65
No. 10	20-50
No. 50	5-30
N0. 200	0-10

- Provide labor and equipment to load into District provided vehicles.
- Provide certified scale (weight) ticket to District representative at time of loading to verify shipment weight and quantity.