



## **ADDENDUM**

**SOLICITATION NO.:** ITB 2019-07 Terramar Park Playground Improvement

**ADDENDUM NO.** 6

**DATE:** 04/03/2019

To All Prospective Bidders:

This addendum is issued to modify the previously issued solicitation documents and/or given for informational purposes, and is hereby made a part of the solicitation documents. Please attach this addendum to the documents in your possession. ***Per the ITB, the proposer shall acknowledge receipt of any and all addenda, if any, listing the Addenda by number(s) and date(s) in their ITB documents.***

---

### **Deadline for Bids:**

N/A

### **Specification Changes/Corrections:**

Please utilize the attached newly revised bid tabulation form, Version 6, dated 04/03/2019 that updates page 49 of the bid document for only Sections: **EARTHWORK, CLEARING AND GRUBBING, EROSION CONTROL, AND SURFACE COURSES AND CONCRETE.**

### **Questions/Clarifications and Answers:**

The following question(s) (shown in italicized text) were submitted by prospective bidder(s). The City's responses are presented here (shown in bold text). The submitters' names and email addresses have been removed due to privacy requirements.

- 1. In the Addendum #4, the EPDM PIP is now 50% Black / 50% Color, and from what I can tell, the design remains the same. Is that exactly what you want bid?*

*Or, is it 100% color, with the design remaining the same?*

**The specification provided calls for 100% premium color for playground. There is no**

**fitness area so this does not apply.**

2. *On the first answer for Add #2, you told us to dispose of the Existing Playground Equipment, and on ADD #5 you're telling us to relocate it. Which one is correct?*

**The Playground equipment is to be disposed of. Please utilize the attached newly revised bid tabulation form that updates page 49 of the bid document for only Sections: EARTHWORK, CLEARING AND GRUBBING, EROSION CONTROL, AND SURFACE COURSES AND CONCRETE.**

NAME OF COMPANY: \_\_\_\_\_

# TERRAMAR PARK PLAYGROUND PROJECT

ADDENDUM NO. 6

## BID TAB REVISION

No	Description	Quantity	Unit	Estimated Cost	Sub-Total
<b>EARTHWORK</b>					
1	REGULAR EXCAVATION <span style="border: 1px solid red; padding: 2px;">(12" DEPTH)</span>	<span style="border: 1px solid red; padding: 2px;">320</span>	CY		
<b>CLEARING AND GRUBBING</b>					
1	REMOVE EXISTING HEADER CURB	665	LF		
2	REMOVE EXISTING WOOD CHIP MULCH IN BOTH AREAS AND RUBBERIZED SURFACE	8,660	SF		
3	<span style="border: 1px solid red; padding: 2px;">Dispose of</span> REMOVE EXISTING PLAY EQUIPMENT (INCLUDING FOOTERS) <del>RELOCATE PER CITY DIRECTIONS</del>	1	LS		
4	REMOVE EXISTING CONCRETE PAD (WHERE INDICATED ON PLANS)	5	SY		
<b>EROSION CONTROL</b>					
1	FURNISH & INSTALL SILT FENCE	700	LF		
<b>SURFACE COURSES AND CONCRETE</b>					
1	FURNISH & INSTALL 4" CONCRETE HEADER CURB (12" DEPTH)	540	LF		
2	FURNISH & INSTALL 6" CONCRETE HEADER CURB (12" DEPTH)	125	LF		
3	FURNISH & INSTALL 4" LIMEROCK BASE	963	SY		
4	STABILIZE EXISTING SOIL (TO 80% MAX DENSITY PER AASHTO T-99)	963	SY		



Subtotal: \$

Project Number : 18245.03

Prepared by: YMD

Checked by: BZ

04/03/2019